

AMRL-TR-78-125



## DEVELOPMENT OF NOISECHECK TECHNOLOGY FOR MEASURING AIRCRAFT NOISE EXPOSURE

*PETER E. RENTZ*

*HARRY SEIDMAN*

*BOLT BERANEK AND NEWMAN INC.*

*P.O. BOX 633*

*CANOGA PARK, CALIFORNIA 91305*

MAY 1980



19951120 078

Approved for public release; distribution unlimited.

AIR FORCE AEROSPACE MEDICAL RESEARCH LABORATORY  
AEROSPACE MEDICAL DIVISION  
AIR FORCE SYSTEMS COMMAND  
WRIGHT-PATTERSON AIR FORCE BASE 45433

## NOTICES

When US Government drawings, specifications, or other data are used for any purpose other than a definitely related Government procurement operation, the Government thereby incurs no responsibility nor any obligation whatsoever, and the fact that the Government may have formulated, furnished, or in any way supplied the said drawings, specifications, or other data, is not to be regarded by implication or otherwise, as in any manner licensing the holder or any other person or corporation, or conveying any rights or permission to manufacture, use, or sell any patented invention that may in any way be related thereto.

Please do not request copies of this report from Aerospace Medical Research Laboratory. Additional copies may be purchased from:

National Technical Information Service  
5285 Port Royal Road  
Springfield, Virginia 22161

Federal Government agencies and their contractors registered with Defense Documentation Center should direct requests for copies of this report to:

Defense Documentation Center  
Cameron Station  
Alexandria, Virginia 22314

## TECHNICAL REVIEW AND APPROVAL

AMRL-TR-78-125

This report has been reviewed by the Information Office (OI) and is releasable to the National Technical Information Service (NTIS). At NTIS, it will be available to the general public, including foreign nations.

This technical report has been reviewed and is approved for publication.

**FOR THE COMMANDER**



**HENNING E. VON GIERKE**

Director

Biodynamics and Bioengineering Division  
Aerospace Medical Research Laboratory

| REPORT DOCUMENTATION PAGE  |                       | READ INSTRUCTIONS<br>BEFORE COMPLETING FORM  |
|--|-----------------------|--|
| 1. REPORT NUMBER<br>AMRL-TR-78-125   | 2. GOVT ACCESSION NO. | 3. RECIPIENT'S CATALOG NUMBER  |
| 4. TITLE (and Subtitle)<br>DEVELOPMENT OF NOISECHECK TECHNOLOGY FOR<br>MEASURING AIRCRAFT NOISE EXPOSURE   |                       | 5. TYPE OF REPORT & PERIOD COVERED<br>Final  |
|  |                       | 6. PERFORMING ORG. REPORT NUMBER<br>BBN Report 3862                                    |
| 7. AUTHOR(s)<br>Peter E. Rentz<br>Harry Seidman  |                       | 8. CONTRACT OR GRANT NUMBER(s)<br>F33615-77-C-0514                                     |
| 9. PERFORMING ORGANIZATION NAME AND ADDRESS<br>Bolt Beranek and Newman Inc.<br>P. O. Box 633<br>Canoga Park, CA. 91305   |                       | 10. PROGRAM ELEMENT, PROJECT, TASK<br>AREA & WORK UNIT NUMBERS<br>62202F<br>7231-07-02 |
| 11. CONTROLLING OFFICE NAME AND ADDRESS<br>Air Force Aerospace Medical Research Lab<br>Aerospace Medical Division<br>Wright-Patterson AFB, Ohio 45433  |                       | 12. REPORT DATE<br>May 1980  |
| 14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)  |                       | 13. NUMBER OF PAGES<br>140   |
|  |                       | 15. SECURITY CLASS. (of this report)<br>Unclassified                                   |
| 15a. DECLASSIFICATION/DOWNGRADING<br>SCHEDULE  |                       |  |
| 16. DISTRIBUTION STATEMENT (of this Report)<br>Approved for public release; distribution unlimited.  |                       |  |
| 17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)   |                       |  |
| 18. SUPPLEMENTARY NOTES  |                       |  |
| 19. KEY WORDS (Continue on reverse side if necessary and identify by block number)<br>Aircraft Noise<br>Airport Planning<br>Community Noise Exposure   |                       |  |
| 20. ABSTRACT (Continue on reverse side if necessary and identify by block number)<br>This report describes a program to develop instrumentation for use by Air Force personnel to make spot checks of the noise exposure at locations in and about air bases. These instruments combined with standardized field measurement procedures form a technology, termed NOISECHECK, which provides a means for measuring the noise environment and checking daily average noise level values (DNL's) calculated by the Air Force NOISEMAP community-aircraft noise prediction program. |                       |  |

After analysis of measurement requirements and a survey of available equipment, four prototype portable noise level monitoring systems were acquired. The principle components were an electret type microphone and a microprocessor based noise level monitor unit with alpha-numeric printout suitable for use by minimally trained personnel. The systems were utilized in a field measurement demonstration test conducted at Barksdale AFB in June 1978. In this three-week field program, aircraft noise levels and operational data were acquired and analyzed in detail to develop and evaluate NOISECHECK procedures for test planning, test conduct, and data analysis.

The data analysis included determination of yearly average DNL values by several methods of varying complexity and assessment of statistical confidence intervals for the different methods. Differences between measurements and predictions were traced to incorrect inputs to NOISEMAP describing heavy aircraft operations at Barksdale AFB.

The detailed NOISECHECK procedures are provided in a separate document.

## SUMMARY

This report describes a program to develop instrumentation for use by Air Force personnel to make spot checks of the noise exposure at locations in and about air bases. These instruments combined with standardized field measurement procedures form a technology, termed NOISECHECK, which provides a means for measuring the noise environment and checking daily average noise level values (DNL's) calculated by the Air Force NOISEMAP community-aircraft noise prediction program.

After analysis of measurement requirements and a survey of available equipment, four prototype portable noise level monitoring systems were acquired. The principle components were an electret type microphone and a microprocessor based noise level monitor unit with alpha-numeric printout suitable for use by minimally trained personnel. The systems were utilized in a field measurement demonstration test conducted at Barksdale AFB in June 1978. In this three-week field program, aircraft noise levels and operational data were acquired and analyzed in detail to develop and evaluate NOISECHECK procedures for test planning, test conduct, and data analysis.

The data analysis included determination of yearly average DNL values by several methods of varying complexity and assessment of statistical confidence intervals for the different methods. Differences between measurements and predictions were traced to incorrect inputs to NOISEMAP describing heavy aircraft operations at Barksdale AFB.

The detailed NOISECHECK procedures are provided in a separate document.

|                      |  |
|----------------------|--|
| <b>Accession For</b> |  |
| NTIS GRA&I           | <input checked="checked" type="checkbox"/> |
| DTIC TAB             | <input type="checkbox"/>                   |
| Unannounced          | <input type="checkbox"/>                   |
| Justification        |  |
| By _____             |  |
| Distribution/        |  |
| Availability Codes   |  |
| Dist                 | Avail and/or<br>Special                    |
| A-1                  |  |

## PREFACE

This research program was performed for the Aerospace Medical Research Laboratory at Wright-Patterson Air Force Base, Ohio under Project/Task 723107, Technology to Define and Assess Environmental Quality of Noise From Air Force Operations. Technical monitor for this effort was Mr. Jerry Speakman of the Biodynamics Environment Branch, Biodynamics and Bioengineering Division, Aerospace Medical Research Laboratory.

The contributions of a number of individuals, in particular Dwight Bishop, David Conant and John Mills are gratefully acknowledged.

## TABLE OF CONTENTS

|  | <u>Page</u> |
|--|-------------|
| SUMMARY . . . . .  | 1           |
| PREFACE . . . . .  | 2           |
| TABLE OF CONTENTS . . . . .  | 3           |
| INTRODUCTION. . . . .  | 6           |
| Purpose and Scope. . . . .   | 6           |
| Background . . . . .   | 7           |
| Report Organization. . . . .                                       | 7           |
| STATE-OF-THE-ART SURVEY AND EQUIPMENT SELECTION . . . . .          | 7           |
| Field Measurement Methods. . . . .                                 | 8           |
| Measurement Variability. . . . .                                   | 10          |
| Microphone Characteristics and Selection . . . . .                 | 12          |
| Preamplifiers and Accessories. . . . .                             | 16          |
| Portable Noise Level Monitor Units . . . . .                       | 16          |
| SYSTEM SAFETY PROGRAM . . . . .                                    | 29          |
| Definitions. . . . .   | 29          |
| Hazard Level Categories. . . . .                                   | 30          |
| System Safety Precedence . . . . .                                 | 30          |
| System Safety Analyses . . . . .                                   | 31          |
| Ground Handling, Storage, Servicing and<br>Transportation. . . . . | 33          |
| FIELD MEASUREMENT DEMONSTRATION . . . . .                          | 39          |
| Air Base Selection . . . . .                                       | 39          |
| Measurement Site Selection . . . . .                               | 40          |
| Data Analysis Procedures . . . . .                                 | 40          |
| Test Results, Confidence Intervals, and Critique . . . . .         | 43          |
| CONCLUSIONS AND RECOMMENDATIONS . . . . .                          | 45          |
| Instrumentation. . . . .   | 45          |
| Field Testing. . . . .   | 46          |
| Future Study Needs . . . . .                                       | 47          |
| APPENDIX - FIELD MEASUREMENTS AT BARKSDALE AFB. . . . .            | 49          |
| REFERENCES. . . . .  | 133         |

## LIST OF TABLES

|     |  | <u>Page</u> |
|-----|--|-------------|
| 1.  | FIELD MEASUREMENT PROGRAM CHARACTERISTICS SURVEY SUMMARY . . . . .   | 9           |
| 2.  | MEASUREMENTS AND STANDARD DEVIATIONS, $\pm$ dB. . . . .  | 11          |
| 3.  | COMPARISON OF MICROPHONE CHARACTERISTICS FOR NOISECHECK. . . . .   | 15          |
| 4.  | COMPARISON OF PREAMPLIFIER CHARACTERISTICS FOR NOISECHECK. . . . .   | 17          |
| 5.  | COMPARISON OF ACCESSORIES CHARACTERISTICS FOR NOISECHECK. . . . .  | 18          |
| 6.  | ATTRIBUTES OF PORTABLE NOISE LEVEL MONITOR. . . . .  | 19          |
| 7.  | GENERAL SPECIFICATIONS FOR PORTABLE NOISE LEVEL MONITORS. . . . .  | 20          |
| 8.  | SPECIFICATION PARAMETER COMPARISON FOR PORTABLE STATISTICAL NOISE LEVEL MONITOR. . . . .                             | 22          |
| 9.  | ANALYSIS OF PERSONNEL INJURY HAZARDS. . . . .  | 35          |
| 10. | ANALYSIS OF INCORRECT DATA HAZARDS. . . . .  | 36          |
| 11. | ANALYSIS OF EQUIPMENT DAMAGE HAZARDS. . . . .  | 37          |
| 12. | ANALYSIS OF EQUIPMENT LOSS HAZARDS. . . . .  | 39          |
| 13. | SUMMARY OF DATA ANALYSIS PROCEDURES FOR FIELD DEMONSTRATION TEST. . . . .  | 42          |
| 14. | BARKSDALE AFB YEARLY DNL ESTIMATES WITH REALISTIC CONFIDENCE INTERVALS BASED ON ALL SOURCES OF VARIABILITY . . . . . | 44          |

## LIST OF FIGURES

|    |   |    |
|----|---|----|
| 1. | RESPONSE OF AN ELECTRET RANDOM INCIDENCE MICROPHONE WITH A FOUR INCH DIAMETER NERF BALL WINDSCREEN. . . | 14 |
| 2. | PORTABLE NOISE LEVEL MONITOR. . . . .   | 27 |
| 3. | DESCRIPTION OF PORTABLE NOISE LEVEL MONITOR RECORD LISTINGS . . . . .                                   | 28 |

LIST OF FIGURES (CONTINUED)

|  | <u>Page</u> |
|--|-------------|
| 4. PORTABLE NOISE LEVEL MONITOR SYSTEM COMPONENTS<br>AND TYPICAL SYSTEM INSTALLATION FOR SAFETY<br>ANALYSIS. . . . . | 32          |
| 5. MONITOR SYSTEM EQUIPMENT USE FLOW CHART . . . . .   | 34          |
| 6. AIRCRAFT NOISE MEASUREMENT SITES AT BARKSDALE<br>AIR FORCE BASE WITH NOISEMAP PREDICTED CONTOURS . .              | 41          |

## INTRODUCTION

### PURPOSE AND SCOPE

The purpose of this project is to develop standardized noise measurement equipment and procedures for making spot checks of the noise exposure at ground locations in and about Air Force air bases. The equipment and procedures, termed NOISECHECK technology, is to be used by Air Force personnel to measure the noise environment and check the noise exposure values calculated by the Air Force NOISEMAP community-aircraft noise exposure prediction program.<sup>1</sup>

The scope of the project included the selection and procurement of four prototype portable noise level monitoring systems, and the development of detailed procedures for performing field measurements. The procedures involve test planning, data acquisition and use of measured data to make yearly average day-night noise level\* (DNL) estimates of predictable accuracy. The procedures are presented as a separate document.<sup>2</sup>

The project consisted of the following tasks"

- . State-of-the-Art Survey
- . Equipment Selection
- . Field Test
- . Data Analysis
- . Critique
- . Safety Study
- . Development of Measurement Procedures

---

\* Day-night noise level is defined as the A-weighted sound level averaged on a power basis over 24 hours with a plus 10 dB weighting applied between 2200 and 0700 hours.

## BACKGROUND

The USAF has recognized that its airbases and adjacent civilian communities must co-exist. In order to protect these adjacent communities from the noise and safety hazards associated with aircraft operations and preserve the operational integrity of the airfields, the USAF has developed and implemented the Air Installation Compatible Use Zone (AICUZ) concept. An AICUZ for an airfield is generated from the composite application of accident potential zones (APZs) and Noise Zones (NZs). The Noise Zones are based on predicted day/night average sound level (DNL) contours. These contours are estimated from airfield operational statistics, the noise generation characteristics of the aircraft involved, (NOISEFILE), and physical noise transmission relations embodied in NOISEMAP.

However, the contour estimates may be subject to error because of incorrect aircraft operational input data, incorrect aircraft noise data, or local acoustic phenomena not accurately represented in NOISEMAP. Often, to resolve controversy or as an aid in litigation, field measurements of a site DNL are desired.

## REPORT ORGANIZATION

Section 2 presents the results of the state-of-the-art survey and equipment selection. The results of the system safety program are presented in Section 3. Section 4 summarizes the field test measurement program which was conducted at Barksdale AFB. Conclusions and recommendations are set forth in Section 5. A detailed description of the field measurement program and the analysis of field data is presented in the Appendix.

## STATE-OF-THE-ART SURVEY AND EQUIPMENT SELECTION

Early in the program, a survey was performed to document the state-of-the-art in the measurement of aircraft generated noise levels. The survey was divided into two aspects, methodologies employed and equipment available. The methodologies survey was based on experience of measurement programs performed at both military and civilian airports. The equipment survey was based mainly on manufacturer's specification data and interviews with users.

## FIELD MEASUREMENT METHODS

Fourteen different measurement programs performed at either military or civil airports were reviewed. A summary of pertinent program characteristics is given in Table 1. In the category of information available, the types of aircraft, the yearly flight statistics, and the flight paths were known beforehand for all military airbase surveys. NOISEMAP predictions, previous site measurements, radar flight tracks, and performance profiles were available for approximately one-half of the military airbase surveys.

Again referring to Table 1, the type of aircraft operations producing the noise at the sites in question were equally divided between takeoffs and landings with some pattern flying and infrequent ground run-ups. The locations of the measurement sites were usually adjacent to the transition portions of the flight paths.

The categories of close-in, intermediate, and extended are generally related to the position of the aircraft from brake release or landing threshold. The definitions of the categories are as follows:

### Takeoff Operations

- . Close-in (0 to 2 miles from brake release)
- . Intermediate (1.5 to 4 miles from brake release)
- . Extended (3 to 10+ miles from brake release)

### Approach Operations

- . Close-in (landing roll to 1 mile from landing threshold)
- . Intermediate (1 to 4 miles from landing threshold)
- . Extended (3 to 10 miles from landing threshold)

The average number of measurement locations for the programs reviewed was ten. On the large programs, especially at Miramar NAS<sup>3</sup>, the units were moved from site-to-site so that the maximum number of units in the field at any one time never exceeded six for any programs listed.

TABLE I - FIELD MEASUREMENT PROGRAM  
CHARACTERISTICS SURVEY SUMMARY \*

| Field Measurement<br>Program Characteristic | Military          |                 |                |                 |                |                 |                 |               | Civilian       |               |              |               |             | Total<br>or<br>Avg. |         |
|---|-------------------|-----------------|----------------|-----------------|----------------|-----------------|-----------------|---------------|----------------|---------------|--------------|---------------|-------------|---------------------|---------|
|   | Barksdale AFB, 76 | England AFB, 76 | Travis AFB, 76 | Lemoore NAS, 72 | Fallon NAS, 72 | El Toro NAS, 71 | El Toro NAS, 77 | March AFB, 70 | Miramar NAS 77 | Anchorage, 72 | Stockton, 76 | San Diego, 77 | Burbank, 77 | Roanoke, 77         |         |
| Information Avail. Beforehand               |                   |                 |                |                 |                |                 |                 |               |                |               |              |               |             |                     |         |
| NOISEMAP                                    | x                 | x               | x              |                 |                |                 |                 |               | x              |               | x            |               |             |                     | 5       |
| Site Measurement                            |                   |                 |                |                 |                |                 | x               |               | x              |               |              |               |             |                     | 2       |
| Types of A/C                                | x                 | x               | x              | x               | x              | x               | x               | x             | x              | x             | x            | x             | x           | x                   | 14      |
| Yearly Flight Statistics                    | x                 | x               | x              | x               | x              | x               | x               | x             | x              |               |              | x             |             |                     | 10      |
| Flight Paths                                | x                 | x               | x              | x               | x              | x               | x               | x             | x              | x             | x            | x             | x           | x                   | 14      |
| Radar Flight Tracks                         | x                 | x               | x              |                 |                |                 | x               |               | x              | x             | x            | x             | x           | x                   | 10      |
| Alt. and Power Profiles                     | x                 | x               | x              |                 |                |                 |                 |               | x              |               |              |               | x           | x                   | 6       |
| Aircraft Operations                         |                   |                 |                |                 |                |                 |                 |               |                |               |              |               |             |                     |         |
| Ground Run-Up                               |                   |                 |                | x               |                |                 |                 |               | x              |               |              |               |             |                     | 2       |
| Takeoff-Close -In                           |                   | x               |                |                 |                |                 |                 |               | x              |               |              | x             |             |                     | 3       |
| Intermediate                                |                   | x               |                | x               | x              | x               | x               | x             | x              | x             | x            | x             | x           | x                   | 12      |
| Extended                                    |                   |                 |                |                 |                |                 |                 |               | x              |               |              |               |             |                     | 1       |
| Pattern Flying                              | x                 |                 |                | x               | x              |                 |                 | x             | x              |               |              |               |             |                     | 5       |
| Landing-Close -In                           |                   |                 | x              |                 |                |                 |                 |               | x              |               |              |               | x           |                     | 3       |
| Intermediate                                |                   |                 | x              | x               | x              | x               |                 | x             | x              | x             | x            | x             | x           | x                   | 11      |
| Extended                                    |                   |                 |                |                 |                |                 |                 |               | x              |               |              |               |             |                     | 1       |
| Accuracy, 90% Confidence, ± dB              | 1                 | 1               | 1              |                 |                |                 |                 | 2.5           |                |               |              |               |             |                     |         |
| Instrument Used                             |                   |                 |                |                 |                |                 |                 |               |                |               |              |               |             |                     |         |
| SLM   | x                 | x               | x              |                 |                | x               |                 | x             | x              |               |              |               |             |                     | 6       |
| White box (BBN 704)                         | x                 | x               | x              | x               | x              |                 | x               |               | x              | x             | x            | x             | x           | x                   | 12      |
| Silver box (BBN 614)                        |                   |                 |                |                 |                |                 | x               |               | x              |               | x            | x             | x           | x                   | 6       |
| How many sites                              | 3                 | 3               | 4              | 12              | 6              | 5               | 7               | 4             | 46             | 6             | 13           | 10            | 10          | 8                   | 10 Avg. |
| Stanchions at Sites                         | 1                 | 2               | 1              | 4               | 6              | 3               | 3               | -             | 2              | 3             | 3            | 0             | 0           | 2                   | 0.3 Avg |
| Security Fences or Homes                    | 2                 | 1               | 3              | 2               | 0              | 0               | 2               | -             | 26             | 3             | 3            | 10            | 10          | 6                   | 0.4 Avg |
| Measurements SEL                            | x                 | x               | x              | <u>x</u>        | <u>x</u>       | <u>x</u>        | <u>x</u>        | <u>x</u>      | x              | <u>x</u>      | <u>x</u>     | <u>x</u>      | <u>x</u>    | <u>x</u>            | 14      |
| (Primary HNL                                | <u>x</u>          | <u>x</u>        | <u>x</u>       | x               | x              |                 | x               |               | <u>x</u>       | x             | x            | x             | x           | x                   | 12      |
| type underlined) DNL (CNEL)                 | x                 | x               | x              |                 |                |                 |                 |               |                |               |              |               | <u>x</u>    |                     | 3       |
| Duration Weeks                              | 2½                | 2½              | 2½             | 2               | 2              | 1               | 2               | 1             | 16             | 2             | 2            | 2             | 2           | 2                   | 2+      |
| Data Corrections                            |                   |                 |                |                 |                |                 |                 |               |                |               |              |               |             |                     |         |
| Number of A/C                               | x                 | x               | x              | x               | x              | x               | x               | x             | x              | x             | x            | x             | x           | x                   | 14      |
| Types of A/C                                | x                 | x               | x              |                 |                |                 |                 |               |                | x             | x            | x             | x           | x                   | 8       |
| Flight Tracks                               | x                 | x               | x              |                 |                |                 |                 |               |                |               |              |               |             |                     | 3       |
| Temp/Humidity                               |                   |                 |                |                 |                |                 |                 |               |                |               |              |               |             |                     |         |
| Site Extrapolation                          |                   |                 |                |                 |                |                 | x               |               | x              |               |              | x             | x           |                     | 4       |
| Contour Line                                |                   |                 |                | x               | x              | x               | x               | x             | x              | x             | x            | x             | x           | x                   | 11      |

\* References 3 - 14.

Protection of the portable noise level monitor systems from vandalism was a constant problem for most of the field measurement programs listed. One unit was stolen during the Miramar study<sup>3</sup>. Suitable stanchions for chaining the units to homes or fences were available approximately 30 percent and 40 percent of the time, respectively.

The average duration of the measurement programs was slightly in excess of two weeks with only one of long duration (16 weeks).

Portable noise level monitor units were employed on all but two of the field measurement programs listed in Table 1. The measurements performed on-site included DNL, HNL and individual aircraft SEL. Most of the measurement programs used the measured SEL values to arrive at the desired expression of daily noise level.

With regard to data analysis, corrections were applied to all measured values for the number of aircraft. One-half of the programs separated the aircraft by types to arrive at corrections. The only field measurement programs which did not result in noise contour line verification were those performed to validate aspects of NOISEMAP<sup>4</sup>.

Confidence intervals were computed for only the program at Miramar NAS<sup>3</sup>. The +2.5 dB interval indicated is considered conservative in that instrumentation variability was added to measured HNL variability in the computation of confidence intervals. This method is conservative because some of the instrumentation variability is naturally included in the HNL variability. Generally, confidence intervals were not stated for the other 13 measurement programs either because a commonly accepted methodology for combining sources of uncertainty was not available or because there were no requirements for specifying the confidence intervals.

#### MEASUREMENT VARIABILITY

In order to plan efficient test programs a priori estimates of the inherent variability in single events and day-night levels are desired. The results from various data sources, including the Barksdale AFB field test performed as part of this program, show that the variability of single events and day-night levels is essentially independent of

distance, Table 2. This trend was verified by the Barksdale AFB test results which showed similar SEL variability for all sites. However, the magnitude of the single site variability values was much greater at Barksdale than for previous programs, even though the SEL's were segregated by type of operation as well as type of aircraft.

Note that 6 dB is the average arithmetic standard deviation of sets SEL values. Some standard deviations were as small as 1.0 dB, usually for straight in approaches of heavy aircraft.

An explanation for the large average SEL variability at Barksdale is that the aircraft are flown with greater variety of flight profiles than previously experienced. This can be attributed to the preponderance of practice flying at Barksdale. Measurement of slant distances and normalization of measured SEL values would have provided a better understanding of the sources of variability but this is not a primary purpose of a site DNL verification field test.

Fortunately, the variability of SEL's is not critical to overall measurement accuracy because their contribution to overall uncertainty decreases as the square root of the number of samples (and numerous single event samples are easily obtainable).

TABLE 2  
MEASUREMENT STANDARD DEVIATIONS,  $\pm$  dB

| Type Measurment | Aircraft  | Civilian | Type Airport |            |
|-----------------|-----------|----------|--------------|------------|
|                 |           |          | Military     | Barksdale* |
| Single Site SEL | Same      | 3.2      | 1.5          | 6          |
| Single Site SEL | Different | 3.4      | 5.3          | 12         |
| Single Site DNL | Different | 2.3      | 3.4          | 3.0        |

\* Measurements reported in the Appendix.

The DNL variability at civilian airfields was found to be less than for military airfields. The Barksdale DNL variability results matched previous experience.

#### MICROPHONE CHARACTERISTICS AND SELECTION

The important microphone characteristics were determined by combining a literature and users survey with the results of an analysis of the NOISECHECK scenarios\*. These important characteristics are as follows:

Frequency response

Directivity

Humidity resistance

Sensitivity stability

Ruggedness

Power Consumption

Accurate measurement of signals between 5000 and 10,000 Hz was considered important since some aircraft radiate significant acoustic energy about 5000 Hz.

The frequency response of a microphone depends mainly on two factors, size and damping. As the diameter of the microphone approaches an acoustic wavelength, the average pressure of a grazing wave across the diaphragm goes to zero. For this reason, only one-half inch microphones were considered for NOISECHECK since the wavelength at 10,000 Hz is only slightly greater than one inch.

Damping controls the pressure-to-deflection frequency response function for a given microphone configuration. Damping may be chosen so as to compensate for the pressure increase effects for a normal incident sound wave. Microphones with

---

\* The analysis of the NOISECHECK scenarios was part of the system safety program.

this degree of damping are called normal incidence microphones. Other microphones with less damping have flat frequency response for sound waves arriving at approximately  $60^\circ$  from normal incidence. These are referred to as "random incidence" or "pressure" type microphones.

For aircraft noise measurements, it is usually possible to point the microphone at the aircraft. Therefore, normal incidence type microphones were seriously considered. However, aircraft noise measurements are also usually performed with windscreens over the microphone. The windscreen serves to prevent wind gusts from reaching the microphone diaphragm which cause low frequency pressure fluctuations (which are not noise). The windscreen also serves to collect rain, keeping moisture from the microphone. For this second purpose, a dense, sponge-like windscreen is desirable. To satisfy this requirement, commercially available acoustic windscreens and four inch diameter Nerf balls were investigated and found to produce a high frequency roll-off which inversely matched the pressure increase effect of an incident wave giving a net flat frequency response, Figure 1. Unfortunately, the Nerf ball, and to a lesser extent, four inch diameter acoustic windscreens, exhibit a slight (1 dB) hump in the frequency response between 1,000 and 2,000 Hz. This has been hypothesized to be due to a one-quarter wave resonance in the windscreen. With the mid-frequency hump in mind, the flat pressure response type microphone along with a dense sponge-like windscreen was the combination selected for NOISECHECK.

The specification characteristics of specific microphones which are both commercially available and suitable for field measurements are presented in Table 3. Some of the microphones are known to have been used for field measurements, others are included for completeness. After eliminating one-inch microphones and  $0^\circ$  incidence microphones, the final choice was between the GEN/RAD Model 1962-9601 and the B&K Model 4166 microphones. The use of a quartz sealed diaphragm with a desiccant accessory was recommended in a National Bureau of Standards study<sup>15</sup>.

However, the long term stability and humidity resistance of the air condenser microphone was not considered as important as the ruggedness and absence of polarization voltage of the




FIGURE 1. RESPONSE OF AN ELECTRET RANDOM INCIDENCE MICROPHONE WITH A FOUR INCH DIAMETER NERF BALL WINDSCREEN

TABLE 3. COMPARISON OF MICROPHONE CHARACTERISTICS FOR NOISECHECK

| MFG         | MODEL         | TYPE (RANDOM INCID.<br>UNLESS NOTED)         | SIZE                  | CLASS | SEN*       | POL<br>VOLT | DYN**<br>RANGE | FREQ.<br>RESP. | CAPAC.<br>Pf | TEMP.<br>CAP.<br>Pf/°C | EFFECT<br>SENS.<br>dB/°C | VIB.<br>SENS,<br>dB re<br>20µN/mg |
|-------------|---------------|--|-----------------------|-------|------------|-------------|----------------|----------------|--------------|------------------------|--------------------------|-----------------------------------|
|             |               |  |                       |       |            |             |                |                |              |                        |                          |                                   |
| GEN/<br>RAD | 1962-<br>9601 | Electret                                     | 1/2                   | I     | -41        | ---         | 26-<br>145     | 5-19K          | 35           | <+0.1                  | <+0.02                   | 83                                |
| B&K         | 4149          | Air Cap, Back Vent,<br>Anti Corros(0° Incid) | 1/2                   | I     | -38        | 200         | 160            | 4-40K          | 18           | N/S                    | 0.01                     | 88                                |
| B&K         | 4165          | Air Cap, Back Vent<br>Quartz (0° Incidence)  | 1/2                   | I     | -26<br>-38 | 200<br>50   | 146            | 3-20K          | 19           | N/S                    | 0.001                    | 80                                |
| B&K         | 4134          | Air Cap Standard                             | 1/2                   | I     | -38        | 200         | 160            | 4-20K          | 18           | N/S                    | 0.01                     | 88                                |
| B&K         | 4125          | Air Cap, Dosimeter<br>(0° Incidence)         | 1/2                   |       | -40        | 28          | 146            | 7-6.3K         | 14.5         | N/S                    | -0.02                    | 85                                |
| B&K         | 4166          | Air Cap, Back Vent<br>Quartz                 | 1/2                   | I     | -26<br>-38 | 200<br>50   | 146            | 3-9K           | 20           | N/S                    | 0.001                    | 80                                |
| GEN/<br>RAD | 1971-<br>9601 | Piezoelectric                                | 1                     | II    | -40        | ---         | 22-<br>145     | 5-10K          | 385          | 2.2                    | -0.01                    | N/S                               |
| B&K         | 4117          | Piezoelectric                                | 1                     | II    | -50        | ---         | 140            | 3-10K          | 4nf          | N/S                    | -0.015                   | 120                               |
| BBN         | 379           | Hydrophone                                   | 0.63x1.5<br>+5/16x4.5 | II    | -66        | ---         | 40-<br>170     | 20-12K         | 160          | N/S                    | -0.005                   | N/S                               |

\*dB re v/Pa

\*\*dB re 20µN/m²

electret microphone. The dominant factor is that for NOISECHECK, the units will be recalibrated frequently and long term environmental effects are, therefore, not important.

#### PREAMPLIFIERS AND ACCESSORIES

Commercially available preamplifiers and accessories suitable for NOISECHECK are listed in Tables 4 and 5, respectively. The main differences between the preamplifiers are the type of microphone fitting and whether or not polarization voltage is supplied. With the selection of an electret type microphone, the standard 0.46-60 microphone fitting was required, no polarization voltage was necessary, and the GR Model 1972-9600 preamplifier was selected. The power consumption for this unit is lower than for any other preamplifier listed, which is due in part to absence of polarization voltage.

Accessories chosen were the GEN/RAD Model 1567-9701 calibrator, Nerf ball windscreens, and commonly available tripods. For shipping cases, inexpensive suitcases were lined with polyurethane foam to the shape of the noise monitors. Accessory cases were similarly lined for carrying battery, tripod, microphones, preamplifier, cable, and locking chain.

#### PORTABLE NOISE LEVEL MONITOR UNITS

Fourteen prospective vendors were contacted in order to develop a definition of the state-of-the-art in portable noise level monitoring. As a result of their replies, in-house experience and a recognition of desirable attributes for NOISECHECK summarized in Table 6, general specifications were developed. These are listed in Table 7.

As a result of the cost specification and operational analyses, only the BBN Model 614 and DAI 607P are considered acceptable. Table 8 compares the two units in detail; the major areas of difference are as follows:

TABLE 4. COMPARISON OF PREAMPLIFIER CHARACTERISTICS FOR NOISECHECK

| MFG.        | MODEL         | SIZE IN |      | FREQ. RESP.<br>(+ 1 dB)<br>— Hz. | IMPEDENCE         |        |          | CONNECTOR |         | POL<br>VOLT                     | POWER |     |
|-------------|---------------|---------|------|----------------------------------|-------------------|--------|----------|-----------|---------|---------------------------------|-------|-----|
|             |               | DIA.    | LEN. |                                  | INPUT<br>$\Omega$ | OUTPUT |          | MIC       | OUTPUT  |                                 | VOLT  | Ma  |
|             |               |         |      |                                  |                   | Pf     | $\Omega$ |           |         |                                 |       |     |
| GEN/<br>RAD | 1972-<br>9600 | 1/2-3/4 | 3.44 | 5 - 100K                         | 1G                | 3      | 20       | 6.8       | 0.46-60 | A3M*                            | 9     | 1   |
| GEN/<br>RAD | 1960-<br>P40  | 1.56    | 6.88 | 5 - 500K                         | 500<br>K          | 6      | 20       | 3.3       | A3M     | A3M                             | 20    | 1.5 |
| GEN/<br>RAD | 1960-<br>P42  | 1/2     | 6.75 | 5 - 500K                         | 2G                | 6      | 15       | 3.3       | 0.46-60 | Cable, 200<br>10'BNC            | 20    | 4   |
| B&K         | 2619          | 1/2     | 3.25 | 2 - 200K                         | 7G                | 1      | 7        |           | 0.46-60 | Cable, 200<br>2m,<br>B&K        | 28    | 0.5 |
| B&K         | 2642          | 1/2     | 2.1  | 20 - 20K                         | 1G                | 3      | 1.6<br>K |           | 0.46-60 | JP0406 Cary<br>2m thru<br>Cable | 30    |     |

\* For use with piezoelectric type microphone

\* Switchcraft

TABLE 5. COMPARISON OF ACCESSORIES CHARACTERISTICS FOR NOISECHECK

| FUNCTION            | MFG.        | MODEL     | SIZE |     |     | PERFORMANCE                 | WEIGHT<br>LB |
|---------------------|-------------|-----------|------|-----|-----|-----------------------------|--------------|
|                     |             |           | MIC  | LEN | DIA |                             |              |
| Dehumidifier        | B&K         | UA0308    | 1/2  | 2   | 1/2 | -                           | -            |
| Calibrator          | GEN/<br>RAD | 1567-9701 | 1/2  | 4.4 | 2.4 | 1000 Hz, 114 dB             | 1            |
|                     | GEN/<br>RAD | 1562-A    | 1/2  | 5   | 2.3 | 125,500,1K,2K,4K,<br>124 dB | 1            |
|                     | B&K         | 4230      | 1/2  | 4.4 | 1.6 | 1000 Hz, 94 dB              | 0.57         |
|                     | B&K         | 4220      | 1/2  | 8.7 | 1.4 | 250 Hz, 124 dB              | 1.5          |
| Windscreen          | B&K         | UA0381    | 1/2  | -   | 4   | Birdspikes                  | -            |
|                     | B&K         | UA0237    | 1/2  | -   | 4   | -                           | -            |
|                     | B&K         | UA0459    | 1/2  | -   | 2.5 | -                           | -            |
|                     | GEN/<br>RAD | 1560-9522 | 1/2  | -   | 4   | -                           | -            |
| Weatherproof System | GEN/<br>RAD | 1945-9730 | 1/2  | 12  | 3.1 | Birdspike, pre amp          | -            |
| Tripod              | BBN         | 802       | -    |     | -   | -                           | -            |
|                     | GEN/<br>RAD | 1560-9590 | -    |     | -   | -                           | -            |
|                     | B&K         | UA0049    | -    |     | -   | -                           | -            |

TABLE 6

ATTRIBUTES OF PORTABLE NOISE LEVEL MONITOR

INPUT

- . Uncomplicated command sequence designed for untrained or infrequent operator
- . Tactile feedback keyboard
- . Bright lighted digital display of command before entry

OUTPUT

- . Alpha-numeric paper tape record
- . Bright lighted digital display presenting information for all three types of commands (set, read, and print) plus error codes
- . Machine status printout

MECHANICAL

- . Balanced about carrying handle
- . Accessable, quick disconnect batteries
- . Separate microphone and accessories connectors
- . Weatherproof connectors
- . Three switches (power, weighting, response) all normally to the right

TABLE 7  
GENERAL SPECIFICATIONS FOR PORTABLE NOISE LEVEL MONITORS

|            | <u>Description</u>            | <u>Specification</u>   |
|------------|-------------------------------|------------------------|
| Mechanical | Weight with Batteries         | $\leq$ 50 lb           |
|            | Batteries                     |                        |
|            | Removable                     | Yes                    |
|            | Rechargeable                  | Desirable              |
|            | Life HNL Mode                 | 3 Days                 |
|            | SEL Mode                      | 1 day, 250 events      |
|            | Rain Proof                    | Yes                    |
|            | Power for Preamplifier        | 15-25 VdC              |
|            | (Desirable)                   | 5 Ma                   |
|            | Security Lock                 | Yes                    |
| Function   | Frequency Weighting           |                        |
|            | Linear                        | Desirable              |
|            | A                             | Yes                    |
|            | D                             | Optional               |
|            | Detection                     | True RMS               |
|            | Time Constant                 | Slow ANSI<br>S1.4-1971 |
|            | Sampling Period               | $\leq$ 0.5 sec.        |
|            | Clock Accuracy                | $\pm$ 10 sec/day       |
|            | Computations                  |                        |
|            | LEQ (Selectable time)         | Desirable              |
|            | HNL                           | Yes                    |
|            | SEL (Threshold<br>adjustable) | Yes                    |
|            | L <sub>MAX</sub> for SEL      | Yes                    |

TABLE 7 (CONT)  
GENERAL SPECIFICATIONS FOR PORTABLE NOISE LEVEL MONITORS

|        | <u>Description</u>              | <u>Specification</u>                         |
|--------|---------------------------------|--|
| Input  | Impedance                       | > 10 K $\Omega$                              |
|        | Source Impedance                | < 70 $\Omega$                                |
|        | Noise Floor "A"                 |  |
|        | Weighting with Source Impedance | - 100 dBV                                    |
|        | Dynamic Range                   |  |
|        | Automatic                       | 80 dB  |
|        | Manual                          | 100 dB                                       |
|        |                                 |  |
| Output | Integral Printer                | Yes  |
|        | Sound Level Range               | 30 - 130 dB<br>re: 20 $\mu$ N/M <sup>2</sup> |
|        | Resolution                      | $\leq$ 0.5 dB                                |
|        | Time Printed with               |  |
|        | LEQ                             | Yes  |
|        | HNL                             | Yes  |
|        | LDN                             | Yes  |
|        | SEL                             | Yes  |

Table 8 - Specification Parameter Comparison for Portable  
Statistical Noise Level Monitor

| Input<br>Parameter                                | Units      | NOISECHECK<br>Requirement | Candidate Units |                   |
|---|------------|---------------------------|-----------------|-------------------|
|   |            |                           | BBN<br>614      | DAI<br>607P       |
| Input Impedance                                   | K $\Omega$ | Greater than 10           | 121             | 60                |
| Source Impedance                                  | $\Omega$   | No more than 70           | NMT 4000        | N/S*              |
| Noise Floor, (A)<br>WTD, with Source<br>Impedance | dBV        | -100                      | -100            | $\geq -100$       |
| Dynamic Range<br>Automatic<br>Manual              | dB<br>dB   | 80<br>100                 | 100<br>N/A      | $\geq 100$<br>N/A |
| Voltage Range                                     | dBV        | -                         | -110 to<br>10   | -100 to<br>0      |
| Crest Factor                                      | dB         | -                         | 10              | 7                 |

\* N/S - Not Specified

Table 8 - Specification Parameter Comparison for Portable  
Statistical Noise Level Monitor (Continued)

| Function<br>Parameter   | Units         | NOISECHECK<br>Requirement             | Candidate Units                 |                                 |
|---|---------------|---------------------------------------|---------------------------------|---------------------------------|
|   |               |                                       | BBN<br>614                      | DAI<br>607P                     |
| Frequency<br>Weighting  | LIN<br>A<br>D | Desirable<br>Yes<br>Option            | Option<br>Yes<br>Not Yet        | Yes<br>Yes<br>Option            |
| Detection   | Type          | True rms                              | True rms                        | True rms                        |
| Time Constant   | Type          | Slow ANSI<br>SI.4-1971                | Slow                            | Slow/<br>Fast                   |
| Sampling Period   | sec           | Less than 0.5                         | 0.5                             | 0.125                           |
| Clock Accuracy  | sec           | Less than $\pm 10$<br>per day         | $< \pm 10$                      | $< \pm 10$                      |
| Computations<br>LEQ (select t)<br>HNL<br>L <sub>dn</sub><br>SENEL<br>LMAX for SENEL | -             | Desirable<br>Yes<br>Yes<br>Yes<br>Yes | Yes<br>Yes<br>Yes<br>Yes<br>Yes | Yes<br>Yes<br>Yes<br>Yes<br>Yes |

Table 8 - Specification Parameter Comparison for Portable Statistical Noise Level Monitor (Continued)

| Output Parameter                    | Units                           | NOISECHECK Requirement | Candidate Units  |           |
|-------------------------------------|---------------------------------|------------------------|------------------|-----------|
|                                     |                                 |                        | BBN 614          | DAI 607P  |
| Integral Printer Type               | -                               | Yes                    | Yes              | Yes       |
| Sound Level Range                   | -                               | -                      | Impact           | Thermal   |
| Resolution                          | dB re 20 $\mu$ N/m <sup>2</sup> | 30-130                 | 30-130 or 38-138 | 30-130    |
| Time Printed With LEQ HNL LDN SENEL | dB                              | Less than 0.5          | 0.2              | 0.1       |
| LED Display                         | -                               | Yes                    | Yes              | Yes       |
| Battery Meter                       | -                               | Yes                    | Yes              | Yes       |
| Printer Columns Characters Rows     | -                               | Yes                    | Yes              | Yes       |
|                                     | -                               | Desirable              | No               | Yes       |
|                                     | -                               | Desirable              | Yes              | Print-Out |
|                                     | no/in                           | -                      | 21               | 20        |
|                                     |                                 | -                      | 16               | 64        |
|                                     |                                 | -                      | 5                | 6         |

Table 8 - Specification Parameter Comparison for Portable Statistical Noise Level Monitor (Continued)

| Mechanical Parameter                                       | Units                            | NOISECHECK Requirement            | Candidate Units                        |                                     |
|--|----------------------------------|-----------------------------------|--|-------------------------------------|
|  |                                  |                                   | BBN                                    | DAI                                 |
|  |                                  |                                   | 614                                    | 607P                                |
| Weight Basic with Batteries Size                           | lbs<br>lbs<br>ft <sup>3</sup>    | Less than 50                      | 18<br>44<br>1.5                        | N/S<br><50<br>N/S                   |
| Batteries Removable Rechargeable Life, HNL mode SENEL mode | -<br>-<br>Days<br>Days<br>Events | Yes<br>Desirable<br>3<br>1<br>250 | Yes<br>Yes<br>7<br>>1<br>>250          | Yes<br>Yes<br>>3<br>>1<br>>250      |
| Battery A/C Power Temp. } Basic Limits } Printer           | Vdc<br>°C<br>°C                  | Desirable<br>-10 to 55<br>0 to 45 | 18<br>Option<br>-10 to 55<br>-10 to 55 | 6<br>Option<br>-10 to 55<br>0 to 45 |
| Rain Proof   |                                  | Yes                               | Yes                                    | Yes                                 |
| Preamplifier Power   | Vdc<br>ma                        | 15-25 } Desirable<br>5            | 17<br>15                               | Yes<br>Yes                          |
| Security Lock Paper Takeup                                 | Bin<br>Spool                     | Yes<br>Minimum<br>Desirable       | Yes<br>Yes<br>Option                   | Yes<br>Yes<br>Option                |

| <u>Area of Difference</u>  | <u>BBN 614</u>     | <u>DAI 607P</u>  |
|----------------------------|--------------------|--|
| Off-the-shelf availability | Standard Unit      | Modification of recently developed unit plus new printer |
| Specification requirements | Acceptable         | Acceptable   |
| Extra Functions            | Acceptable         | Acceptable   |
| Input Format               | Acceptable         | Excellent  |
| Output Format              | Slightly ambiguous | Excellent  |
| Printer readability        | Excellent          | Acceptable   |

In summary, the comparison centers on the printer. It is felt that the human factors aspects of the DAI unit are superior to the BBN unit, and that this superiority outweighs the advantages of an off-the-shelf unit.

The DAI Model 607P unit is represented in Figure 2. The front panel control labels are self explanatory. The other accessible components are identified. The lid, which is not shown, is hinged at the back and protects the operating components during unattended noise level measurements.

Typical portable noise level monitor record listings are presented as Figure 3. The header presents operator entered parameter values along with the unit serial number. Noise level measurements include SEL, HNL, LEQ, and DNL. All of the record listings consist of an alpha-numeric identification and the parameter value. Further explanation of each parameter identification is presented in Figure 3 including initial values which are pre-programmed into the unit.

The performance characteristics and operating instruction for the portable noise level monitor are presented in the companion procedures document<sup>2</sup>.





FIGURE 2. PORTABLE NOISE LEVEL MONITOR



### NOISE LEVEL MEASUREMENTS




FIGURE 3 - DESCRIPTION OF PORTABLE NOISE LEVEL MONITOR RECORD LISTINGS

The performance of portable noise level monitor units was evaluated under laboratory ambient and extreme environmental conditions. All specification parameters of Table 7 were checked (except crest factor) and were found to be in compliance. However, all units were found to exhibit a short term drift characteristic of  $\pm 0.2$  dB which is disconcerting but not critical because of the average process inherent in field measurements.

The frequency response and print quality were evaluated at  $-10^{\circ}\text{C}$  ( $14^{\circ}\text{F}$ ) and  $50^{\circ}\text{C}$  ( $122^{\circ}\text{F}$ ). The frequency response deviated less than  $\pm 1.0$  dB from 20 to 15000 Hz. No discernable change in print quality occurred as a result of the extreme temperatures.

#### SYSTEM SAFETY PROGRAM

A system safety program was planned in accordance with MIL-STD-882<sup>15</sup> and conducted in conjunction with the other tasks. As a result of the experience of the field measurements program, the system safety analysis has been updated as follows:

The purpose of the system safety program was to identify potential conditions which could cause injury to the operators of the instrumentation, or incorrect measurements, or loss of equipment, or damage to the instrumentation while setting up and making discrete spot checks of the ground locations in and about Air Force air bases and to plan preventive measures.

#### DEFINITIONS

The following definitions apply to this system safety program:

- Safety - Freedom from those conditions that can cause injury or death to personnel, damage to or loss of equipment or property, or data.
- System Safety - The optimum degree of safety within the constraints of operational effectiveness, time and cost, attained through specific application of system safety management and engineering principles throughout all phases of a system's life cycle.

- . Hazard - Any real or potential conditions such that personnel error, environment, design characteristics, procedural deficiencies, or subsystem or component failure or malfunction can cause injury or death to personnel, or damage to or loss of equipment or property.
- . Accident - Injury or death to personnel, or damage to or loss of equipment or property.

#### HAZARD LEVEL CATEGORIES

A hazard level is a qualitative measure of hazards stated in relative terms in accordance with MIL-STD-882 as follows:

##### Category I - Negligible

....will not result in personnel injury or system damage

##### Category II - Marginal

....can be counteracted or controlled without injury to personnel or major system damage

##### Category III - Critical

....will cause personnel injury or major system damage, or will require immediate corrective action for personnel or system survival

##### Category IV - Catastrophic

....will cause death or severe injury to personnel, or system loss.

#### SYSTEM SAFETY PRECEDENCE

The achievement of optimal system safety has been accomplished by a number of actions. Certain types of actions are preferable, in the following order:

Design - Protective design features for each identifiable hazard have been selected if feasible and reasonable.

Safety Devices - Safety devices have been added for known hazards which could not be reduced to an acceptable level through design selection.

Procedures - Where it is not possible to preclude the existence of an identified hazard, the operating procedures were structured to minimize the probability of occurrence.

Warning Devices - Where it is not possible to preclude or minimize the probability of occurrence of an identified hazard through design and procedures, passive warning decals are to be employed.


#### SYSTEM SAFETY ANALYSES

Three analysis techniques were employed. First, equipment use scenarios were constructed and evaluated, step-by-step, for potential hazards. Secondly, users of similar equipment listed any experience where a person was injured, equipment was damaged, or equipment was lost. Thirdly, the Barksdale AFB field test experiences with the prototype portable noise level monitor systems were compared with the preceding analyses.


In order to construct use scenarios, a baseline installation was established, Figure 4. This installation consists of the portable noise level monitor unit chained to a stanchion but with the microphone, preamplifier, and tripod unprotected.

The use of the portable noise level monitor systems will involve at least three different modes of operation.

- . Unattended operation for up to three days, measuring average hourly levels (HNL) and computing the time weighted day-night level (DNL), followed by collection of the tabulated levels and replacement of the batteries with recharged units and recalibration.
- . Unattended operation for up to 24 hours, measuring sound exposure levels (SEL), occurring at a rate up to 20 per hour, followed by a collection of the tabulated levels and replacement of the batteries with recharged units and recalibration.



SYSTEM BLOCK DIAGRAM



SYSTEM INSTALLATION

FIGURE 4. PORTABLE NOISE LEVEL MONITOR SYSTEM COMPONENTS AND TYPICAL SYSTEM INSTALLATION FOR SAFETY ANALYSIS

- . Attended operation, measuring SEL's occurring at a rate up to 20 per hour, while continuously annotating the tabulated results.

Interrogation, battery recharging, and recalibration will be by minimally trained personnel. These personnel will transfer the tabulated monitor readings to data summary forms for subsequent analysis by either data technicians or the field test director.

The transportation and use of the equipment is represented in Figure 5. In this figure, three types of places are shown; the storage area, the roads between storage and measurement location, and the measurement location.

Due to the nature and operation of the noise level monitoring systems, four types of hazards were defined as follows:

- . Personal injury
- . Incorrect data
- . Equipment damage
- . Equipment loss

Identified hazards were classified by type and are listed in Table 9 through 12, along with the hazard category, identification method, and corrective action taken.

#### GROUND HANDLING, STORAGE, SERVICING AND TRANSPORTATION

The noise level monitoring systems are intended to be portable, to be used at a variety of locations, and to be relocated daily, if necessary. Therefore, ground handling, storage, servicing, and transportation were major considerations in the design of the systems.

The noise level monitor has transportation container lined with resilient foam material to protect it from damage in normal baggage and freight handling situations.

Similarly, the fragile accessories (microphones, preamplifier, and calibrator) are transported in resilient foam material lined cases.




FIGURE 5. MONITOR SYSTEM EQUIPMENT  
USE FLOW CHART

TABLE 9  
ANALYSIS OF PERSONNEL INJURY TYPE HAZARDS

| Hazard  |          |                                       | Corrective Action                            |                |               |         |
|---|----------|---------------------------------------|--|----------------|---------------|---------|
| Description                                       | Category | Identification Method                 | Design Features                              | Safety Devices | Procedure     | Warning |
| Shorting battery with metal tool and burning self | Critical | Previous Experience                   | Terminal Covers                              | -              | -             | -       |
| Straining back while lifting unit incorrectly     | Critical | Previous Experience with larger units | Light weight balanced unit                   | -              | -             | -       |
| Falling off of building or ladders                | Critical | Scenario                              | -  | -              | Work in pairs | -       |
| Pinching fingers                                  | Marginal | Scenario                              | Avoid Sharp Edges, Make batteries accessible | -              | -             | Decal   |

TABLE 10  
ANALYSIS OF INCORRECT DATA HAZARDS

| Hazard                               |          |                               | Corrective Action             |                      |                               |         |
|--------------------------------------|----------|-------------------------------|-------------------------------|----------------------|-------------------------------|---------|
| Description                          | Category | Identification Method         | Design Features               | Safety Devices       | Procedure                     | Warning |
| Low battery charge                   | Marginal | Previous Experience Barksdale | Long Battery Life             | -                    | Check Battery Voltage         | -       |
| Incorrect instruction to monitor     | Marginal | Previous Experience           | Error codes                   | -                    | Check Status Printout         | -       |
| Incorrect time setting               | Marginal | Previous Experience           | Status Header Printout        | -                    | -                             | -       |
| Incorrect calibration                | Marginal | Previous Experience           | Status Header Printout        | -                    | -                             | -       |
| Incorrect readout of printer         | Marginal | Experience                    | Clear printer format          | -                    | -                             | -       |
| Any of above                         | Marginal | Experience                    | -                             | -                    | Use log sheet printout status | -       |
| Temperature exceeds operating limits | Marginal | Scenerios                     | -                             | -                    | Avoid extremes                | -       |
| Humidity exceeds operating limits    | Marginal | Previous Experience           | Humidity resistant microphone | Dessicant in monitor | -                             | -       |

TABLE 11  
ANALYSIS OF EQUIPMENT DAMAGE HAZARDS

| Hazard                                    |                                  |   | Corrective Action         |                            |  |                |
|---|----------------------------------|---|---------------------------|----------------------------|--|----------------|
| Description                               | Category                         | Identification Method                     | Design Features           | Safety Devices             | Procedure                                  | Warning        |
| Corrosion                                 | Marginal                         | Scenerios                                 | Similar metals            | -                          | Clean                                      | -              |
| Rain shorting microphone                  | Marginal                         | Previous Experience                       | Rain resistant microphone | -                          | -  |                |
| Bumping or dropping microphone            | Critical                         | Previous Experience                       | Rugged microphone         | Box mic-preamp-wind-screen | -  | -              |
| Stand falling or being knocked over       | Marginal                         | Previous Experience, Barksdale Field Test | Wide sturdy tripod        | Wind-screen                | -  | -              |
| Dropping monitor box                      | Marginal                         | Scenerios                                 | -                         | -                          | Remove all cables, Transport w/o batteries | -              |
| Vandalism Manual With instrument With gun | Critical<br>Critical<br>Critical | Previous Experience                       | -                         | Heavy box, chain           | select location                            | US Govt. decal |

TABLE 12

## ANALYSIS OF EQUIPMENT LOSS HAZARDS

| Hazard  |           |                       | Corrective Action |                           |                                 |                |
|---|-----------|-----------------------|-------------------|---------------------------|---------------------------------|----------------|
| Description   | Category  | Identification Method | Design Features   | Safety Devices            | Procedure                       | Warning        |
| Theft of monitor system<br>. Cut handles<br>. Extract stanchion<br>. Cut chain or lock<br>. Open case, take innards<br>. Any one of the above | Critical* | Previous Experience   | -                 | -                         | Chain Tightly                   | -              |
|   | Critical  | Previous Experience   | -                 | -                         | Use big stanchion               | -              |
|   | Critical  | Previous Experience   | -                 | Proper chain and lock     | -                               | -              |
|   | Critical  | Previous Experience   | -                 | Chain security box closed | -                               | -              |
|   | Critical  | Previous Experience   | Small unit        | -                         | Select location .safe .hidden   | US Govt. decal |
| Theft of microphone, preamplifier and/or tripod   | Critical  | Scenario              | -                 |                           | Select location . safe . hidden | -              |

\*The system is defined as four monitors, therefore the loss of one is not catastrophic.

## FIELD MEASUREMENT DEMONSTRATION

A field test was conducted at Barksdale AFB, Shreveport, Louisiana from 5 to 22 June 1978 to demonstrate the portable noise level monitor system and to develop procedures for test planning, test conduct, data analysis, and critiqueing results. Details of the field measurement program and of the field data analysis are presented in the Appendix.

### AIR BASE SELECTION

Barksdale AFB adjacent to Shreveport, Louisiana, was selected for the field measurements demonstration because of the following desirable characteristics:

- Types of missions - Both training missions and operational missions are conducted.
- Aircraft mix - Flight operations consist of both heavy aircraft (KC-135A and B-52G) and small fighter aircraft (A/T-37).
- Aircraft volume - The volume of aircraft flight operations is substantial, averaging 174 takeoffs (departures plus pattern passes) daily.
- Takeoff direction variety - The flying activity is regulated toward the southeast (Runway 14) approximately 40% of the time.
- Weather - During the scheduled field test, the temperatures, precipitation, and wind were forecast (and were, in fact) moderate.
- Political sensitivity - The NOISEMAP contours at Barksdale AFB were not under political challenge.
- Airbase cooperation - A previous measurement program (4) at Barksdale AFB had experienced willing and knowledgeable airbase cooperations.
- Documentation - NOISEMAP contours and chronicles were available.

## MEASUREMENT SITES SELECTION

Three different types of site DNL problems were selected for evaluation. The types of problems are synonymous with the location of areas in relation to the flight tracks as follows:

- . An area perpendicular to the flight track with a large DNL gradient (10 dB) and with the furthest point hypothetically in question because it is in the analytic model transition from air-to-ground and ground-to-ground propagation.
- . An area under the flight track from one to five miles from the end of the runway where the closures of the DNL contours were hypothetically in question.
- . An area under pattern flying where previous DNL measurements were hypothetically in question.

The location of the measurement sites in relation to the Barksdale AFB runway and the NOISEMAP contours are shown in Figure 6. Site 2 was used as a key site and measurements were made there during the entire field test. The conduct of the field test is described in detail in the Appendix.

## DATA ANALYSIS PROCEDURES

For the purpose of this field demonstration, analysis of the data from the Barksdale AFB field test consisted of 16 separate procedures. These procedures, the type data used, and the results of the analysis are summarized in Table 13. The procedures are organized in order of increasing complexity and improved accuracy.

Before analyzing measured data, the frequencies of aircraft operations for an average day were summarized from the NOISEMAP chronicles for Barksdale AFB. This information was required for all estimates of average day DNL values. The procedure used is listed first in Table 13.

The least complex method of estimating average day DNL values from measured data was to adjust the measured DNL values for the frequency of appropriate aircraft operations. The procedures using measured DNL values are grouped together as the second listing in Table 13.




FIGURE 6. AIRCRAFT NOISE MEASUREMENT SITES AT BARKSDALE AIR FORCE BASE WITH NOISEMAP PREDICTED CONTOURS

Table 13 - Summary of Data Analysis Procedures for Field Demonstration Test

| Data Used                                  |   | Data Analysis Procedure  | Result                      |
|--|---|--|-----------------------------|
| Field Test                                 | Other   |  |                             |
| --   | NOISEMAP Chrons                                       | <ul style="list-style-type: none"> <li>Tabulate yearly average day frequencies of appropriate operations of aircraft</li> </ul>  | Average Busy Day Operations |
| Measured DNL Values;<br>Tower Log          | Average Day Total Number of A/C Operations over Sites | <ul style="list-style-type: none"> <li>Tabulate measured HNL and DNL values from portable noise level monitor records.</li> <li>Sum appropriate flight operations from tower log.</li> <li>Compute corrections based on sums of A/C Opps.</li> <li>Apply corrections to measured (DNL) values; compute energy average and sample standard deviations.</li> <li>Compare corrected measured and NOISEMAP DNL values</li> </ul>         | Yearly Average DNL Estimate |
| Measured SEL Values;<br>Tower Log          | Average Day A/C Frequency by Type Operation           | <ul style="list-style-type: none"> <li>Correlate SELs from portable noise level monitor records with tower log events.</li> <li>Compile measured SEL values by aircraft and type operation; calculate energy average and sample standard deviation.</li> <li>Synthesize DNL values from average measured SEL values and NOISEMAP average day aircraft frequencies.</li> <li>Compare synthesized and predicted DNL values.</li> </ul> | Yearly Average DNL Estimate |
| Measured HNL Values;<br>Key Site DNL Value | --  | <ul style="list-style-type: none"> <li>Compute site-to-site energy differences using HNL values from portable noise level monitor records</li> <li>Extrapolate satellite site DNL values from key site DNL values and site-to-site energy differences.</li> <li>Compare measured and NOISEMAP DNL values.</li> </ul>   | Yearly Average DNL Estimate |
| Weather Logs                               | Yearly Temp/Humidity Values                           | <ul style="list-style-type: none"> <li>Compare atmospheric absorption during field test with NOISEMAP.</li> <li>Compare field test average temperature with NOISEMAP. Evaluate effect of differences.</li> </ul>   | Atmospheric Bias            |
| Sample Statistics                          | Student t Dist.                                       | <ul style="list-style-type: none"> <li>Compute statistical limits at the 90% level of confidence</li> </ul>  | Confidence Intervals        |

The most accurate method of estimating average day DNL values employed measured SEL values. The portable noise level monitor records were correlated with the tower log. Next, the SEL values for types of aircraft and operation were compiled and averaged.

Finally, average day DNL estimates were synthesized from the averaged SEL values and NOISEMAP average day aircraft operation frequencies. The procedures using measured SEL values are grouped together in the third listing in Table 13.

An alternate method of estimating average day DNL values consists of extrapolating from a key site to satellite sites on the basis of energy averaged HNL values. The method is usually efficient in that it requires less data analysis than synthesis from SEL values. In addition, all HNL values which are measured simultaneously at both sites may be utilized, including partial day records which do not contribute measured DNL values. The procedures using measured HNL values for extrapolation to satellite sites are grouped together in the fourth listing in Table 13.

Following the estimation of average day DNL values by one or more of the above methods, the effect of weather conditions and other bias errors was evaluated. These procedures are grouped together as the fifth listing in Table 13.

Variabilities in measured data, equipment inaccuracies, and uncorrected bias errors contribute to uncertainties in average day DNL estimates. These uncertainties were expressed in terms of statistical confidence intervals around the average day DNL estimates. The procedure for developing statistical confidence intervals is the final listing in Table 13.

#### TEST RESULTS, CONFIDENCE INTERVALS, AND CRITIQUE

The yearly average DNL values estimated from the field measurements are presented in Table 14. Three basically different analysis procedures were carried out, with resulting different confidence intervals.

The results show that the average day DNL estimates for all sites at Barksdale AFB are consistently lower than NOISEMAP predictions. In several instances, described in the Appendix,

Table 14 Barksdale AFB Yearly DNL Estimates With Realistic Confidence Intervals Based on All Sources of Variability

| Data Source                   | SITE |        |      |        |      |        |      |        |      |        |      |        |
|-------------------------------|------|--------|------|--------|------|--------|------|--------|------|--------|------|--------|
|                               | 1    |        |      | 2      |      |        | 3    |        |      | 202    |      |        |
|                               | Avg  | 90% CI | Avg  | 90% CI | Avg  | 90% CI | Avg  | 90% CI | Avg  | 90% CI | Avg  | 90% CI |
| All Days Measurements         |      |        |      |        |      |        |      |        |      |        |      |        |
| No Corrections                | -    | -      | 72.0 | +3.0   | -    | -      | -    | -      | -    | -      | -    | -      |
| Corrected for total A/C       | -    | -      | 72.7 | +2.4   | -    | -      | -    | -      | -    | -      | -    | -      |
| Corrected for heavy A/C       | -    | -      | 72.6 | +2.4   | -    | -      | -    | -      | -    | -      | -    | -      |
| Week Days Measurements        |      |        |      |        |      |        |      |        |      |        |      |        |
| No Corrections                | -    | -      | 73.5 | +2.2   | -    | -      | -    | -      | -    | -      | -    | -      |
| Corrected for total A/C       | -    | -      | 73.2 | +2.3   | -    | -      | -    | -      | -    | -      | -    | -      |
| Corrected for heavy A/C       | -    | -      | 72.4 | +2.6   | -    | -      | -    | -      | -    | -      | -    | -      |
| SEL Synthesis Measured Data   | 79.1 | +1.6   | 75.3 | +1.6   | 68.0 | +1.6   | 72.3 | +1.6   | 73.2 | +1.6   | -    | -      |
| Extrapolation from Site 2 DNL | 75.7 | +2.5   | -    | -      | 66.3 | +2.6   | 70.8 | +2.6   | 71.1 | +2.5   | 66.7 | +2.6   |
| NOISEMAP (REF)                | 80.5 | -      | 76.4 | -      | 69.4 | -      | 75.8 | -      | 73.7 | -      | 69.0 | -      |

the differences were traced through individual aircraft/operation SEL differences to incorrect NOISEMAP input data. This procedure requires accurate reconstruction of aircraft flight profiles from NOISEMAP chronicles to arrive at a close approximation of NOISEMAP SEL values.

## CONCLUSIONS AND RECOMMENDATIONS

Conclusions and recommendations are given below regarding NOISECHECK technology. These are based upon the experience gained in procuring and in utilizing the portable noise level monitor systems in the field, and in analyzing the resulting data, as described in detail in the Appendix.

## INSTRUMENTATION

Field experience with the portable noise level monitoring systems showed that all components performed reasonably well. No identifiable problems occurred with the microphones, pre-amplifiers, and accessories. No major problems were encountered with the portable noise level monitor units, although several minor problems were experienced. These were:

- . The paper supply roll jammed when the unit was installed up-side-down
- . Extraneous SEL's were recorded when the calibrator was left on
- . The unit identifies DNL's with the following day's date.

Particular advantages of the Digital Acoustics Model 607P portable noise level monitor unit over previously available units include:

- . Alpha-numeric identification of the printer output
- . Header printout of unit status
- . Paper supply and takeup for approximately eight day's operation
- . Presentation of commands on a brightly lit display before entry.

The types of microphones, preamplifiers, and accessories employed in the prototype evaluation are all recommended for future procurement for NOISECHECK. Similarly, portable noise level monitor units satisfying the attributes and detailed specifications of Tables 6 and 7 are recommended with the following additions, or modifications:

1. Items presently in NOISECHECK, Version 1.

Weight - 40 pounds

Battery Life - 5 days with 200 SEL's per day

Internal battery charger with unregulated 12 volt DC input.

2. Items for future consideration.

DNL identification corresponding to the day measured

Reactivation after calibration prohibited if calibrator is left on microphone.

## FIELD TESTING

Much of the experience gained in undertaking the field measurements are reflected in the procedures<sup>2</sup>. Therefore, extensive recommendations are not set forth in this report. However, the following recommendations are felt to be particularly pertinent.

Base cooperation is necessary for a successful field test. This cooperation can be insured by advance planning and being specific as possible about requirements. However, if the base resources don't match expectations, flexibility and replanning are recommended.

Equipment security is never totally satisfactory. The preferred methods for insuring against theft are to locate in a controlled area, preferably a private residence, and/or to properly chain the monitor unit. In the field, hypothesizing of techniques for theft and improving methods to discourage theft are recommended.

Daily recalibration of the monitor units and tabulation of the recorded values is recommended.

Analysis of the data using only measured DNL values and those corrected for aircraft volume is recommended.

The correlations between measured and predicted yearly average DNL values are obtained with measured SEL values, by aircraft, and NOISEMAP yearly average flight statistics. This method also permits tracing of the differences between measured and predicted DNL values to the aircraft and operational errors input to NOISEMAP.

It is common to find differences between the predicted and measured DNL values for the various air bases. The differences normally result from inaccurate inputs to the NOISEMAP program. These errors may result from incorrect power settings, altitude profiles, flight tracks, etc. The NOISEMAP program also assumes meteorological conditions that can bias the results by up to 1 dB.

#### FUTURE STUDY NEEDS

In the analyses of the field data undertaken in this project, a detailed analysis of data variability was made, with subsequent calculation of statistical confidence intervals. Major sources of variability were humidity and temperature differences which were identified but not corrected for because of probable inaccuracies in the evaluation of these uncertainties. Further study into evaluating the effects of temperature and humidity on the noise generation from aircraft and transmission through the atmosphere is recommended to permit more accurate average day DNL estimates from measured data.

The variability analyses performed in this project have necessarily involved a number of assumptions regarding the root sum square addition of standard deviations, and consideration of alternate methods of calculating confidence limits. It is felt that the problem of determining accurate estimates of confidence limits needs further study, particularly taking into account the development of estimates of variability considering the period of sampling with respect to yearly variability in noise exposure.

Determining aircraft volume corrections for the measured data required summarizing the flight operational statistics from the NOISEMAP chronicles. Similarly, tracing differences between measurements and predictions required reconstructing individual aircraft/mission SEL values from the DATASCREEN chronicles. The DATASCREEN chronicles at present give the aircraft code number and mission number by runway and flight track. An additional cross reference of power profiles, delta SEL and altitude profiles would be beneficial.

Other studies that would improve the accuracy of the NOISEMAP would include an investigation of the transition model from air-to-ground versus ground-to-ground propagation. Also a study of the sound duration model as a function of distance would be beneficial.

## APPENDIX

### FIELD MEASUREMENTS AT BARKSDALE AFB

The field measurements program undertaken to demonstrate the portable noise level monitor system and to develop procedures for noise test planning, test conduct, and data analysis was conducted at Barksdale AFB, Shreveport, Louisiana, from 5 to 22 June 1978. Three different types of site DNL problems were selected for evaluation. The types of problems are synonymous with the location of areas in relation to the flight tracks as follows:

1. An area perpendicular to the flight track with a large DNL gradient (10 dB) and with the furthest point hypothetically in question because it is in the analytic model transition from air-to-ground and ground-to-ground propagation.
2. An area under the flight track from one to five miles from the end of the runway where the closures of the DNL contours were hypothetically in question.
3. An area under pattern flying where previous DNL measurements were hypothetically in question.

The location of the measurement sites in relation to the Barksdale AFB runway and the day-night level (DNL) contours are shown in Figure 6 of this report. This figure was developed by tracing the DNL contours\* onto a 7.5 minute series (topographic) Geological Survey map.

### TEST CONDUCT

Upon arrival at Barksdale AFB, a coordination meeting was arranged with the base commander by the base civil engineering personnel. The activities represented were as follows:

\*The DNL contours were computed and drawn by NOISEMAP. NOISEMAP contours and chronicles were obtained from AFESC, Tyndall AFB, Florida 32403 through Hq. SAC/DEV Offutt AFB, Nebraska.

Activities Represented at Coordination Meeting

| <u>Organization</u> | <u>Activity</u>                      |
|---------------------|--------------------------------------|
| Barksdale AFB       | Base Commander                       |
| "                   | Assistant Base Commander             |
| "                   | Civil Engineering                    |
| "                   | Weather Station                      |
| "                   | Tower Operations                     |
| "                   | FAA Rapcon                           |
| "                   | Base Hospital (Environmental Health) |
| WPAFB               | AMRL/BBE                             |
| Brooks AFB          | OEHL/ECH                             |
| BBN                 | Contractor                           |

The specific measurement site selections were made after inspection of the areas. Only the pattern flying area was over air base property. Therefore, permission to install measurement systems had to be obtained from civilian property owners. The sites and methods for obtaining necessary permissions are as follows:

| <u>Type Area</u>              | <u>Site Number</u> | <u>Site Description</u> | <u>Method of Obtaining Permission</u> |
|-------------------------------|--------------------|-------------------------|---------------------------------------|
| Perpendicular to flight track | 1                  | St. Jude Church         | Telephone                             |
|                               | 2 (key)            | Freeway/Creek           | Visit Construction Supervisor         |
|                               | 3                  | Freeway/Airport School  | "                                     |
| Parallel to flight track      | 2 (key)            | Freeway/Creek           | Visit Construction Supervisor         |
|                               | 202                | Wallace Utility         | Visit Mrs. Wallace                    |
|                               | 203                | Mt. Zion Church         | Telephone Church Officials            |
| Patterns                      | 2 (key)            | Freeway/Creek           | Visit Construction Supervisor         |
|                               | 4                  | Ranger Tower            | Contact Base Ranger                   |
|                               | 5                  | FAA transmitter         | Contact Base FAA                      |

Microphone installations at four of the six measurement sites are shown in Figure A-1. The terrain at all sites was essentially flat. Trees were present around all sites, but care was taken to ensure unobstructed line of sight to the aircraft at least at the point of closest approach. The noise monitor units, which are out of the fields of view in the installation pictures, were secured against theft. At Site 202, the monitor unit was locked inside the Wallace utility building. At all other sites, a chain was passed under the handle, around the unit, and snugly locked. This prevented opening of the unit. The rest of the chain was routed around a tree or fence post and locked with a second lock. A plastic bag was then draped over the unit to shield it from rain and to make the installation less visible.

The chronology of the field test is presented in Table A-1. Three noise level monitor units were used to perform measurements at five sites. During the course of the field test, a fourth unit was installed at the sixth site. However, the fourth unit was subsequently found to have a defect causing erratic data.

During the first week, BBN, OEHL/ECH, and AMRL/BBE personnel participated actively. During the second week, BBN was assisted by base personnel. These same base personnel performed the necessary recalibration, moving, and shipping of the instrumentation during the third week.


At the request of the field measurement team, aircraft operations logs and weather logs were maintained by the Barksdale AFB tower and weather personnel, respectively.

#### DATA COLLECTION

##### NOISE LEVEL DATA

The noise levels measured by the portable noise level monitors are automatically printed on paper tape records. The printer listings are described in Figure 3 of this report.


Data records from three monitor units were edited to synchronize the SEL, HNL, and DNL listings and are presented in Figure A-2.




(a) Site 2, Looking North



(b) Site 3, Looking Across Highway To Airport School, Calibrator on Microphone.



(c) Site 203, Mt. Zion Church Looking South



(d) Site 202, Wallace Utility Building Looking East.

Figure A-1 Microphone Installations at Measurement Sites 2, 3, 202 and 203.

Table A-1  
Chronology - Barksdale AFB Field Noise Level Measurements

| <u>Day</u> | <u>(June 78)</u> | <u>Activity</u>                                  | <u>Site Number</u>  |                     |                     |                     |
|------------|------------------|--|---------------------|---------------------|---------------------|---------------------|
|            |                  |  | <u>Unit<br/>101</u> | <u>Unit<br/>102</u> | <u>Unit<br/>103</u> | <u>Unit<br/>108</u> |
| Mon        | 5                | Meeting with base CMDR<br>Surveyed sites         | -                   | -                   | -                   | -                   |
| Tues       | 6                | Selected sites, installed<br>units               | 1                   | 2                   | 3                   | -                   |
| Wed        | 7                | Found paper jam                                  | 1                   | 2                   | 3                   | -                   |
| Thurs      | 8                | Serviced units, extra SEL                        | 1                   | 2                   | 3                   | -                   |
| Fri.       | 9                | Serviced units                                   | 1                   | 2                   | 3                   | -                   |
| Sat.       | 10               | Serviced Units, Found<br>mic knocked over by cow | 1                   | 2                   | 3                   | -                   |
| Sun.       | 11               | Moved 101  | 1/202               | 2                   | 3                   | -                   |
| Mon.       | 12               | Moved 103  | 202                 | 2                   | 3/203               | -                   |
| Tue.       | 13               | Serviced Units                                   | 202                 | 2                   | 203                 | -                   |
| Wed.       | 14               | Serviced Units                                   | 202                 | 2                   | 203                 | -                   |
| Thur       | 15               | Moved 101, Reset 103,<br>Installed 108           | 202/4               | 2                   | 203                 | 5                   |
| Fri        | 16               | 108 data erratic                                 | 4                   | 2                   | 203                 | 5                   |
| Sat        | 17               | -  | 4                   | 2                   | 203                 | 5                   |
| Sun        | 18               | Serviced units                                   | 4                   | 2                   | 203                 | 5                   |
| Mon        | 19               | Serviced units                                   | 4                   | 2                   | 203                 | 5                   |
| Tues       | 20               | Tower stopped log                                | 4                   | 2                   | 203                 | 5                   |
| Wed        | 21               | 101, 108 packed up                               | -                   | 2                   | 203                 | -                   |
| Thur       | 22               | 102, 103 packed up                               | -                   | 2                   | 203                 | -                   |

|  |  |   |
|--|--|---|
| SER= 101 LOC= 1.00<br>CAL= 21.4DB DAY 7<br>THRESHOLDS:<br>SEL= 60.0DB<br>HNL/CNEL= 0.0DB<br>INTERVAL DURATION=<br>1H 0M<br>CNEL/DNL BEG 0H 0M<br>INTERVAL BEG 0H 0M<br>BATTERY VOLTAGE= 6.0<br>PRINT MODES: 1234<br>START AT 9H 30M 15 | SER= 102 LOC= 2.00<br>CAL= 20.6DB DAY 7<br>THRESHOLDS:<br>SEL= 60.0DB<br>HNL/CNEL= 0.0DB<br>INTERVAL DURATION=<br>1H 0M<br>CNEL/DNL BEG 0H 0M<br>INTERVAL BEG 0H 0M<br>BATTERY VOLTAGE= 6.0<br>PRINT MODES: 1234<br>START AT 10H 27M 235 | SER= 103 LOC= 3.00<br>CAL= 22.4DB DAY 7<br>THRESHOLDS:<br>SEL= 60.0DB<br>HNL/CNEL= 0.0DB<br>INTERVAL DURATION=<br>1H 0M<br>CNEL/DNL BEG 0H 0M<br>INTERVAL BEG 0H 0M<br>BATTERY VOLTAGE= 0.0<br>PRINT MODES: 1234<br>START AT 9H 55M 185 |
| <sup>10</sup> SEL=115.9DB B-52<br>MAX=106.5DB DAY 7<br>DURATION= 80.25 SEC<br>MAX AT 10H 32M 155   | SEL=109.0DB B-52<br>MAX= 98.6DB DAY 7<br>DURATION= 92.00 SEC<br>MAX AT 10H 32M 235   | SEL=101.7DB B-52<br>MAX= 92.4DB DAY 7<br>DURATION= 97.50 SEC<br>MAX AT 10H 32M 365  |
| SEL= 81.4DB C-130<br>MAX= 72.7DB DAY 7<br>DURATION= 22.37 SEC<br>MAX AT 10H 33M 005  | SEL= 65.3DB C-130<br>MAX= 62.2DB DAY 7<br>DURATION= 02.75 SEC<br>MAX AT 10H 39M 535  | SEL= 65.8DB C-130<br>MAX= 60.4DB DAY 7<br>DURATION= 03.50 SEC<br>MAX AT 10H 33M 425   |
| SEL= 86.2DB C-130<br>MAX= 78.1DB DAY 7<br>DURATION= 22.75 SEC<br>MAX AT 10H 49M 495  | SEL= 88.8DB C-130<br>MAX= 81.1DB DAY 7<br>DURATION= 22.75 SEC<br>MAX AT 10H 49M 565  | SEL= 79.2DB C-130<br>MAX= 68.4DB DAY 7<br>DURATION= 20.75 SEC<br>MAX AT 10H 50M 35  |
| HNL= 80.5DB HOUR 11  | HNL= 74.2DB HOUR 11  | HNL= 66.7DB HOUR 11   |
| SEL= 86.1DB C-130<br>MAX= 78.5DB DAY 7<br>DURATION= 20.02 SEC<br>MAX AT 11H 2M 505   | SEL= 87.3DB C-130<br>MAX= 78.9DB DAY 7<br>DURATION= 21.87 SEC<br>MAX AT 11H 3M 55  | SEL= 77.4DB C-130<br>MAX= 68.4DB DAY 7<br>DURATION= 21.25 SEC<br>MAX AT 11H 3M 85   |
| <sup>2</sup> SEL= 94.2DB T-39<br>MAX= 85.7DB DAY 7<br>DURATION= 36.25 SEC<br>MAX AT 11H 37M 045  | <sup>3</sup> SEL= 95.5DB T-39<br>MAX= 86.3DB DAY 7<br>DURATION= 39.50 SEC<br>MAX AT 11H 37M 275  | <sup>4</sup> SEL= 86.8DB T-39<br>MAX= 77.3DB DAY 7<br>DURATION= 39.50 SEC<br>MAX AT 11H 37M 335   |
| HNL= 58.2DB HOUR 24  | HNL= 49.2DB HOUR 24  | HNL= 54.5DB HOUR 24   |
| DNL = 77.9DB DAY 8   | DNL = 73.5DB DAY 8   | DNL = 66.1DB DAY 8  |
| CNEL= 79.7DB DAY 8   | CNEL= 74.6DB DAY 8   | CNEL= 66.8DB DAY 8  |

FIGURE A-2 - TYPICAL PORTABLE NOISE LEVEL MONITOR  
DATA RECORDS

The data records in this figure show three different types of entries--status header, SEL's, and HNL's. The status header, which is printed on operator command, must be printed to initiate computation. The time period covered immediately follows the recalibration of unit S/N 102 at location 2.

#### CALIBRATION OFFSET

During calibration, the portable noise level monitor calculates the ratio of the incoming signal voltage to an internal reference of 1.16 vrms. This ratio, expressed in dB, is called the calibration offset. Variation in the calibration offset is a measure of the drift of part of the calibrator-microphone-pre-amplifier-monitor system. The calibration offset values from the field test are presented in Table A-2. The range of the values for each unit is greater than the  $\pm 0.2$  dB observed under ambient laboratory conditions. Possible sources of variation in calibration offset under field conditions are improper seating of the calibrator on the microphone and not allowing the calibrator to stabilize for at least 30 seconds before doing the calibration.

The calibration offset value is applied to calculated levels at the time the particular noise value is printed. Therefore, if the calibration offset changes during mid-day recalibration, the previous SEL and HNL values are based on the previous calibration offset and subsequent SEL and HNL values are based on the new calibration offset. In addition, the DNL value at the end of that day is based on the mid-day calibration offset even though the energy was accumulated throughout the entire day. This computation method will cause minor differences between measured DNL values and values calculated from HNL values.

Since the calibration offset variation appeared to be random in nature, no daily corrections were applied to the measured data. Instead, the variation was considered an uncertainty which was used, along with other uncertainties, to determine statistical confidence intervals.

#### AIRCRAFT TOWER LOGS

The flight control tower maintained log of aircraft operations during the field measurement program. A typical log sheet is presented as Table A-3\*. This log sheet covers the

---

\*The tower log data sheet was redesigned after the test program. The data in Table A-3 were copied from the original to the new form.

TABLE A-2 PORTABLE NOISE MONITOR CALIBRATION OFFSET VALUE HISTORY

| Day | Date        | Unit<br>S/N<br>101 | Unit<br>S/N<br>102 | Unit<br>S/N<br>103 | Unit<br>S/N<br>108 |
|-----|-------------|--------------------|--------------------|--------------------|--------------------|
| T   | 6 June 1978 | 21.5               | 20.0               | 22.2               | -                  |
| W   | 7           | 21.4               | 20.2               | 22.4               | -                  |
| Th  | 8           | 21.6               | 20.7               | 23.0               | -                  |
| F   | 9           | 21.4               | 20.7               | 22.6               | -                  |
| S   | 10          | 21.4               | 21.5               | 22.6               | -                  |
| S   | 11          | 21.5               | 21.5               | 22.7               | -                  |
| M   | 12          | 22.2               | 20.4               | 22.6               | -                  |
| T   | 13          | 21.6               | 20.4               | 22.8               | -                  |
| W   | 14          | 21.6               | 20.7               | 23.0               | -                  |
| Th  | 15          | 21.5               | 20.6               | 22.8               | 23.9               |
| F   | 16          | 21.5               | 20.6               | 22.2               | 23.9               |
| S   | 17          | -                  | -                  | -                  | -                  |
| S   | 18          | 22.0               | 20.7               | 22.6               | 23.3               |
| M   | 19          | -                  | 20.7               | 22.6               | 24.2               |
| T   | 20          | 22.0               | 20.9               | 22.7               | 24.5               |
| W   | 21          | -                  | -                  | -                  | 24.8               |
| Th  | 22          | -                  | -                  | 22.7               | 24.8               |

TABLE A-3

AIRCRAFT TOWER LOG AND NOISE  
MONITOR DATA TABULATION FORM
 Installation BAFB  
 Date 7 JUNE '78  
 Runway(s) 14 / 32

| Aircraft Type    |       |      |      |      |      |       |       | Operation            |                   | Time |       | Noise Monitor Data |         |          |         |
|------------------|-------|------|------|------|------|-------|-------|----------------------|-------------------|------|-------|--------------------|---------|----------|---------|
| KC-135A          | B-52G | A-37 | T-37 | T-38 | T-39 | C-130 | Other | Approch <sup>*</sup> | T/O <sup>+</sup>  | GMT  | Local | Time               | SEL, dB | Dur, sec | Max, dB |
|                  |       | ✓    |      |      |      |       |       | P                    | P                 | 1358 | 0858  |                    |         |          |         |
|                  |       |      |      |      |      | ✓     |       | P                    | P                 | 1359 | 0859  |                    |         |          |         |
|                  |       | ✓    |      |      |      |       |       | P                    | P                 | 1403 | 0903  |                    |         |          |         |
|                  |       |      |      |      |      | ✓     |       | P                    | P                 | 1405 | 0905  |                    |         |          |         |
|                  |       | 2    |      |      |      |       |       |                      | SO <sup>(2)</sup> | 1408 | 0907  |                    |         |          |         |
|                  |       | ✓    |      |      |      |       |       | P                    | P                 | 1408 | 0908  |                    |         |          |         |
|                  |       | ✓    |      |      |      |       |       |                      | SO                | 1410 | 0910  |                    |         |          |         |
|                  |       |      |      |      |      |       | C-9   |                      | SO                | 1410 | 0911  |                    |         |          |         |
|                  |       | ✓    |      |      |      |       |       | P                    | P                 | 1412 | 0912  |                    |         |          |         |
|                  |       |      |      |      |      | ✓     |       | P                    | P                 | 1413 | 0913  |                    |         |          |         |
|                  |       | ✓    |      |      |      |       |       | P                    | P                 | 1418 | 0918  |                    |         |          |         |
|                  |       | ✓    |      |      |      |       |       | P                    | P                 | 1425 | 0925  |                    |         |          |         |
|                  |       |      |      |      |      | ✓     |       | P                    | P                 | 1427 | 0927  |                    |         |          |         |
|                  |       | ✓    |      |      |      |       |       | P                    | P                 | 1430 | 0930  |                    |         |          |         |
|                  |       |      |      |      |      |       | C131  | SI                   |                   | 1432 | 0932  |                    |         |          |         |
|                  |       | 2    |      |      |      |       |       | P <sup>(2)</sup>     | P <sup>(2)</sup>  | 1439 | 0939  |                    |         |          |         |
|                  |       |      |      |      |      | ✓     |       | P                    | P                 | 1441 | 0941  |                    |         |          |         |
|                  |       |      | ✓    |      |      |       |       |                      | SO                | 1443 | 0943  |                    |         |          |         |
|                  |       | ✓    |      |      |      |       |       | P                    | P                 | 1445 | 0945  |                    |         |          |         |
|                  |       | ✓    |      |      |      |       |       | P                    | P                 | 1448 | 0948  |                    |         |          |         |
|                  |       | ✓    |      |      |      |       |       | P                    | OUT               | 1450 | 0950  |                    |         |          |         |
| ← CHANGE TO 32 → |       |      |      |      |      |       |       |                      |                   |      |       |                    |         |          |         |
|                  |       | 2    |      |      |      |       |       | P <sup>(2)</sup>     | P <sup>(2)</sup>  | 1454 | 0954  |                    |         |          |         |
|                  |       |      |      |      |      | ✓     |       | P                    | P                 | 1456 | 0956  |                    |         |          |         |
|                  |       | ✓    |      |      |      |       |       | SI                   |                   | 1459 | 0959  |                    |         |          |         |
|                  |       | ✓    |      |      |      |       |       | P                    | P                 | 1502 | 1002  |                    |         |          |         |
|                  |       |      |      |      |      | ✓     |       |                      | OUT               | 1506 | 1006  |                    |         |          |         |
|                  |       | 2    |      |      |      |       |       | SI <sup>(6)</sup>    |                   | 1509 | 1009  |                    |         |          |         |
|                  |       | ✓    |      |      |      |       |       | SI                   |                   | 1513 | 1013  |                    |         |          |         |
|                  |       | ✓    |      |      |      |       |       | SI                   |                   | 1514 | 1014  |                    |         |          |         |

 \*Approach - SI - Straight In  
 P - Pattern

 +Takeoff  
 57

 SO - Straight Out  
 P - Pattern

 R - Right Turn Departure  
 L - Left Turn Departure

time from 8:58 to 10:14 on 7 June 1978. During that period of time, the runway was changed from 14 (approaches over the measurement sites) to 32 (takeoffs over the measurement sites). Note that no heavy aircraft operations (B-52 or KC-135) took place. The heavy aircraft operations usually occurred early and late in the day.

#### WEATHER LOGS

Weather logs were maintained by the base weather office. The temperature and relative humidity were tabulated every three hours for the duration of the test program. A typical weather log sheet is presented as Table A-4. This particular log sheet covers the time period from 5 June through 9 June 1978.

#### PROBLEMS ENCOUNTERED

During the course of the field measurements, various problems were encountered and mistakes were made.

- . On five occasions during the daily recalibration procedure, a monitor unit was reactivated before the calibrator was removed. This caused an extra SEL with significantly more energy than the rest of the daily aircraft operations. To rectify each of these mistakes, the affected HNL was reconstructed from SEL's, and the affected DNL was reconstructed from the corrected HNL's.
- . During the initial installation, two monitor units were tipped back over against a nearby tree. This procedure caused the paper supply reel in the thermal printer to jam. Nevertheless, much usable data were obtained because the paper take-up mechanism partially overcame the jamming. The jam became more serious, the print height became smaller, and finally no data were printed. It should be noted that on any such occasion, the values for the last SEL, HNL, and most importantly the last DNL may be read on the monitor LED display.
- . A microphone in its tripod was set on the pasture side of a fence to make it less visible. However, a number of cows visited the area, knocking over the tripod. Fortunately, no damage to the instruments was incurred. In addition, the cows were present at the time the monitor unit was inspected and the knocking over was assumed to have recently occurred, with no apparent loss of data.

| WIND         |                          | WIND      |              | WIND                        |                          | WIND      |              |
|--------------|--------------------------|-----------|--------------|-----------------------------|--------------------------|-----------|--------------|
| DATE/TIME(L) | DIR/SPEED<br>(°TRUE/KTS) | TEMP (°F) | REL HUMIDITY | WEATHER LOG<br>DATE/TIME(L) | DIR/SPEED<br>(°TRUE/KTS) | TEMP (°F) | REL HUMIDITY |
| 05/0100CDT   | CALM                     | 71        | 84%          | 07/1300CDT                  | 050/02                   | 77        | 72%          |
| 0600         | CALM                     | 69        | 90%          | 1600                        | 240/02                   | 79        | 68%          |
| 0700         | CALM                     | 67        | 90%          | 1900                        | 140/01                   | 79        | 68%          |
| 1000         | 180/06                   | 79        | 67%          | 2200                        | 170/02                   | 73        | 86%          |
| 1300         | 160/05                   | 85        | 51%          | 08/0100CDT                  | 290/03                   | 74        | 82%          |
| 1600         | 110/06                   | 86        | 49%          | 0400                        | 270/02                   | 72        | 84%          |
| 1900         | 120/03                   | 84        | 56%          | 0700                        | 280/05                   | 71        | 84%          |
| 2200         | 080/01                   | 76        | 74%          | 1000                        | 330/06                   | 77        | 64%          |
| 06/0100CDT   | CALM                     | 73        | 76%          | 1300                        | 280/06G16                | 84        | 51%          |
| 0400         | 140/02                   | 72        | 78%          | 1600                        | 330/12                   | 85        | 49%          |
| 0700         | 170/03                   | 73        | 87%          | 1900                        | 060/04                   | 81        | 60%          |
| 1000         | 190/11G17                | 84        | 67%          | 2200                        | CALM                     | 73        | 78%          |
| 1300         | 150/05                   | 76        | 82%          | 09/0100CDT                  | 340/05                   | 68        | 81%          |
| 1600         | 150/08G14                | 75        | 85%          | 0400                        | 350/04                   | 63        | 86%          |
| 1900         | 190/08                   | 77        | 79%          | 0700                        | 020/04                   | 64        | 81%          |
| 2200         | 180/07                   | 74        | 84%          | 1000                        | 040/08                   | 74        | 59%          |
| 07/0100CDT   | 150/02                   | 72        | 87%          | 1300                        | 330/09                   | 79        | 50%          |
| 0400         | 270/04                   | 72        | 76%          | 1600                        | 070/04                   | 82        | 44%          |
| 0700         | 140/05                   | 71        | 84%          | 1900                        | 030/06                   | 80        | 43%          |
| 1000         | CALM                     | 73        | 76%          | 2200                        | 090/02                   | 68        | 80%          |

MAC FORM 36c PREVIOUS EDITIONS OF THIS FORM ARE OBSOLETE

GENERAL PURPOSE WORK SHEET

☆U. S. GPO:1976-0-765-034/13

- . Tower personnel stopped keeping the aircraft operations log as originally instructed on Tuesday, June 20, while measurement program was extended until Thursday, June 22. The conduct of the test had been turned over to the base personnel the previous Thursday with mostly verbal instructions. Fortunately, the loss of information was not critical to the Barksdale AFB field test program. The event possibly could have been avoided by making explicit agreements with supporting personnel and/or reviewing the daily progress by telephone.
- . The portable noise level monitor units sensed and recorded SEL events which could not be correlated with aircraft operations. The SEL values were generally low with short durations. While recalibrating unit 103 at site 3, extraneous SEL events were attributed to a mowing tractor operating on the other side of the unopened freeway. Such extraneous SEL events could have been avoided by setting the SEL threshold to a value higher than the 60 dB pre-set level. Subsequently, the threshold level was raised to 65 dB which did reduce the number of extraneous SEL events, but they still outnumbered aircraft-related events. The threshold was maintained at a level lower than necessary for heavy aircraft in order to measure the noise levels of the small aircraft. This would have been unnecessary for a typical site validation. Virtually no significant SEL information would have been lost by setting the SEL threshold at 25 dB below the maximum A-weighted sound level which was 95 to 105 dB depending on the site.
- . On one occasion, the paper became misaligned on the paper take-up reel and folded over on one edge. The problem was traced to factory alignment of the printer. By re-adjusting the printer in the factory, the misalignment problem was solved.
- . On one occasion, the battery voltage dropped below that necessary to run the printer. This came about by using only one battery in the unit while the second battery was being recharged in the laboratory. On the occasion in question, the portable noise level monitor unit was left unattended for an extra day. Fortunately, even though the printer failed to document SEL's and HNL's, the unit was still calculating. With fresh batteries, the unit resumed printing. At the end of that day the unit listed the DNL value for the whole day.

## NOISEMAP AIRCRAFT OPERATIONS

The frequencies of aircraft operations over the measurement sites for the six most frequently flown aircraft were determined from the NOISEMAP chronicles and listed in Table A-5. For synthesis of DNL values from measured SEL values, four different types of aircraft operation were considered as follows:

- Straight-in Approach
- Pattern Approach
- Pattern Takeoff
- Straight-Out Takeoff

The number of each type of operation over the northern measurement sites for both daytime and nighttime were derived by summing of appropriate mission frequencies. For example, four different KC-135A pattern flying missions are listed as departing on Runway 32 with a total rate of 8.240 during the day and 1.780 during the night.

For each type of aircraft operation, the number of nighttime operations was multiplied by 10 and added to the number of daytime operations to arrive at equivalent number of daily operations shown in Table A-5. The sum of the equivalent daytime operations, 329, was subsequently used to correct measured DNL values. In addition, the number of equivalent daily operations for heavy aircraft (B-52G and KC-135A) was determined. This number, 174, was alternatively used to correct measured DNL values.

The numbers of practice operations were similarly derived for correcting measurements at the sites under the practice flight tracks in the east reservation. Noting that all pattern operations are routed over the measurement sites north of the runway, the number of pattern operations is simply the sum of practice approaches and takeoffs.

## ANALYSIS USING MEASURED DNL VALUES

### TABULATION OF MEASURED HNL AND DNL VALUES

The measured HNL and DNL values tabulated directly from the portable noise monitor unit records for each of the five sites are listed in Table A-6. For those situations during recalibration when the calibrator was not removed before the portable noise level monitor was reactivated, the HNL value was reconstructed from the valid SEL values as follows:

TABLE A-5 DAILY FREQUENCIES OF FLIGHT OPERATIONS OVER NORTHERN MEASUREMENT SITES FROM NOISEMAP CHRONICLES

| Type<br>A/C        | Operations |       |       |    | Frequency |        |                      |
|--------------------|------------|-------|-------|----|-----------|--------|----------------------|
|                    | App        |       | T/O   |    | Day       | Night  | Equiv.<br>Day,<br>N* |
|                    | SI         | Patrn | Patrn | SO |           |        |                      |
| KC -<br>135A       | ✓          |       |       |    | 3.180     | 0.510  | 8.28                 |
|                    |            | ✓     |       |    | 12.412    | 2.670  | 39.11                |
|                    |            |       | ✓     |    | 8.240     | 1.780  | 26.04                |
|                    |            |       |       | ✓  | 2.871     | 0.426  | 7.13                 |
| B52G               | ✓          |       |       |    | 2.910     | 0.960  | 12.51                |
|                    |            | ✓     |       |    | 9.750     | 3.600  | 45.75                |
|                    |            |       | ✓     |    | 6.480     | 2.400  | 30.48                |
|                    |            |       |       | ✓  | 2.436     | 0.225  | 4.68                 |
| A-37               | ✓          |       |       |    | 14.430    | 0.092  | 15.35                |
|                    |            | ✓     |       |    | 7.168     | 0.144  | 8.60                 |
|                    |            |       | ✓     |    | 4.770     | 0.099  | 5.76                 |
|                    |            |       |       | ✓  | 5.420     | 0.140  | 6.82                 |
| T-37               | ✓          |       |       |    | 5.400     | 0      | 5.40                 |
|                    |            | ✓     |       |    | 19.260    | 0      | 19.26                |
|                    |            |       | ✓     |    | 10.50     | 0.02   | 10.70                |
|                    |            |       |       | ✓  | 3.580     | 0.02   | 3.78                 |
| T-38               | ✓          |       |       |    | 1.780     | 0.102  | 2.80                 |
|                    |            | ✓     |       |    | 4.160     | 0.298  | 7.14                 |
|                    |            |       | ✓     |    | 2.548     | 0.172  | 4.26                 |
|                    |            |       |       | ✓  | 1.190     | 0.07   | 1.89                 |
| T-39               | ✓          |       |       |    | 2.540     | 1.220  | 14.74                |
|                    |            | ✓     |       |    | 5.230     | 0.190  | 7.13                 |
|                    |            |       | ✓     |    | 3.490     | 0.820  | 11.69                |
|                    |            |       |       | ✓  | 2.370     | 0.130  | 3.67                 |
| Other              | ✓          |       |       |    | 2.80      | 0.10   | 3.80                 |
|                    |            | ✓     |       |    | 5.875     | 0.57   | 11.57                |
|                    |            |       | ✓     |    | 4.08      | 0.41   | 8.18                 |
|                    |            |       |       | ✓  | 1.75      | 0.07   | 2.45                 |
| App.<br>and<br>T/O | All A/C    |       |       |    | 156.6     | 17.238 | 329                  |
|                    | Heavy A/C  |       |       |    | 48.28     | 12.57  | 174                  |
| Patrn<br>(REF)     | All A/C    |       |       |    | 102.2     | 13.17  | 234                  |
|                    | Heavy A/C  |       |       |    | 36.9      | 10.45  | 1414                 |

TABLE A-6 MEASURED HNL AND DNL VALUES\*\*

| Day | Tuesday, 6 June 1978 |      |      |   | Wednesday, 7 June 1978 |      |      |   | Thursday, 8 June 1978 |       |      |   |
|-----|----------------------|------|------|---|------------------------|------|------|---|-----------------------|-------|------|---|
|     | 1                    | 2    | 3    | 4 | 1                      | 2    | 3    | 4 | 1                     | 2     | 3    | 4 |
| 1   | -                    | -    | -    | - | 66.9                   | 59.7 | -    | - | 66.3                  | 56.7  | 54.9 | - |
| 2   | -                    | -    | -    | - | 54.7                   | 49.1 | -    | - | 75.4                  | 70.6  | 63.1 | - |
| 3   | -                    | -    | -    | - | 55.1                   | 46.0 | -    | - | 65.6                  | 52.1  | 52.9 | - |
| 4   | -                    | -    | -    | - | 73.1                   | 66.9 | -    | - | 50.5                  | 44.4  | 50.1 | - |
| 5   | -                    | -    | -    | - | 53.6                   | 44.5 | -    | - | 52.3                  | 43.5  | 47.7 | - |
| 6   | -                    | -    | -    | - | 50.9                   | 48.8 | -    | - | 46.1                  | 48.5  | 49.3 | - |
| 7   | -                    | -    | -    | - | 49.3                   | 50.6 | -    | - | 45.7                  | 50.2  | 54.7 | - |
| 8   | -                    | -    | -    | - | 60.0                   | 52.0 | -    | - | 85.2                  | 79.7  | 71.0 | - |
| 9   | -                    | -    | -    | - | 60.8                   | -    | -    | - | 78.1                  | 72.1  | 64.2 | - |
| 10  | -                    | -    | -    | - | 66.7                   | -    | 58.0 | - | 79.9                  | 79.5  | 72.5 | - |
| 11  | -                    | -    | -    | - | 80.9                   | 74.6 | 67.1 | - | 66.0                  | 64.5  | 60.5 | - |
| 12  | -                    | -    | -    | - | 81.5                   | 81.8 | 72.9 | - | 63.7                  | 59.9  | 54.8 | - |
| 13  | -                    | -    | -    | - | 71.9                   | 73.4 | 68.4 | - | 82.7                  | 76.9* | 69.0 | - |
| 14  | -                    | -    | -    | - | 79.3                   | 78.5 | 71.7 | - | 72.2                  | 72.8  | 68.4 | - |
| 15  | -                    | -    | -    | - | 75.0                   | 65.1 | 59.4 | - | 63.0                  | 57.0  | 68.7 | - |
| 16  | -                    | -    | -    | - | 75.3                   | 64.1 | 61.2 | - | 73.4                  | 61.0  | 60.6 | - |
| 17  | -                    | -    | -    | - | 48.8                   | 46.1 | 48.8 | - | 75.8                  | 65.9  | 61.4 | - |
| 18  | 76.8                 | 69.0 | 57.9 | - | 83.7                   | 75.3 | 65.9 | - | 79.3                  | 78.0  | 64.8 | - |
| 19  | 53.2                 | 48.1 | 52.8 | - | 83.7                   | 81.1 | 70.9 | - | 85.1                  | 82.7  | 74.5 | - |
| 20  | 70.3                 | 61.8 | -    | - | 86.3                   | 79.3 | 69.1 | - | 64.2                  | 62.3  | 61.9 | - |
| 21  | 60.1                 | 50.4 | -    | - | 54.7                   | 46.3 | 55.2 | - | 54.8                  | 49.7  | 51.3 | - |
| 22  | 56.2                 | 45.3 | -    | - | 57.5                   | 48.6 | 59.9 | - | 63.0                  | 52.7  | 56.9 | - |
| 23  | 56.6                 | 47.7 | -    | - | 57.6                   | 48.2 | 57.1 | - | 65.5                  | 57.5  | 58.9 | - |
| 24  | 68.7                 | 66.3 | -    | - | 58.6                   | 49.6 | 55.2 | - | 54.9                  | 42.6  | 56.8 | - |
| DNL | -                    | -    | -    | - | 78.3                   | 73.9 | 66.5 | - | 78.4                  | 74.4  | 68.0 | - |
| LEQ | -                    | -    | -    | - | 77.9                   | 73.5 | -    | - | 77.1                  | 73.5  | 66.1 | - |

\*Reconstructed from valid SEL values

\*\*Calibration correction applied

TABLE A-6 MEASURED HNL AND DNL VALUES\*\*

| Day<br>Hr Site | Friday, 9 June 1978 |      |      |   | Saturday, 10 June 1978 |       |      |   | Sunday, 11 June 1978 |      |      |       |
|----------------|---------------------|------|------|---|------------------------|-------|------|---|----------------------|------|------|-------|
|                | 1                   | 2    | 3    | 4 | 1                      | 2     | 3    | 4 | 1                    | 2    | 3    | 4     |
| 1              | 54.4                | 40.2 | 55.7 | - | 47.6                   | 42.0  | 53.9 | - | 59.6                 | 43.7 | 53.7 | -     |
| 2              | 56.1                | 44.1 | 49.8 | - | 54.5                   | 44.9  | 47.8 | - | 60.0                 | 43.1 | 55.9 | -     |
| 3              | 53.6                | 42.4 | 45.4 | - | 43.6                   | 37.3  | 44.7 | - | 60.3                 | 45.6 | 56.7 | -     |
| 4              | 53.1                | 37.2 | 49.1 | - | 38.5                   | 34.3  | 41.5 | - | 58.8                 | 46.4 | 54.7 | -     |
| 5              | 50.5                | 39.8 | 52.1 | - | 43.7                   | 40.5  | 42.9 | - | 56.2                 | 46.4 | 49.4 | -     |
| 6              | 58.8                | 58.1 | 55.4 | - | 39.5                   | 39.3  | 49.3 | - | 51.6                 | 43.1 | 50.5 | -     |
| 7              | 48.2                | 41.9 | 57.3 | - | 50.5                   | 48.3  | 51.6 | - | 45.6                 | 43.1 | 47.2 | -     |
| 8              | 84.6                | 85.5 | 83.3 | - | 48.0                   | 43.5  | 49.2 | - | 49.4                 | 44.6 | 47.5 | -     |
| 9              | 82.6                | 75.1 | 67.5 | - | 50.1                   | 50.2  | 53.5 | - | 55.4                 | 52.1 | 52.4 | -     |
| 10             | 67.8                | 63.0 | 61.4 | - | 52.6                   | 48.8  | 50.5 | - | 58.6                 | 53.7 | 54.1 | -     |
| 11             | 64.9                | 57.8 | 55.1 | - | 61.3                   | 54.5  | 50.2 | - | 61.9                 | 48.1 | 54.4 | -     |
| 12             | 79.2                | 79.4 | 67.8 | - | 58.0                   | 49.3* | 47.1 | - | 56.9                 | 49.4 | 52.7 | -     |
| 13             | 70.9                | 73.2 | 70.1 | - | 54.7                   | 44.8  | 51.1 | - | 57.2                 | 54.4 | 52.2 | -     |
| 14             | 79.5                | 76.5 | 68.5 | - | 60.7                   | 59.6  | 54.5 | - | 60.9                 | 44.1 | 48.2 | -     |
| 15             | 78.4                | 70.2 | 61.7 | - | 55.6                   | 45.2  | 51.1 | - | -                    | 64.2 | 56.7 | -     |
| 16             | 83.5                | 79.1 | 71.2 | - | 74.7                   | 65.9  | 57.6 | - | -                    | 65.8 | 58.9 | 62.2* |
| 17             | 73.3                | 67.6 | 60.2 | - | 70.1                   | 60.5  | 56.5 | - | -                    | 56.2 | 57.6 | 56.3  |
| 18             | 80.1                | 82.2 | 71.3 | - | 59.7                   | 54.0  | 52.0 | - | -                    | 57.1 | 53.5 | 57.0  |
| 19             | 62.5                | 55.8 | 53.4 | - | 56.5                   | 41.6  | 50.3 | - | -                    | 43.0 | 58.0 | 53.0  |
| 20             | 66.1                | 72.5 | 70.9 | - | 51.2                   | 43.9  | 48.5 | - | -                    | 50.6 | 53.0 | 55.5  |
| 21             | 69.5                | 58.8 | 53.9 | - | 54.4                   | 46.5  | 52.5 | - | -                    | 43.8 | 54.6 | 60.8  |
| 22             | 76.5                | 62.7 | 58.5 | - | 59.9                   | 45.4  | 57.8 | - | -                    | 46.1 | 57.9 | 50.6  |
| 23             | 48.5                | 43   | 57.6 | - | 59.5                   | 44.0  | 54.7 | - | -                    | 45.9 | 61.2 | 46.0  |
| 24             | 46.9                | 43.8 | 55.9 | - | 59.0                   | 45.1  | 53.3 | - | -                    | 46.0 | 59.9 | 42.7  |
| DNL            | 76.9                | 75.4 | 70.4 | - | 64.6                   | 55.7  | 57.8 | - | -                    | 56.5 | 62.6 | -     |
| LEQ            | 76.8                | 75.4 | 70.8 | - | 63.1                   | 54.7  | 52.6 | - | -                    | 48.9 | 55.7 | -     |

\*Reconstructed from valid SEL values

\*\*Calibration correction applied

TABLE A-6 MEASURED HNL AND DNL VALUES\*\*

| Day | Hr | Monday, 12 June 1978 |      |       |      | Tuesday, 13 June 1978 |   |   |      | Wednesday, 14 June 1978 |      |      |   |
|-----|----|----------------------|------|-------|------|-----------------------|---|---|------|-------------------------|------|------|---|
|     |    | 1                    | 2    | 3     | 202  | 203                   | 4 | 1 | 2    | 3                       | 202  | 203  | 4 |
| 1   | -  | 47.4                 | 54.4 | 41.7  | -    | -                     | - | - | 45.1 | -                       | 44.5 | 37.6 | - |
| 2   | -  | 46.5                 | 54.6 | 40.8  | -    | -                     | - | - | 57.6 | -                       | 56.7 | 65.8 | - |
| 3   | -  | 45.5                 | 54.2 | 43.6  | -    | -                     | - | - | 54.3 | -                       | 44.0 | 41.6 | - |
| 4   | -  | 43.8                 | 55.4 | 42.1  | -    | -                     | - | - | 53.2 | -                       | 53.0 | 57.7 | - |
| 5   | -  | 42.1                 | 57.1 | 38.7  | -    | -                     | - | - | 43.0 | -                       | 46.6 | 37.8 | - |
| 6   | -  | 48.7                 | 52.7 | 43.1  | -    | -                     | - | - | 50.2 | -                       | 44.7 | 41.0 | - |
| 7   | -  | 47.6                 | 54.3 | 45.6  | -    | -                     | - | - | 44.6 | -                       | 48.9 | 39.6 | - |
| 8   | -  | 52.1                 | 58.7 | 51.8  | -    | -                     | - | - | 80.5 | -                       | 81.9 | 74.9 | - |
| 9   | -  | 66.1                 | 57.7 | 49.1  | -    | -                     | - | - | 82.1 | -                       | 82.7 | 71.9 | - |
| 10  | -  | 63.0                 | 58.1 | 54.3  | -    | -                     | - | - | 81.6 | -                       | 75.7 | 71.3 | - |
| 11  | -  | -                    | 62.7 | 65.5  | -    | -                     | - | - | 72.3 | -                       | 64.9 | 52.9 | - |
| 12  | -  | 61.0                 | -    | 54.5  | -    | -                     | - | - | 65.0 | -                       | 54.8 | 47.9 | - |
| 13  | -  | 62.2                 | -    | 63.4  | 64.5 | -                     | - | - | 65.0 | -                       | 58.4 | 51.8 | - |
| 14  | -  | 60.7                 | -    | 59.3  | 46.4 | -                     | - | - | 64.2 | -                       | 62.3 | 55.6 | - |
| 15  | -  | 70.7                 | -    | 62.6  | 50.6 | -                     | - | - | 70.8 | -                       | 63.9 | 57.6 | - |
| 16  | -  | 72.2                 | -    | 58.3  | 47.5 | -                     | - | - | 70.0 | -                       | 63.7 | 53.7 | - |
| 17  | -  | 71.1                 | -    | 64.4  | 68.2 | -                     | - | - | 71.3 | -                       | 71.9 | 66.3 | - |
| 18  | -  | 55.5                 | -    | 58.6  | 43.5 | -                     | - | - | 60.1 | -                       | 58.8 | 55.0 | - |
| 19  | -  | 78.9                 | -    | 71.9* | 70.5 | -                     | - | - | 81.1 | -                       | 71.3 | 69.1 | - |
| 20  | -  | 74.0                 | -    | 72.6  | 71.7 | -                     | - | - | 82.6 | -                       | 77.5 | 63.1 | - |
| 21  | -  | 47.5                 | -    | 63.6  | 50.5 | -                     | - | - | 57.3 | -                       | 67.5 | 70.4 | - |
| 22  | -  | 47.5                 | -    | 51.5  | 43.5 | -                     | - | - | 56.1 | -                       | 56.3 | 48.3 | - |
| 23  | -  | 50.0                 | -    | 46.8  | 42.5 | -                     | - | - | 50.2 | -                       | 44.0 | 40.7 | - |
| 24  | -  | 46.1                 | -    | 44.4  | 39.4 | -                     | - | - | 73.5 | -                       | 73.5 | 66.5 | - |
| DNL | -  | 68.4                 | -    | 63.4  | -    | -                     | - | - | 76.4 | -                       | 74.2 | 68.7 | - |
| LEQ | -  | -                    | -    | 63.0  | -    | -                     | - | - | 75.3 | -                       | 75.2 | 66.0 | - |

\*Reconstructed from valid SEL values

\*\*Calibration correction applied

TABLE A-6 MEASURED HNL AND DNL VALUES\*\*

| Day<br>Hr Site | Thursday, 15 June 1978 |      |   |      | Friday, 16 June 1978 |      |   |      | Saturday, 17 June 1978 |     |      |      |
|----------------|------------------------|------|---|------|----------------------|------|---|------|------------------------|-----|------|------|
|                | 1                      | 2    | 3 | 202  | 203                  | 4    | 1 | 2    | 3                      | 202 | 203  | 4    |
| 1              | -                      | 64.4 | - | 64.8 | 71.1                 | -    | - | 60.7 | -                      | -   | 58.5 | 45.6 |
| 2              | -                      | 60.4 | - | 47.7 | 47.9                 | -    | - | 64.7 | -                      | -   | 71.9 | 46.6 |
| 3              | -                      | 40.5 | - | 38.5 | 38.5                 | -    | - | 71.3 | -                      | -   | 65.9 | 41.8 |
| 4              | -                      | 66.0 | - | 67.3 | 67.5                 | -    | - | 60.7 | -                      | -   | 67.5 | 40.9 |
| 5              | -                      | 64.3 | - | 64.8 | 68.0                 | -    | - | 44.5 | -                      | -   | 44.7 | 39.0 |
| 6              | -                      | 46.8 | - | 44.1 | 42.9                 | -    | - | 48.1 | -                      | -   | 48.9 | 52.7 |
| 7              | -                      | 47.2 | - | 49.5 | 48.9                 | -    | - | 57.6 | -                      | -   | 50.7 | 42.3 |
| 8              | -                      | 81.9 | - | 80.5 | 61.5                 | -    | - | 78.3 | -                      | -   | 77.7 | 41.2 |
| 9              | -                      | 54.8 | - | 52.8 | 51.2                 | -    | - | -    | -                      | -   | 42.6 | 44.4 |
| 10             | -                      | 57.8 | - | 57.7 | 63.0                 | -    | - | -    | -                      | -   | 56.3 | 48.4 |
| 11             | -                      | 65.8 | - | -    | 64.8                 | -    | - | 68.5 | -                      | -   | 70.4 | 56.9 |
| 12             | -                      | 66.8 | - | -    | 68.4                 | -    | - | 70.4 | -                      | -   | 73.2 | 50.9 |
| 13             | -                      | 56.2 | - | -    | 49.5                 | 43.0 | - | 74.5 | -                      | -   | 77.5 | 51.5 |
| 14             | -                      | 60.0 | - | -    | 64.2                 | 46.5 | - | 69.1 | -                      | -   | 74.0 | 60.3 |
| 15             | -                      | 55.5 | - | -    | 55.4                 | 41.1 | - | 72.9 | -                      | -   | 77.7 | 58.4 |
| 16             | -                      | 65.4 | - | -    | 73.0                 | 69.3 | - | 72.1 | -                      | -   | 78.9 | 65.9 |
| 17             | -                      | 68.5 | - | -    | 74.7                 | 60.4 | - | 65.8 | -                      | -   | 68.3 | 50.7 |
| 18             | -                      | 61.6 | - | -    | 69.2                 | 41.9 | - | 64.1 | -                      | -   | 64.1 | 45.0 |
| 19             | -                      | 74.1 | - | -    | 75.5                 | 69.6 | - | 68.1 | -                      | -   | 73.2 | 52.5 |
| 20             | -                      | 50.2 | - | -    | 62.4                 | 63.0 | - | 55.8 | -                      | -   | 56.8 | 37.6 |
| 21             | -                      | 48.0 | - | -    | 55.7                 | 45.5 | - | 65.4 | -                      | -   | 67.5 | 47.8 |
| 22             | -                      | 68.7 | - | -    | 66.8                 | 57.7 | - | 68.6 | -                      | -   | 55.1 | 51.1 |
| 23             | -                      | 65.2 | - | -    | 69.1                 | 51.0 | - | 62.8 | -                      | -   | 65.2 | 48.6 |
| 24             | -                      | 68.6 | - | -    | 71.7                 | 47.5 | - | 51.1 | -                      | -   | 43.4 | 46.2 |
| DNL            | -                      | 72.5 | - | -    | 73.5                 | -    | - | 72.2 | -                      | -   | 74.3 | 56.8 |
| LEQ            | -                      | 69.9 | - | -    | 68.1                 | -    | - | 69.3 | -                      | -   | 71.9 | 54.9 |

\*\*Calibration correction applied

TABLE A-6 MEASURED HNL AND DNL VALUES\*\*

| Day |      | Sunday, 18 June 1978 |       |   |     |      | Monday, 19 June 1978 |   |      |   |     | Tuesday, 20 June 1978 |      |   |       |   |     |      |      |
|-----|------|----------------------|-------|---|-----|------|----------------------|---|------|---|-----|-----------------------|------|---|-------|---|-----|------|------|
| Hr  | Site | 1                    | 2     | 3 | 202 | 203  | 4                    | 1 | 2    | 3 | 202 | 203                   | 4    | 1 | 2     | 3 | 202 | 203  | 4    |
| 1   | -    | -                    | 44.7  | - | -   | 42.3 | 47.3                 | - | 43.5 | - | -   | 42.0                  | 49.5 | - | 65.2  | - | -   | 66.7 | 49.8 |
| 2   | -    | -                    | 43.4  | - | -   | 44.7 | 46.7                 | - | 45.4 | - | -   | 41.7                  | 47.2 | - | 64.6  | - | -   | 67.8 | 50.6 |
| 3   | -    | -                    | 46.8  | - | -   | 52.4 | 47.0                 | - | 47.7 | - | -   | 45.4                  | 50.9 | - | 43.1  | - | -   | 41.8 | 48.1 |
| 4   | -    | -                    | 41.3  | - | -   | 43.2 | 45.8                 | - | 43.6 | - | -   | 43.8                  | 45.7 | - | 64.4  | - | -   | 72.2 | 47.1 |
| 5   | -    | -                    | 41.8  | - | -   | 45.5 | 44.9                 | - | 41.3 | - | -   | 44.9                  | 41.3 | - | 43.2  | - | -   | 48.0 | 42.9 |
| 6   | -    | -                    | 55.1  | - | -   | 40.7 | 46.7                 | - | 66.6 | - | -   | 68.1                  | 60.8 | - | 41.8  | - | -   | 43.5 | 49.6 |
| 7   | -    | -                    | 52.7  | - | -   | 40.2 | 46.6                 | - | 70.2 | - | -   | 72.2                  | 67.0 | - | 47.2  | - | -   | 52.7 | 44.7 |
| 8   | -    | -                    | 58.3  | - | -   | 38.1 | 42.2                 | - | 71.4 | - | -   | 70.9                  | 68.5 | - | 52.9  | - | -   | 43.8 | 42.0 |
| 9   | -    | -                    | 63.8  | - | -   | 38.5 | 41.4                 | - | 46.2 | - | -   | 42.6                  | 44.7 | - | 60.3  | - | -   | 55.3 | 45.2 |
| 10  | -    | -                    | 56.5  | - | -   | 43.4 | 36.7                 | - | 52.7 | - | -   | 56.8                  | 51.0 | - | 65.5  | - | -   | 66.0 | 58.7 |
| 11  | -    | -                    | 54.8  | - | -   | 53.4 | 45.2                 | - | 58.5 | - | -   | 51.6                  | 51.4 | - | 75.7  | - | -   | 61.7 | 49.2 |
| 12  | -    | -                    | 61.9  | - | -   | 53.1 | 44.9                 | - | 65.1 | - | -   | 65.6                  | 57.9 | - | 57.8* | - | -   | 56.4 | 44.5 |
| 13  | -    | -                    | 53.1* | - | -   | 51.8 | 53.7                 | - | 63.8 | - | -   | 68.3                  | 45.7 | - | 70.4  | - | -   | 71.6 | 56.9 |
| 14  | -    | -                    | 52.5  | - | -   | 54.2 | 45.0                 | - | 58.5 | - | -   | 49.5                  | 44.9 | - | 63.4  | - | -   | 67.0 | 50.6 |
| 15  | -    | -                    | 53.7  | - | -   | 58.6 | 42.9                 | - | 68.3 | - | -   | 75.7                  | 70.4 | - | 66.8  | - | -   | 72.0 | 50.4 |
| 16  | -    | -                    | 48.6  | - | -   | 43.7 | 43.5                 | - | 66.4 | - | -   | 73.9                  | 50.6 | - | 58.0  | - | -   | 55.6 | 54.1 |
| 17  | -    | -                    | 60.2  | - | -   | 59.8 | 40.2                 | - | 53.7 | - | -   | 58.4                  | 46.1 | - | 57.9  | - | -   | 55.9 | 47.9 |
| 18  | -    | -                    | 57.3  | - | -   | 48.8 | 47.8                 | - | 53.4 | - | -   | 45.0                  | 47.2 | - | 55.1  | - | -   | 56.3 | 38.5 |
| 19  | -    | -                    | 59.0  | - | -   | 48.6 | 51.8                 | - | 61.9 | - | -   | 56.3                  | 74.0 | - | 58.3  | - | -   | 59.4 | 60.0 |
| 20  | -    | -                    | 61.9  | - | -   | 55.5 | 42.3                 | - | 54.7 | - | -   | 46.5                  | 39.7 | - | 46.0  | - | -   | 46.9 | 42.9 |
| 21  | -    | -                    | 56.4  | - | -   | 49.1 | 52.4                 | - | 50.2 | - | -   | 53.5                  | 47.7 | - | 51.8  | - | -   | 52.8 | 53.7 |
| 22  | -    | -                    | 46.9  | - | -   | 42.9 | 52.8                 | - | 65.7 | - | -   | 74.9                  | 62.3 | - | 55.9  | - | -   | 62.7 | 54.5 |
| 23  | -    | -                    | 45.5  | - | -   | 44.6 | 50.8                 | - | 70.1 | - | -   | 72.3                  | 64.1 | - | 60.3  | - | -   | 64.9 | 61.6 |
| 24  | -    | -                    | 43.8  | - | -   | 48.9 | 49.6                 | - | 63.9 | - | -   | 68.5                  | 50.4 | - | 65.5  | - | -   | 71.1 | 63.1 |
| DNL | -    | -                    | 58.6  | - | -   | 54.8 | 54.7                 | - | 71.2 | - | -   | 73.9                  | 67.6 | - | 69.2  | - | -   | 73.0 | 62.5 |
| LEQ | -    | -                    | 56.7  | - | -   | 51.7 | 48.1                 | - | 64.4 | - | -   | 68.4                  | 63.6 | - | 65.1  | - | -   | 65.7 | 54.9 |

\*Reconstructed from valid SEL values

\*\*Calibration correction applied

TABLE A-6 MEASURED HNL AND DNL VALUES\*\*

| Day     | Wednesday, 21 June 1978 |      |   |     | Thursday, 22 June 1978 |      |   |   |   |     |     |      |
|---------|-------------------------|------|---|-----|------------------------|------|---|---|---|-----|-----|------|
|         | 1                       | 2    | 3 | 202 | 203                    | 4    | 1 | 2 | 3 | 202 | 203 | 4    |
| Hr Site |                         |      |   |     |                        |      |   |   |   |     |     |      |
| 1       | -                       | 68.2 | - | -   | 70.5                   | 60.5 | - | - | - | -   | -   | 52.8 |
| 2       | -                       | 64.4 | - | -   | 74.9                   | 57.2 | - | - | - | -   | -   | 51.7 |
| 3       | -                       | 55.9 | - | -   | 44.3                   | 49.0 | - | - | - | -   | -   | 50.2 |
| 4       | -                       | 43.9 | - | -   | 45.6                   | 48.3 | - | - | - | -   | -   | 48.9 |
| 5       | -                       | 43.8 | - | -   | 46.5                   | 58.8 | - | - | - | -   | -   | 48.5 |
| 6       | -                       | 61.5 | - | -   | 71.1                   | 52.3 | - | - | - | -   | -   | 47.7 |
| 7       | -                       | 48.8 | - | -   | 54.4                   | 41.7 | - | - | - | -   | -   | 41.6 |
| 8       | -                       | 61.9 | - | -   | 49.0                   | 42.5 | - | - | - | -   | -   | 43.7 |
| 9       | -                       | 59.6 | - | -   | 53.3                   | 49.6 | - | - | - | -   | -   | 43.6 |
| 10      | -                       | 62.4 | - | -   | 53.1                   | 46.2 | - | - | - | -   | -   | -    |
| 11      | -                       | 63.0 | - | -   | 47.9                   | 48.9 | - | - | - | -   | -   | -    |
| 12      | -                       | 64.2 | - | -   | 58.3                   | 47.7 | - | - | - | -   | -   | -    |
| 13      | -                       | 63.4 | - | -   | 61.4                   | 57.4 | - | - | - | -   | -   | -    |
| 14      | -                       | 67.9 | - | -   | 74.8                   | 65.5 | - | - | - | -   | -   | -    |
| 15      | -                       | 68.7 | - | -   | 70.8                   | 69.0 | - | - | - | -   | -   | -    |
| 16      | -                       | 57.6 | - | -   | -                      | 52.5 | - | - | - | -   | -   | -    |
| 17      | -                       | -    | - | -   | -                      | 61.5 | - | - | - | -   | -   | -    |
| 18      | -                       | -    | - | -   | -                      | 38.3 | - | - | - | -   | -   | -    |
| 19      | -                       | -    | - | -   | -                      | 53.1 | - | - | - | -   | -   | -    |
| 20      | -                       | -    | - | -   | -                      | 39.5 | - | - | - | -   | -   | -    |
| 21      | -                       | -    | - | -   | -                      | 66.5 | - | - | - | -   | -   | -    |
| 22      | -                       | -    | - | -   | -                      | 62.4 | - | - | - | -   | -   | -    |
| 23      | -                       | -    | - | -   | -                      | 55.4 | - | - | - | -   | -   | -    |
| 24      | -                       | -    | - | -   | -                      | 60.9 | - | - | - | -   | -   | -    |
| DNL     | -                       | -    | - | -   | -                      | 64.2 | - | - | - | -   | -   | -    |
| LEQ     | -                       | -    | - | -   | -                      | 60.1 | - | - | - | -   | -   | -    |

\*\*Calibration correction applied

$$L_h = 10 \log \sum_p 10^{\frac{L_{AE}}{10}} - 10 \log(3600) \quad (1)$$

where

$L_h$  = hourly noise level (HNL), dB

$L_{AE}$  = A-Weighted Sound Exposure Level (SEL), dB

$p$  = summation index for SEL values in particular hour.

The day-night noise levels for those situations were then calculated from the hourly noise levels as follows:

$$L_{dn} = 10 \log \sum_i 10^{\frac{L_h}{10}} + 10 \log \sum_j 10^{\frac{(L_h+10)}{10}} - 10 \log(24) \quad (2)$$

where

$L_{dn}$  = day-night noise level (DNL), dB

$L_h$  = hourly noise level (HNL), dB

$i$  = summation index for daytime HNL's

$j$  = summation index for nighttime HNL's.

In addition, the average sound levels were calculated from the HNL and DNL values for each complete day of data and are also listed. If all 24 HNL values were available, the particular LEQ value was calculated using Eq. (3).

$$L_{24} = 10 \log \left[ \sum_i 10^{\frac{L_h}{10}} + \sum_j 10^{\frac{L_h}{10}} \right] - 10 \log(24) \quad (3)$$

where

$L_{24}$  = twenty-four-hour average noise level (LEQ), dB

$L_h$  = hourly noise level (HNL), dB

$i$  = summation index for daytime HNL's

$j$  = summation index for nighttime HNL's.

If one or more daytime hourly noise levels were missing and all nighttime hourly noise levels were recorded, the LEQ was calculated using Eq. (4).

$$L_{24} = 10 \log \left[ 10^{\frac{L_{dn}}{10}} - \sum_j 10^{\frac{9(L_h + 10)}{10}} \right] \quad (4)$$

where

$L_{24}$  = twenty-four-hour average noise level (LEQ), dB

$L_{dn}$  = day-night noise level (DNL), dB

$L_h$  = hourly noise level (HNL), dB

$j$  = summation index for nighttime HNL's.

Inspection of the data in Table A-6 reveals missing HNL values. The missing HNL values at sites 2 and 3 on June 6-7 are due to the paper jam caused by installing the portable noise level monitor units over backwards against trees. On other occasions, HNL values were not printed because the unit was being recalibrated.

#### SUMMARY OF FIELD TEST DAILY FLIGHT OPERATIONS

Next, the daily flight operations statistics were summarized from the tower log sheets. The log sheet for the end of 7 June with totals of that day's operations over the measurement sites is presented as Table A-7. These totals of each day's operations were summarized in Tables A-8(a), (b), and (c) for approaches, takeoffs, and patterns, respectively. In each case, summaries were made for both heavy aircraft and all aircraft. Equivalent numbers of daytime operations were then computed by multiplying the numbers of nighttime operations by 10 and adding to the numbers of daytime operations. In Tables A-8(c) and A-8(b), the reversing of the direction of flights from Runway 14 (approaches over the measurement sites) to Runway 32 (takeoffs over the measurement sites) is apparent.

#### CALCULATION OF DAILY CORRECTIONS FOR AIRCRAFT OPERATIONS

If the daily proportion of takeoffs and landings are similar to the annual average, it is possible to adjust the daily DNL values based on equation 5.

AIRCRAFT TOWER LOG AND NOISE  
MONITOR DATA TABULATION FORM

Installation BAFB

Date 7 JUNE

Runway(s) 32

TABLE A-7

| Aircraft Type |        |      |      |      |      |       |       | Operation            |                  | Time  |          | Noise Monitor Data                   |         |          |         |
|---------------|--------|------|------|------|------|-------|-------|----------------------|------------------|-------|----------|--------------------------------------|---------|----------|---------|
| KC-135A       | B-52 G | A-37 | T-37 | T-38 | T-39 | C-130 | Other | Approch <sup>*</sup> | T/O <sup>+</sup> | GMT   | Local    | Time                                 | SEL, dB | Dur, sec | Max, dB |
|               |        |      |      |      |      |       | C-150 | IN                   |                  | 0020  | 1920     |                                      |         |          |         |
| ✓             |        |      |      |      |      |       |       | IN                   |                  | 0035  | 1935     |                                      |         |          |         |
| ✓             |        |      |      |      |      |       |       |                      | OUT              | 0056  | 1956     |                                      |         |          |         |
|               |        |      |      |      |      |       | C-150 |                      | OUT              | 0105  | 2005     |                                      |         |          |         |
|               |        |      |      |      |      |       | C-150 |                      | OUT              | 0112  | 2012     |                                      |         |          |         |
|               |        |      |      |      |      |       | C-150 | P                    | P                | 0150  | 2050     |                                      |         |          |         |
|               |        |      |      |      |      |       | C-150 | P                    | P                | 0155  | 2055     |                                      |         |          |         |
|               |        |      |      |      |      |       | C-150 | P                    | P                | 0202  | 2102     |                                      |         |          |         |
|               |        |      |      |      |      |       | C-150 | IN                   |                  | 0203  | 2103     |                                      |         |          |         |
|               |        |      |      |      |      |       | C-150 | IN                   |                  | 0208  | 2108     |                                      |         |          |         |
|               |        |      |      |      | ✓    |       |       | IN                   |                  | 0328  | 2228     |                                      |         |          |         |
|               |        |      |      |      | ✓    |       |       |                      | OUT              | 0400  | 2300     |                                      |         |          |         |
| 0             | 0      | 11   | 2    | 0    | 0    | 11    | 1     | 25                   | —                | DAY   | APPROACH | OVER NORTHERN<br>MEASUREMENT<br>SITE |         |          |         |
| 2             | 7      | 0    | 0    | 0    | 0    | 1     | 0     | 10                   | —                | NIGHT |          |                                      |         |          |         |
| 28            | 15     | 27   | 0    | 0    | 2    | 21    | 17    | —                    | 93               | DAY   | TAKEOFF  |                                      |         |          |         |
| 0             | 0      | 0    | 0    | 0    | 1    | 0     | 0     | —                    | 1                | NIGHT |          |                                      |         |          |         |
| 18.5          | 12     | ←    |      | 93   | →    |       |       | 123.5                |                  | DAY   | PATTERN  | OVER EAST<br>RESERVATION             |         |          |         |
| 1             | 6.5    | ←    |      | 16   | →    |       |       | 23.5                 |                  | NIGHT |          |                                      |         |          |         |
|               |        |      |      |      |      |       |       | TOTALS               |                  |       |          |                                      |         |          |         |

\*Approach - SI - Straight In  
P - Pattern

+Takeoff SO - Straight Out  
P - Pattern

R - Right Turn Departure  
L - Left Turn Departure

TABLE A-8(a) DAILY OPERATIONS SUMMARY, APPROACHES OVER THE NORTHERN MEASUREMENT SITES

| Day | Date       | KC-135A |       | B-52G |       | Total Heavy A/C |       | Equivalent Day Heavy A/C |       | Other A/C |       | Total A/C |       | Equivalent Day A/C |
|-----|------------|---------|-------|-------|-------|-----------------|-------|--------------------------|-------|-----------|-------|-----------|-------|--------------------|
|     |            | Day     | Night | Day   | Night | Day             | Night | Day                      | Night | Day       | Night | Day       | Night |                    |
| T   | 6 June 78* | 0       | 1     | 5     | 0     | 5               | 1     | 15                       | 0     | 15        | 0     | 20        | 1     | 30                 |
| W   | 7          | 0       | 2     | 0     | 7     | 0               | 9     | 90                       | 1     | 25        | 1     | 25        | 10    | 125                |
| Th  | 8          | -       | -     | -     | -     | -               | -     | -                        | -     | -         | -     | -         | -     | -                  |
| F   | 9          | -       | -     | -     | -     | -               | -     | -                        | -     | -         | -     | -         | -     | -                  |
| S   | 10         | 9       | 0     | 0     | 0     | 9               | 0     | 9                        | 2     | 64        | 2     | 73        | 2     | 93                 |
| S   | 11         | 7       | 0     | 0     | 0     | 7               | 0     | 7                        | 0     | 30        | 0     | 37        | 0     | 37                 |
| M   | 12         | 11      | 0     | 0     | 0     | 11              | 0     | 11                       | 2     | 35        | 2     | 46        | 2     | 66                 |
| T   | 13         | -       | -     | -     | -     | -               | -     | -                        | -     | -         | -     | -         | -     | -                  |
| W   | 14         | 30      | 1     | 22    | 1     | 52              | 2     | 72                       | 0     | 120       | 0     | 172       | 2     | 192                |
| Th  | 15         | 17      | 21    | 11    | 5     | 28              | 26    | 288                      | 0     | 116       | 0     | 144       | 26    | 404                |
| F   | 16         | 39      | 20    | 31    | 11    | 70              | 31    | 380                      | 0     | 84        | 0     | 154       | 31    | 464                |
| S   | 17         | 6       | 0     | 13    | 0     | 19              | 0     | 19                       | 4     | 38        | 4     | 57        | 4     | 97                 |
| S   | 18         | 0       | 0     | 0     | 0     | 0               | 0     | 0                        | 3     | 52        | 3     | 52        | 3     | 82                 |
| M   | 19         | 18      | 26    | 14    | 4     | 32              | 30    | 332                      | 0     | 104       | 0     | 136       | 30    | 436                |
| T   | 20         | *       | -     | -     | 14    | -               | 14    | 140                      | 2     | -         | 2     | -         | 16    | 160                |
| W   | 21         |         |       |       |       |                 |       |                          |       |           |       |           |       |                    |
| Th  | 22         |         |       |       |       |                 |       |                          |       |           |       |           |       |                    |

\*Partial Day

TABLE A-8 (b) DAILY OPERATIONS SUMMARY, TAKEOFFS OVER THE NORTHERN MEASUREMENT SITES

| Day | Date        | KC-135A |       | B-52G |       | Total Heavy A/C |       | Equivalent Day Heavy A/C |       | Other A/C |       | Total A/C |       | Equivalent Day A/C |
|-----|-------------|---------|-------|-------|-------|-----------------|-------|--------------------------|-------|-----------|-------|-----------|-------|--------------------|
|     |             | Day     | Night | Day   | Night | Day             | Night | Day                      | Night | Day       | Night | Day       | Night |                    |
| T   | 6 June 78 * | -       | -     | -     | -     | -               | -     | -                        | -     | -         | -     | -         | -     | -                  |
| W   | 7           | 28      | 0     | 15    | 0     | 43              | 0     | 43                       |       | 48        | 1     | 93        | 1     | 103                |
| Th  | 8           | 11      | 9     | 18    | 7     | 29              | 16    | 189                      |       | 164       | 9     | 193       | 25    | 443                |
| F   | 9           | 29      | 0     | 25    | 3     | 54              | 3     | 84                       |       | 112       | 3     | 166       | 6     | 226                |
| S   | 10          | 0       | 0     | 0     | 0     | 0               | 0     | 0                        |       | 0         | 1     | 0         | 1     | 10                 |
| S   | 11          | -       | -     | -     | -     | -               | -     | -                        |       | -         | -     | -         | -     | -                  |
| M   | 12          | 7       | 3     | 18    | 0     | 25              | 3     | 55                       |       | 75        | 1     | 100       | 4     | 140                |
| T   | 13          | 14      | 6     | 23    | 11    | 37              | 17    | 207                      |       | 134       | 18    | 171       | 35    | 521                |
| W   | 14          | 2       | 5     | 3     | 12    | 5               | 17    | 175                      |       | 9         | 2     | 14        | 19    | 204                |
| Th  | 15          | -       | -     | -     | -     | -               | -     | -                        |       | -         | -     | -         | -     | -                  |
| F   | 16          | -       | -     | -     | -     | -               | -     | -                        |       | -         | -     | -         | -     | -                  |
| S   | 17          | -       | -     | -     | -     | -               | -     | -                        |       | -         | -     | -         | -     | -                  |
| S   | 18          | -       | -     | -     | -     | -               | -     | -                        |       | -         | -     | -         | -     | -                  |
| M   | 19          | -       | -     | -     | -     | -               | -     | -                        |       | -         | -     | -         | -     | -                  |
| T   | 20*         | -       | -     | -     | -     | -               | -     | -                        |       | -         | -     | -         | -     | -                  |
| W   | 21          |         |       |       |       |                 |       |                          |       |           |       |           |       |                    |
| Th  | 22          |         |       |       |       |                 |       |                          |       |           |       |           |       |                    |

\* Partial day

TABLE A-8 (c) DAILY OPERATIONS SUMMARY, PATTERNS OVER THE EAST RESERVATION MEASUREMENT SITES

| Day | Date       | KC-135A |       | B-52G |       | Total Heavy A/C |       | Equivalent Day Heavy A/C |       | Other A/C |       | Total A/C |       | Equivalent Day A/C |
|-----|------------|---------|-------|-------|-------|-----------------|-------|--------------------------|-------|-----------|-------|-----------|-------|--------------------|
|     |            | Day     | Night | Day   | Night | Day             | Night | Day                      | Night | Day       | Night | Day       | Night |                    |
| T   | 6 June 78* | 1       | 0     | 1     | 0     | 2               | 0     | 2                        |       | 5         | 0     | 7         | 0     | 7                  |
| W   | 7          | 18.5    | 1     | 12    | 6.5   | 30.5            | 7.5   | 105.5                    |       | 93        | 16    | 123.5     | 23.5  | 358.5              |
| Th  | 8          | 7       | 0     | 11    | 0     | 18              | 0     | 18                       |       | 90        | 7     | 108       | 7     | 178                |
| F   | 9          | 23      | 0     | 25    | 3     | 48              | 3     | 78                       |       | 70        | 0     | 118       | 3     | 148                |
| S   | 10         | 4       | 0     | 0     | 0     | 4               | 0     | 4                        |       | 43        | 0     | 47        | 0     | 47                 |
| S   | 11         | 4       | 0     | 0     | 0     | 4               | 0     | 4                        |       | 2         | 0     | 6         | 0     | 6                  |
| M   | 12         | 12      | 3     | 15    | 0     | 27              | 3     | 57                       |       | 80        | 2     | 137       | 5     | 187                |
| T   | 13         | 10      | 2     | 15    | 10    | 25              | 12    | 145                      |       | 93        | 12    | 118       | 24    | 358                |
| W   | 14         | 22      | 4     | 15    | 12    | 37              | 16    | 197                      |       | 61        | 0     | 98        | 16    | 258                |
| Th  | 15         | 2       | 23    | 8     | 7     | 10              | 30    | 310                      |       | 37        | 11    | 47        | 41    | 457                |
| F   | 16         | 32      | 19    | 26    | 10    | 58              | 29    | 248                      |       | 38        | 0     | 96        | 29    | 386                |
| S   | 17         | 3       | 0     | 11    | 0     | 14              | 0     | 14                       |       | 23        | 0     | 37        | 0     | 37                 |
| S   | 18         | 0       | 0     | 0     | 0     | 0               | 0     | 0                        |       | 15        | 1     | 15        | 1     | 25                 |
| M   | 19         | 15      | 24    | 11    | 3     | 26              | 27    | 296                      |       | 68        | 0     | 94        | 27    | 364                |
| T   | 20*        | -       | 0     | -     | 12    | -               | 12    | 120                      |       | -         | 2     | -         | 14    | 140                |
| W   | 21         |         |       |       |       |                 |       |                          |       |           |       |           |       |                    |
| Th  | 22         |         |       |       |       |                 |       |                          |       |           |       |           |       |                    |

\*Partial Day

$$\Delta = 10 \log \frac{\text{Number NOISEMAP Equiv Average Day Operations}}{\text{Number Field Test Equiv Day Operations}} \quad (5)$$

Typically the ratio of takeoffs and landings vary from day to day. Measurement at the same location for an extended period of time will normally provide average operational data that has a ratio similar to the annual average operational data. During the field measurements at Barksdale, one location was measured throughout the study. This was site 2. Corrections for all aircraft and for heavy aircraft are shown in Table A-9.

#### APPLICATION OF AIRCRAFT OPERATIONS CORRECTIONS TO MEASURED DNL VALUES

The corrections for the number of aircraft operations were applied to the measured DNL values in Table A-10 for total aircraft volume and for heavy aircraft volume. The energy average and sample standard deviations were calculated. This calculation was performed on a hand calculator with statistical functions. In equation form, the energy average DNL value for a specific site is given by

$$\overline{L}_{dn} = 10 \log \frac{1}{n} \sum_{\ell} 10^{\frac{L_{dn}}{10}} \quad (6)$$

where

$\overline{L}_{dn}$  = energy average day-night noise level (DNL), dB

$n$  = number of DNL values measured at the specific site

$L_{dn}$  = individual day-night noise level (DNL), dB

$\ell$  = summation index for DNL values.

Note that in all subsequent calculations involving sets of data, the symbol "n" is used to represent the number of data values involved in the particular calculation.

Table A-9 Flight Operations Corrections

| Day of Week              | Date                  | All Aircraft Over Site 2 |            |            | Heavy Aircraft Over Site 2 |          |            | Total |
|--------------------------|-----------------------|--------------------------|------------|------------|----------------------------|----------|------------|-------|
|                          |                       | App                      | T/O        | Total      | App                        | T/O      | Total      |       |
| W                        | 7 June 1978           | 125                      | 103        | 228        | 90                         | 43       | 133        |       |
| Th                       | 8                     | 0                        | 443        | 443        | 0                          | 189      | 189        |       |
| F                        | 9                     | 0                        | 226        | 226        | 0                          | 84       | 84         |       |
| S                        | 10                    | 93                       | 10         | 103        | 9                          | 0        | 9          |       |
| S                        | 11                    | 37                       | 0          | 37         | 7                          | 0        | 7          |       |
| M                        | 12                    | 66                       | 140        | 206        | 11                         | 55       | 66         |       |
| T                        | 13                    | 0                        | 521        | 521        | 0                          | 207      | 207        |       |
| W                        | 14                    | 192                      | 204        | 396        | 72                         | 175      | 247        |       |
| Th                       | 15                    | 404                      | 0          | 404        | 288                        | 0        | 288        |       |
| F                        | 16                    | 464                      | 0          | 464        | 380                        | 0        | 380        |       |
| S                        | 17                    | 97                       | 0          | 93         | 19                         | 0        | 19         |       |
| S                        | 18                    | 82                       | 0          | 82         | 0                          | 0        | 0          |       |
| M                        | 19                    | 436                      | 0          | 436        | 332                        | 0        | 332        |       |
| Average Daily Flight     | All Days<br>Week Days | 154<br>174               | 127<br>182 | 281<br>356 | 93<br>130                  | 58<br>84 | 151<br>224 |       |
| NOISEMAP                 |                       | 197                      | 132        | 329        | 104                        | 70       | 174        |       |
| Correction $\Delta$ , dB | All Days<br>Week Days |                          |            | .7<br>-.3  |                            |          | .6<br>-1.1 |       |

Table A-10 Application of Corrections to Measured DNL Values - Site 2

| <u>Day of Week</u> | <u>Date</u> | <u>Measured DNL Values</u> |                       |
|--------------------|-------------|----------------------------|-----------------------|
| W                  | 7 June 1978 | 73.9                       |                       |
| Th                 | 8           | 74.4                       |                       |
| F                  | 9           | 75.8                       |                       |
| S                  | 10          | 55.7                       |                       |
| S                  | 11          | 56.5                       |                       |
| M                  | 12          | 68.4                       |                       |
| T                  | 13          | 76.4                       |                       |
| W                  | 14          | 71.4                       |                       |
| Th                 | 15          | 72.5                       |                       |
| F                  | 16          | 72.2                       |                       |
| S                  | 17          | 61.7                       |                       |
| S                  | 18          | 58.6                       |                       |
| M                  | 19          | 71.2                       |                       |
|                    |             |                            |                       |
| Energy Average     | All Days    | 72.0                       |                       |
| DNL (dB)           | Week Days   | 73.5                       |                       |
|                    |             |                            |                       |
| Energy Average     | All Days    | +2.8/-10.6                 |                       |
| Standard Deviation | Week Days   | +1.9/-3.4                  |                       |
|                    |             |                            |                       |
|                    |             | <u>All Aircraft</u>        | <u>Heavy Aircraft</u> |
| Correction         | All Days    | .7                         | .6                    |
| Δ, dB              | Week Days   | -.3                        | -1.1                  |
|                    |             |                            |                       |
| Corrected Energy   | All Days    | 72.7                       | 72.6                  |
| Average DNL        | Week Days   | 73.2                       | 72.4                  |
|                    |             |                            |                       |
| NOISEMAP           |             |                            |                       |
| DNL (Ref)          |             | 76.4                       | 76.4                  |

The average DNL estimates based on both weekdays' and all-days' measurements are given in Table A-10 along with the corresponding NOISEMAP predictions. The estimates based on the field measurements are lower than the NOISEMAP predictions.

With only the use of measured DNL data, these differences in measurements and predictions cannot be resolved.

The DNL sample standard deviation values were calculated on the basis on energy at the same time the energy average values were determined (with the hand-held calculator) using the relationship

$$s^2 = \frac{1}{n-1} \left[ \sum_{\ell} \left( 10^{\frac{L_{dn}}{10}} \right)^2 - n \left( 10^{\frac{\overline{L_{dn}}}{10}} \right)^2 \right] \quad (7)$$

where

s = sample standard deviation expressed as an antilog with 1.0 equal to the sound level reference of  $20\mu$   
 $N/n^2$

n = number of DNL values in sample.

The energy standard deviation was first added to and then subtracted from the energy mean value. These values were then converted to dB, the mean DNL value was subtracted and the standard deviation in terms of dB was thus calculated.

#### ANALYSIS USING MEASURED SEL VALUES

##### CORRELATION OF RECORDED SEL'S WITH TOWER LOGS

A Noise Monitor Data Tabulation Form Extension was added to each page of the tower flight log. The SEL events recorded on the portable noise level monitor units were correlated with tower flight log events, and the recorded data were tabulated. A tabulation for one day, 7 June 1978, is presented as Table A-11. This tabulation is a laborious task which was facilitated by employing the following steps:

TABLE A-11

AIRCRAFT TOWER LOG AND NOISE  
MONITOR DATA TABULATION FORM

NOISE MONITOR DATA TABULATION FORM EXTENSION, THREE SITES

BAFB  
Installation  
Date 7 June 78  
Runway(s) 14

| Aircraft Type |  |  | Operation | Time    |      | Time |        |        | SEL, dB |        |        |        |        |    | Duration, sec. |        |        | MAX, dB |        |        |
|---------------|--|--|-----------|---------|------|------|--------|--------|---------|--------|--------|--------|--------|----|----------------|--------|--------|---------|--------|--------|
|               |  |  |           | Approch | T/O* | GMT  | Local  | Site 1 | Site 2  | Site 3 | Site 1 | Site 2 | Site 3 | Δ  | Δ              | Site 1 | Site 2 | Site 3  | Site 1 | Site 2 |
| KC 135A       |  |  |           |         |      |      |        |        |         |        |        |        |        |    |                |        |        |         |        |        |
| B 52 G        |  |  |           |         |      |      |        |        |         |        |        |        |        |    |                |        |        |         |        |        |
| A-37          |  |  |           |         |      |      |        |        |         |        |        |        |        |    |                |        |        |         |        |        |
| T-37          |  |  |           |         |      |      |        |        |         |        |        |        |        |    |                |        |        |         |        |        |
| T-38          |  |  |           |         |      |      |        |        |         |        |        |        |        |    |                |        |        |         |        |        |
| T-39          |  |  |           |         |      |      |        |        |         |        |        |        |        |    |                |        |        |         |        |        |
| C-130         |  |  |           |         |      |      |        |        |         |        |        |        |        |    |                |        |        |         |        |        |
| Other         |  |  |           |         |      |      |        |        |         |        |        |        |        |    |                |        |        |         |        |        |
| ✓             |  |  | SI        |         | 0502 | 0002 | 000201 | 000148 | —       | 90.0   | 81.1   | —      | 23     | 24 | —              | 8.9    | —      | —       | 82.9   | 70.7   |
| ✓             |  |  | P         |         | 0510 | 0010 | 001110 | 00106  | —       | 89.9   | 77.9   | —      | 70     | 25 | —              | 12     | —      | —       | 79.9   | 67.2   |
|               |  |  | SI        |         | 0518 | 0018 | 001704 | 001656 | —       | 101.6  | 94.5   | —      | 46     | 47 | —              | 7.1    | —      | —       | 92.2   | 85.1   |
| ✓             |  |  | SO        |         | 0520 | 0020 |        |        |         |        |        |        |        |    |                |        |        |         |        |        |
| ✓             |  |  | P         |         | 0815 | 0315 | 031317 | 031310 | —       | 105.5  | 100.7  | —      | 53     | 51 | —              | 4.8    | —      | —       | 97.9   | 91.2   |
| ✓             |  |  | P         |         | 0818 | 0318 |        |        |         |        |        |        |        |    |                |        |        |         |        |        |
| ✓             |  |  | P         |         | 0820 | 0320 | 032525 | 032524 | —       | 102.9  | 96.1   | —      | 52     | 41 | —              | 6.8    | —      | —       | 94.4   | 85.8   |
| ✓             |  |  | P         |         | 0836 | 0336 | 033507 | 033448 | —       | 90.9   | 76.8   | —      | 41     | 16 | —              | 14.1   | —      | —       | 81.3   | 68.4   |
| ✓             |  |  | P         |         | 0847 | 0347 | 034615 | 034558 | —       | 100.7  | 89.7   | —      | 43     | 40 | —              | 11     | —      | —       | 92.5   | 80.1   |
| ✓             |  |  | P         |         | 0851 | 0351 | 035123 | 035120 | —       | 88.4   | 74.8   | —      | 23     | 12 | —              | 13.6   | —      | —       | 79.5   | 67.1   |
| ✓             |  |  | P         |         | 0858 | 0358 | 035716 | 035710 | —       | 92.1   | 77.8   | —      | 46     | 24 | —              | 14.3   | —      | —       | 80.7   | 67.4   |
| ✓             |  |  | P         |         | 1056 | 0556 | 074052 | 074041 | —       | 93.0   | 82.2   | —      | 22     | 24 | —              | 9.8    | —      | —       | 85.7   | 71.9   |
| ✓             |  |  | SO        |         | 1241 | 0741 |        |        |         |        |        |        |        |    |                |        |        |         |        |        |
| ✓             |  |  | P         |         | 1245 | 0745 | 075530 | 075530 | —       | 92.1   | 81.6   | —      | 25     | 28 | —              | 10.5   | —      | —       | 84.8   | 70.5   |
| ✓             |  |  | P         |         | 1256 | 0756 | 080923 |        | —       | 79.4   |        | —      | 19     | —  | —              | —      | —      | —       | 71.3   |        |
| ✓             |  |  | SO        |         | 1310 | 0810 |        |        |         |        |        |        |        |    |                |        |        |         |        |        |
| ✓             |  |  | SO        |         | 1316 | 0816 |        |        |         |        |        |        |        |    |                |        |        |         |        |        |
| ✓             |  |  | SO        |         | 1317 | 0817 |        |        |         |        |        |        |        |    |                |        |        |         |        |        |
| ✓             |  |  | SO        |         | 1328 | 0828 |        |        |         |        |        |        |        |    |                |        |        |         |        |        |
| ✓             |  |  | SO        |         | 1329 | 0829 |        |        |         |        |        |        |        |    |                |        |        |         |        |        |
| ✓             |  |  | SO        |         | 1331 | 0831 |        |        |         |        |        |        |        |    |                |        |        |         |        |        |
| ✓             |  |  | SO        |         | 1335 | 0835 |        |        |         |        |        |        |        |    |                |        |        |         |        |        |
| ✓             |  |  | P         |         | 1337 | 0837 |        |        |         |        |        |        |        |    |                |        |        |         |        |        |
| ✓             |  |  | P         |         | 1342 | 0842 | 084148 | 094143 | —       | 97.7   | 83.0   | —      | 23     | 28 | —              | 4.7    | —      | —       | 79.2   | 74.2   |
| ✓             |  |  | P         |         | 1345 | 0845 |        |        |         |        |        |        |        |    |                |        |        |         |        |        |
| ✓             |  |  | SI        |         | 1347 | 0847 |        |        |         |        |        |        |        |    |                |        |        |         |        |        |
| ✓             |  |  | P         |         | 1348 | 0848 | 094905 | 094910 | —       | 96.9   | 70.3   | —      | 23     | 8  | —              | 13.6   | —      | —       | 79.9   | 65.3   |
| ✓             |  |  | SO        |         | 1350 | 0850 |        |        |         |        |        |        |        |    |                |        |        |         |        |        |
| ✓             |  |  | P         |         | 1354 | 0854 | 085331 | —      | —       | 78.8   |        | —      | 16     | —  | —              | —      | —      | —       | 70.6   |        |
| ✓             |  |  | SO        |         | 1356 | 0856 |        |        |         |        |        |        |        |    |                |        |        |         |        |        |

\*Approach - SI - Straight In  
P - Pattern

+Takeoff  
SO - Straight Out  
P - Pattern

R - Right Turn Departure  
L - Left Turn Departure

TABLE A-11

AIRCRAFT TOWER LOG AND NOISE  
MONITOR DATA TABULATION FORM

NOISE MONITOR DATA TABULATION FORM EXTENSION, THREE SITES

BAFB

Installation

7 June 78-

Date

Runway(s)

14 (92)

| Aircraft Type | Operation<br>*Approch | T/O <sup>+</sup> | Time      |       | Time   |        |        | SEL, dB |        |        | Duration, sec. |     |        | MAX, dB |        |        |        |        |
|---------------|-----------------------|------------------|-----------|-------|--------|--------|--------|---------|--------|--------|----------------|-----|--------|---------|--------|--------|--------|--------|
|               |                       |                  | GMT       | Local | Site 1 | Site 2 | Site 3 | Site 1  | Site 2 | Site 3 | 1-2            | 3-2 | Site 1 | Site 2  | Site 3 | Site 1 | Site 2 | Site 3 |
|               |                       |                  |           |       |        |        |        |         |        |        |                |     |        |         |        |        |        |        |
| KC 135A       |                       |                  |           |       |        |        |        |         |        |        |                |     |        |         |        |        |        |        |
| B 52 G        |                       |                  |           |       |        |        |        |         |        |        |                |     |        |         |        |        |        |        |
| A-37          |                       |                  |           |       |        |        |        |         |        |        |                |     |        |         |        |        |        |        |
| T-37          |                       |                  |           |       |        |        |        |         |        |        |                |     |        |         |        |        |        |        |
| T-38          |                       |                  |           |       |        |        |        |         |        |        |                |     |        |         |        |        |        |        |
| T-39          |                       |                  |           |       |        |        |        |         |        |        |                |     |        |         |        |        |        |        |
| C-130         |                       |                  |           |       |        |        |        |         |        |        |                |     |        |         |        |        |        |        |
| Other         |                       |                  |           |       |        |        |        |         |        |        |                |     |        |         |        |        |        |        |
|               | P                     | P                | 1358 0858 |       | 0852   | —      | —      | 92.5    | —      | —      | —              | —   | 42     | —       | —      | 83.5   | —      | —      |
|               | P                     | P                | 1359 0859 |       | 0854   | —      | —      | 82.9    | —      | —      | —              | —   | 36     | —       | —      | 72.2   | —      | —      |
|               | P                     | P                | 1403 0903 |       | 0902   | —      | —      | 96.7    | —      | —      | —              | —   | 35     | —       | —      | 92     | —      | —      |
|               | P                     | P                | 1405 0905 |       | 0904   | —      | —      | 89.6    | —      | —      | —              | —   | 23     | —       | —      | 82.2   | —      | —      |
|               | P                     | P                | 1407 0907 |       | 0906   | —      | —      | 91.8    | —      | —      | —              | —   | 32     | —       | —      | 84.4   | —      | —      |
|               | P                     | P                | 1408 0908 |       | 0907   | —      | —      | 79.2    | —      | —      | —              | —   | 33     | —       | —      | 67.5   | —      | —      |
|               | P                     | P                | 1410 0910 |       | 0909   | —      | —      | —       | —      | —      | —              | —   | —      | —       | —      | —      | —      | —      |
|               | P                     | P                | 1411 0911 |       | 0910   | —      | —      | —       | —      | —      | —              | —   | —      | —       | —      | —      | —      | —      |
|               | P                     | P                | 1412 0912 |       | 0911   | —      | —      | —       | —      | —      | —              | —   | —      | —       | —      | —      | —      | —      |
|               | P                     | P                | 1413 0913 |       | 0912   | —      | —      | 79.7    | —      | —      | —              | —   | 21     | —       | —      | 69.3   | —      | —      |
|               | P                     | P                | 1418 0918 |       | 0917   | —      | —      | 86.5    | —      | —      | —              | —   | 17     | —       | —      | 79.2   | —      | —      |
|               | P                     | P                | 1425 0925 |       | 0924   | —      | —      | —       | —      | —      | —              | —   | —      | —       | —      | —      | —      | —      |
|               | P                     | P                | 1427 0927 |       | 0926   | —      | —      | 88.9    | —      | —      | —              | —   | 22     | —       | —      | 81.2   | —      | —      |
|               | P                     | P                | 1430 0930 |       | 0929   | —      | —      | 88.1    | —      | —      | —              | —   | 27     | —       | —      | 79.5   | —      | —      |
|               | P                     | P                | 1432 0932 |       | 0931   | —      | —      | 82.3    | —      | —      | —              | —   | 22     | —       | —      | 73.4   | —      | —      |
|               | P                     | P                | 1439 0939 |       | 0938   | —      | —      | 94.2    | —      | —      | —              | —   | 30     | —       | —      | 86.8   | —      | —      |
|               | P                     | P                | 1441 0941 |       | 0940   | —      | —      | 90.3    | —      | —      | —              | —   | 26     | —       | —      | 83.5   | —      | —      |
|               | P                     | P                | 1443 0943 |       | 0942   | —      | —      | —       | —      | —      | —              | —   | —      | —       | —      | —      | —      | —      |
|               | P                     | P                | 1445 0945 |       | 0944   | —      | —      | 84.6    | —      | —      | —              | —   | 21     | —       | —      | 76.1   | —      | —      |
|               | P                     | P                | 1448 0948 |       | 0947   | —      | —      | 86.7    | —      | —      | —              | —   | 29     | —       | —      | 78.4   | —      | —      |
|               | P                     | P                | 1450 0950 |       | 0949   | —      | —      | —       | —      | —      | —              | —   | —      | —       | —      | —      | —      | —      |
|               | P                     | P                | 1454 0954 |       | 0953   | —      | —      | 81.7    | —      | —      | —              | —   | 24     | —       | —      | 73.0   | —      | —      |
|               | P                     | P                | 1456 0956 |       | 0955   | —      | —      | 88.1    | —      | —      | —              | —   | 54     | —       | —      | 74.5   | —      | —      |
|               | P                     | P                | 1459 0959 |       | 0958   | —      | —      | —       | —      | —      | —              | —   | —      | —       | —      | —      | —      | —      |
|               | P                     | P                | 1502 1002 |       | 1001   | —      | —      | —       | —      | —      | —              | —   | —      | —       | —      | —      | —      | —      |
|               | P                     | P                | 1506 1006 |       | 1005   | —      | —      | —       | —      | —      | —              | —   | —      | —       | —      | —      | —      | —      |
|               | P                     | P                | 1509 1009 |       | 1008   | —      | —      | —       | —      | —      | —              | —   | —      | —       | —      | —      | —      | —      |
|               | P                     | P                | 1513 1013 |       | 1012   | —      | —      | —       | —      | —      | —              | —   | —      | —       | —      | —      | —      | —      |
|               | P                     | P                | 1514 1014 |       | 1013   | —      | —      | —       | —      | —      | —              | —   | —      | —       | —      | —      | —      | —      |

\*Approach - SI - Straight In      +Takeoff      SO - Straight Out      R - Right Turn Departure  
P - Pattern      L - Left Turn Departure

TABLE A-11

AIRCRAFT TOWER LOG AND NOISE  
MONITOR DATA TABULATION FORM

NOISE MONITOR DATA TABULATION FORM EXTENSION, THREE SITES

BAFB

Installation

Date 7 June 78

Runway(s) 32

| Aircraft Type | Operation | Time |       | Time   |        |        | SEL, dB |        |        | Duration, sec. |        |        | MAX, dB |        |        |
|---------------|-----------|------|-------|--------|--------|--------|---------|--------|--------|----------------|--------|--------|---------|--------|--------|
|               |           | GMT  | Local | Site 1 | Site 2 | Site 3 | Site 1  | Site 2 | Site 3 | Site 1         | Site 2 | Site 3 | Site 1  | Site 2 | Site 3 |
|               |           |      |       |        |        |        |         |        |        |                |        |        |         |        |        |
| KC 135A       |           |      |       |        |        |        |         |        |        |                |        |        |         |        |        |
| B 52 G        |           |      |       |        |        |        |         |        |        |                |        |        |         |        |        |
| A-37          |           |      |       |        |        |        |         |        |        |                |        |        |         |        |        |
| T-37          |           |      |       |        |        |        |         |        |        |                |        |        |         |        |        |
| T-38          |           |      |       |        |        |        |         |        |        |                |        |        |         |        |        |
| T-39          |           |      |       |        |        |        |         |        |        |                |        |        |         |        |        |
| C-130         |           |      |       |        |        |        |         |        |        |                |        |        |         |        |        |
| Other         |           |      |       |        |        |        |         |        |        |                |        |        |         |        |        |
|               | P         | 1516 | 1016  |        |        |        |         |        |        |                |        |        |         |        |        |
|               | P         | 1518 | 1018  |        |        |        |         |        |        |                |        |        |         |        |        |
|               | P         | 1520 | 1020  |        |        |        |         |        |        |                |        |        |         |        |        |
|               | P         | 1521 | 1021  |        |        |        |         |        |        |                |        |        |         |        |        |
|               | IN        | 1523 | 1023  |        |        |        |         |        |        |                |        |        |         |        |        |
|               | P         | 1524 | 1024  |        |        |        |         |        |        |                |        |        |         |        |        |
|               | P         | 1527 | 1027  |        |        |        |         |        |        |                |        |        |         |        |        |
|               | P         | 1529 | 1029  |        |        |        |         |        |        |                |        |        |         |        |        |
|               | P         | 1531 | 1031  |        |        |        |         |        |        |                |        |        |         |        |        |
|               | IN        | 1533 | 1033  |        |        |        |         |        |        |                |        |        |         |        |        |
|               | P         | 1534 | 1034  |        |        |        |         |        |        |                |        |        |         |        |        |
|               | P         | 1537 | 1037  |        |        |        |         |        |        |                |        |        |         |        |        |
|               | P         | 1540 | 1040  |        |        |        |         |        |        |                |        |        |         |        |        |
|               | P         | 1545 | 1045  |        |        |        |         |        |        |                |        |        |         |        |        |
|               | P         | 1547 | 1047  |        |        |        |         |        |        |                |        |        |         |        |        |
|               | P         | 1600 | 1100  |        |        |        |         |        |        |                |        |        |         |        |        |
|               | P         | 1629 | 1124  |        |        |        |         |        |        |                |        |        |         |        |        |
|               | P         | 1634 | 1134  |        |        |        |         |        |        |                |        |        |         |        |        |
|               | P         | 1636 | 1136  |        |        |        |         |        |        |                |        |        |         |        |        |
|               | P         | 1637 | 1137  |        |        |        |         |        |        |                |        |        |         |        |        |
|               | P         | 1645 | 1145  |        |        |        |         |        |        |                |        |        |         |        |        |
|               | P         | 1648 | 1148  |        |        |        |         |        |        |                |        |        |         |        |        |
|               | P         | 1717 | 1217  |        |        |        |         |        |        |                |        |        |         |        |        |
|               | P         | 1718 | 1218  |        |        |        |         |        |        |                |        |        |         |        |        |
|               | P         | 1719 | 1219  |        |        |        |         |        |        |                |        |        |         |        |        |
|               | P         | 1723 | 1223  |        |        |        |         |        |        |                |        |        |         |        |        |
|               | P         | 1725 | 1225  |        |        |        |         |        |        |                |        |        |         |        |        |
|               | P         | 1728 | 1228  |        |        |        |         |        |        |                |        |        |         |        |        |
|               | P         | 1730 | 1230  |        |        |        |         |        |        |                |        |        |         |        |        |

\*Approach - S1 - Straight In P - Pattern  
 +Takeoff S0 - Straight Out R - Right Turn Departure L - Left Turn Departure  
 P - Pattern

TABLE A-17

AIRCRAFT TOWER LOG AND NOISE  
MONITOR DATA TABULATION FORM

NOISE MONITOR DATA TABULATION FORM EXTENSION, THREE SITES

|              |        |
|--------------|--------|
| Installation | BAFB   |
| Date         | 7 June |
| Runway(s)    | 32     |

[illegible]

\*Approach - SI - Straight In  
p - Pattern  
+Takeoff  
S0 - Straight Out  
p - Pattern  
R - Right Turn Departure  
L - Left Turn Departure

TABLE A-11

NOISE MONITOR DATA TABULATION FORM EXTENSION, THREE SITES

AIRCRAFT TOWER LOG AND NOISE  
MONITOR DATA TABULATION FORM

| Aircraft Type | Operation | Time     |      | Time |       |      | SEL, dB |      |   | Duration, sec. |      |      | MAX, dB |      |      |
|---------------|-----------|----------|------|------|-------|------|---------|------|---|----------------|------|------|---------|------|------|
|               |           | Approach | T/O* | Time |       | Site | Site    | Site | Δ | Site           | Site | Site | Site    | Site | Site |
|               |           |          |      | GMT  | Local |      |         |      |   |                |      |      |         |      |      |
| KC 135A       |           |          |      |      |       | 1    | 2       | 3    |   |                |      |      |         |      |      |
| B 52 G        |           |          |      |      |       |      |         |      |   |                |      |      |         |      |      |
| A-37          |           |          |      |      |       |      |         |      |   |                |      |      |         |      |      |
| T-37          |           |          |      |      |       |      |         |      |   |                |      |      |         |      |      |
| T-38          |           |          |      |      |       |      |         |      |   |                |      |      |         |      |      |
| T-39          |           |          |      |      |       |      |         |      |   |                |      |      |         |      |      |
| C-130         |           |          |      |      |       |      |         |      |   |                |      |      |         |      |      |
| Other         |           |          |      |      |       |      |         |      |   |                |      |      |         |      |      |
|               | P         |          |      | 1931 | 1431  |      |         |      |   |                |      |      |         |      |      |
|               | P         |          |      | 1933 | 1433  |      |         |      |   |                |      |      |         |      |      |
|               | P         |          |      | 1938 | 1438  |      |         |      |   |                |      |      |         |      |      |
|               | IN        |          |      | 1940 | 1440  |      |         |      |   |                |      |      |         |      |      |
|               | OUT       |          |      | 1944 | 1444  |      |         |      |   |                |      |      |         |      |      |
|               | OUT       |          |      | 1953 | 1453  |      |         |      |   |                |      |      |         |      |      |
|               | P         |          |      | 1958 | 1458  |      |         |      |   |                |      |      |         |      |      |
|               | P         |          |      | 2004 | 1504  |      |         |      |   |                |      |      |         |      |      |
|               | P         |          |      | 2009 | 1509  |      |         |      |   |                |      |      |         |      |      |
|               | P         |          |      | 2009 | 1509  |      |         |      |   |                |      |      |         |      |      |
|               | P         |          |      | 2012 | 1512  |      |         |      |   |                |      |      |         |      |      |
|               | P         |          |      | 2018 | 1518  |      |         |      |   |                |      |      |         |      |      |
|               | P         |          |      | 2022 | 1522  |      |         |      |   |                |      |      |         |      |      |
|               | P         |          |      | 2026 | 1526  |      |         |      |   |                |      |      |         |      |      |
|               | P         |          |      | 2027 | 1527  |      |         |      |   |                |      |      |         |      |      |
|               | P         |          |      | 2033 | 1533  |      |         |      |   |                |      |      |         |      |      |
|               | IN        |          |      | 2035 | 1535  |      |         |      |   |                |      |      |         |      |      |
|               | P         |          |      | 2040 | 1540  |      |         |      |   |                |      |      |         |      |      |
|               | P         |          |      | 2047 | 1547  |      |         |      |   |                |      |      |         |      |      |
|               | P         |          |      | 2048 | 1548  |      |         |      |   |                |      |      |         |      |      |
|               | P         |          |      | 2052 | 1552  |      |         |      |   |                |      |      |         |      |      |
|               | IN        |          |      | 2054 | 1554  |      |         |      |   |                |      |      |         |      |      |
|               | P         |          |      | 2056 | 1556  |      |         |      |   |                |      |      |         |      |      |
|               | OUT       |          |      | 2101 | 1601  |      |         |      |   |                |      |      |         |      |      |
|               | P         |          |      | 2106 | 1606  |      |         |      |   |                |      |      |         |      |      |
|               | P         |          |      | 2115 | 1615  |      |         |      |   |                |      |      |         |      |      |
|               | IN        |          |      | 2120 | 1620  |      |         |      |   |                |      |      |         |      |      |
|               | IN        |          |      | 2134 | 1634  |      |         |      |   |                |      |      |         |      |      |
|               | P         |          |      | 2159 | 1659  |      |         |      |   |                |      |      |         |      |      |
|               | P         |          |      | 2209 | 1709  |      |         |      |   |                |      |      |         |      |      |

\*Approach - SI - Straight In  
P - Pattern  
+Takeoff  
SO - Straight Out  
P - Pattern  
R - Right Turn Departure  
L - Left Turn Departure

TABLE A-11

AIRCRAFT TOWER LOG AND NOISE  
MONITOR DATA TABULATION FORM

NOISE MONITOR DATA TABULATION FORM EXTENSION, THREE SITES

Installation BAFB  
Date 7 June 78  
Runway(s)

| Aircraft Type |       | Operation |      | Time |        | SEL, dB |        |        |        |        |        | Duration, sec. |       |        |        |        |        | MAX, dB |        |      |
|---------------|-------|-----------|------|------|--------|---------|--------|--------|--------|--------|--------|----------------|-------|--------|--------|--------|--------|---------|--------|------|
|               |       | Approch   | T/O* | GMT  | Local  | Site 1  | Site 2 | Site 3 | Site 1 | Site 2 | Site 3 | Δ 1-2          | Δ 3-2 | Site 1 | Site 2 | Site 3 | Site 1 | Site 2  | Site 3 |      |
|               |       |           |      |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| KC 135A       | Other | ✓         | P    | 2213 | 1713   |         | 171518 | 171530 | 171535 | 112.9  | 103.5  | 93.0           | 9.4   | -10.5  | 59     | 49     | 52     | 106.6   | 95.0   | 84.8 |
|               |       | ✓         | IN   | 2215 | 1715   |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
|               |       | ✓         | IN   | 2218 | 1718   |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
|               |       | ✓         | P    | 2220 | 1720   |         | 172234 | 172239 |        | 92.8   | 86.8   |                | 12    |        | 33     | 22     |        | 83.7    | 71.7   |      |
|               |       | ✓         | P    | 2222 | 1722   |         | 172432 | 172438 | 172440 | 98.5   | 88.1   | 85.3           | 10.4  | -2.8   | 74     | 50     | 36     | 87.2    | 77.5   | 77.3 |
|               |       | ✓         | P    | 2224 | 1724   |         | 172625 | 172634 | 172639 | 71.9   | 70.0   | 78.1           | 1.9   | 8.1    | 9      | 7      | 10     | 63.2    | 63.1   | 72.8 |
|               |       | ✓         | P    | 2227 | 1727   |         | 172830 | 172834 |        | 85.7   | 76.2   |                | 10.5  |        | 27     | 10     |        | 77.6    | 70.0   |      |
|               |       | ✓         | P    | 2230 | 1730   |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
|               |       | ✓         | P    | 2232 | 1732   |         | 17342  |        |        | 92.9   |        |                |       |        | 33     |        |        | 83.2    |        |      |
|               |       | ✓         | P    | 2235 | 1735   |         | 173806 | 173810 | 173812 | 96.6   | 88.0   | 81.8           | 8.6   | -6.2   | 71     | 39     | 31     | 86.9    | 77.9   | 72.8 |
|               |       | ✓         | P    | 2238 | 1738   |         | 174040 | 174049 | 174053 | 113.3  | 101.1  | 91.0           | 12.2  | -10.1  | 60     | 44     | 40     | 106.4   | 92.0   | 82.4 |
|               |       | ✓         | P    | 2241 | 1741   |         | 174139 |        |        | 78.5   |        |                |       |        | 22     |        |        | 71.4    |        |      |
|               |       | ✓         | IN   | 2246 | 1746   |         | 175146 | 175157 | 175150 | 88.9   | 81.4   | 76.1           | 7.5   | -5.3   | 36     | 25     | 19     | 78.8    | 71.2   | 65.5 |
|               |       | ✓         | P    | 2249 | 1749   |         | 175410 | 175422 | 175429 | 112.7  | 106.1  | 96.6           | 6.6   | -9.5   | 70     | 52     | 49     | 104.8   | 96.6   | 86.5 |
|               |       | ✓         | P    | 2252 | 1752   |         | 175706 | 175722 |        | 88.1   | 77.6   |                | 10.5  |        | 39     | 19     |        | 78.3    | 69.5   |      |
|               |       | ✓         | P    | 2255 | 1755   |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | P     | 2258      | 1758 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | P     | 2259      | 1759 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2306      | 1806 |      | 180840 | 180856  | 180859 | 100.8  | 91.6   | 86.2   | 9.2    | -5.4           | 37    | 41     | 43     | 94.5   | 90.4   | 76.8    |        |      |
| ✓             | IN    | 2307      | 1807 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2315      | 1815 |      | 182018 | 182024  | 182032 | 115.9  | 113.2  | 104.1  | 12.7   | -9.1           | 75    | 78     | 78.5   | 106.2  | 102.9  | 92.8    |        |      |
| ✓             | P     | 2318      | 1818 |      | 182441 | 182448  | 182449 | 104.0  | 92.3   | 87.3   | 11.7   | -5             | 47    | 40     | 37     | 94.5   | 82.4   | 77.4    |        |      |
| ✓             | P     | 2322      | 1822 |      | 182812 | 182818  | 182824 | 116.0  | 113.8  | 102.3  | 2.2    | -11.5          | 62    | 69     | 67     | 105.7  | 107.3  | 89.7    |        |      |
| ✓             | P     | 2325      | 1825 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2325      | 1825 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2338      | 1838 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2343      | 1843 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2358      | 1858 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2400      | 1900 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2406      | 1906 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2407      | 1907 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2408      | 1908 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2409      | 1909 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2410      | 1910 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2411      | 1911 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2412      | 1912 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2413      | 1913 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2414      | 1914 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2415      | 1915 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2416      | 1916 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2417      | 1917 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2418      | 1918 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2419      | 1919 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2420      | 1920 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2421      | 1921 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2422      | 1922 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2423      | 1923 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2424      | 1924 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2425      | 1925 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2426      | 1926 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2427      | 1927 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2428      | 1928 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2429      | 1929 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2430      | 1930 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2431      | 1931 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2432      | 1932 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2433      | 1933 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2434      | 1934 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2435      | 1935 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2436      | 1936 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2437      | 1937 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2438      | 1938 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2439      | 1939 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2440      | 1940 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2441      | 1941 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2442      | 1942 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2443      | 1943 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2444      | 1944 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2445      | 1945 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2446      | 1946 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2447      | 1947 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2448      | 1948 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2449      | 1949 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2450      | 1950 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2451      | 1951 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2452      | 1952 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2453      | 1953 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2454      | 1954 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2455      | 1955 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2456      | 1956 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2457      | 1957 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2458      | 1958 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2459      | 1959 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2500      | 2000 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2501      | 2001 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2502      | 2002 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2503      | 2003 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2504      | 2004 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2505      | 2005 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2506      | 2006 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2507      | 2007 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2508      | 2008 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2509      | 2009 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2510      | 2010 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2511      | 2011 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2512      | 2012 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2513      | 2013 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2514      | 2014 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2515      | 2015 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2516      | 2016 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2517      | 2017 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2518      | 2018 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2519      | 2019 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2520      | 2020 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2521      | 2021 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2522      | 2022 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2523      | 2023 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2524      | 2024 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2525      | 2025 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2526      | 2026 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2527      | 2027 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2528      | 2028 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2529      | 2029 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2530      | 2030 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2531      | 2031 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2532      | 2032 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2533      | 2033 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2534      | 2034 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |
| ✓             | IN    | 2535      | 2035 |      |        |         |        |        |        |        |        |                |       |        |        |        |        |         |        |      |

\*Approach - SI - Straight In      +Takeoff      SO - Straight Out      R - Right Turn Departure  
 P - Pattern      L - Left Turn Departure

BAFB

Installation  
Date

7 June 78

Runway(s)

32

TABLE A-11

NOISE MONITOR DATA TABULATION FORM EXTENSION, THREE SITES

AIRCRAFT TOWER LOG AND NOISE  
MONITOR DATA TABULATION FORM

Table D-3

| Table D-3   |        |      |           |      |      |       |       |         |       |         |       |        |                |        |   |         |        |        |        |        |        |        |        |        |        |
|---|--------|------|-----------|------|------|-------|-------|---------|-------|---------|-------|--------|----------------|--------|---|---------|--------|--------|--------|--------|--------|--------|--------|--------|--------|
| Aircraft Type   |        |      | Operation |      | Time |       | Time  |         |       | SEL, dB |       |        | Duration, sec. |        |   | MAX, dB |        |        |        |        |        |        |        |        |        |
| KC 135A   | B 52 G | A-37 | T-37      | T-38 | T-39 | C-130 | Other | Approch | T/O*  | GMT     | Local | Site 1 | Site 2         | Site 3 | Δ | Δ       | Site 1 | Site 2 | Site 3 | Site 1 | Site 2 | Site 3 | Site 1 | Site 2 | Site 3 |
|   |        |      |           |      |      |       |       |         |       |         |       |        |                |        |   |         |        |        |        |        |        |        |        |        |        |
| ✓   |        |      |           |      |      |       | C-150 | IN      |       | 0020    | 1920  |        |                |        |   |         |        |        |        |        |        |        |        |        |        |
| ✓   |        |      |           |      |      |       |       | IN      |       | 0035    | 1935  |        |                |        |   |         |        |        |        |        |        |        |        |        |        |
|   |        |      |           |      |      |       |       |         | OUT   | 0056    | 1956  |        |                |        |   |         |        |        |        |        |        |        |        |        |        |
|   |        |      |           |      |      |       |       |         | OUT   | 0105    | 2005  |        |                |        |   |         |        |        |        |        |        |        |        |        |        |
|   |        |      |           |      |      |       |       |         | OUT   | 0112    | 2012  |        |                |        |   |         |        |        |        |        |        |        |        |        |        |
|   |        |      |           |      |      |       |       | P       | P     | 0150    | 2050  |        |                |        |   |         |        |        |        |        |        |        |        |        |        |
|   |        |      |           |      |      |       |       | P       | P     | 0155    | 2055  |        |                |        |   |         |        |        |        |        |        |        |        |        |        |
|   |        |      |           |      |      |       |       | P       | P     | 0202    | 2102  |        |                |        |   |         |        |        |        |        |        |        |        |        |        |
|   |        |      |           |      |      |       |       | IN      | IN    | 0203    | 2103  |        |                |        |   |         |        |        |        |        |        |        |        |        |        |
|   |        |      |           |      |      |       |       | IN      | IN    | 0205    | 2105  |        |                |        |   |         |        |        |        |        |        |        |        |        |        |
|   |        |      |           |      |      |       |       | IN      | IN    | 0328    | 2228  |        |                |        |   |         |        |        |        |        |        |        |        |        |        |
|   |        |      |           |      |      |       |       | OUT     | OUT   | 0400    | 2300  |        |                |        |   |         |        |        |        |        |        |        |        |        |        |
| 0   | 0      | 11   | 2         | 0    | 0    | 11    | 1     | 25      | -     | DAY     |       |        |                |        |   |         |        |        |        |        |        |        |        |        |        |
| 2   | 7      | 0    | 0         | 0    | 0    | 1     | 0     | 10      | -     | NIGHT   |       |        |                |        |   |         |        |        |        |        |        |        |        |        |        |
| 28  | 15     | 27   | 0         | 0    | 2    | 21    | 17    | -       | 93    | DAY     |       |        |                |        |   |         |        |        |        |        |        |        |        |        |        |
| 0   | 0      | 0    | 0         | 1    | 0    | 0     | 0     | -       | 1     | NIGHT   |       |        |                |        |   |         |        |        |        |        |        |        |        |        |        |
| 15  | 12     | 1    | 1         | 1    | 1    | 1     | 1     | 123.5   | 123.5 | DAY     |       |        |                |        |   |         |        |        |        |        |        |        |        |        |        |
| 1   | 6      | 1    | 1         | 1    | 1    | 1     | 1     | 23.5    | 23.5  | NIGHT   |       |        |                |        |   |         |        |        |        |        |        |        |        |        |        |
| TOTALS  |        |      |           |      |      |       |       |         |       |         |       |        |                |        |   |         |        |        |        |        |        |        |        |        |        |
| 230141 230149 230156 91.2 91.2 73.5 17.7 -7.7 39 29 17 80.6 70.3 62.1 |        |      |           |      |      |       |       |         |       |         |       |        |                |        |   |         |        |        |        |        |        |        |        |        |        |
| APPROACH OVER NORTHERN MEASUREMENT SITE                               |        |      |           |      |      |       |       |         |       |         |       |        |                |        |   |         |        |        |        |        |        |        |        |        |        |
| PATTERN OVER EAST RESERVATION   |        |      |           |      |      |       |       |         |       |         |       |        |                |        |   |         |        |        |        |        |        |        |        |        |        |

\*Approach - SI - Straight In  
P - Pattern  
+Takeoff  
SO - Straight Out  
P - Pattern  
R - Right Turn Departure  
L - Left Turn Departure

- Checking for consistent time differences: The time delay between tower events and monitor unit events was approximately 2.5 minutes for takeoffs and approximately (-)1.0 minute for approaches. The difference in time delays is attributed to the logging procedure used in the tower. Takeoffs and approaches were listed in anticipation of passing in front of the tower. This relieved the tower personnel to concern themselves with the next operation instead of waiting after clearance to land or takeoff was given.
- On the first pass through the data, identifying only the loudest aircraft, in this case B-52G and KC-135A. The loudest aircraft are both the easiest to identify and the dominant contributors to average day DNL levels.
- Verifying that the SEL level and duration are both consistent with other results from the same type operation.

#### TABULATION AND AVERAGING OF SEL VALUES

Next, the SEL values were summarized by aircraft as shown in Table A-12. For the heavy aircraft, the SEL events were divided into four categories:

Straight-in Approaches  
Pattern Approaches  
Pattern Takeoffs  
Straight-out Takeoffs.

For the smaller aircraft, the SEL events were divided into only two categories:

Approaches  
Takeoffs.

In Table A-12, the SEL values for each type of aircraft operation are correlated from site to site. For example, the first entry for site 1, 102.9, is for the same straight-in KC-135A approach as the first entry for site 2, 99.6 dB. At site 3, the portable noise level monitor unit was not operational at that time because of the aforementioned paper jam. This bookkeeping technique is helpful in critiquing the results. In Table A-12, dashes represent events which did not

1

NES

10

TABLE A-12 MEASURED SEL TABULATION FORM, SITE 2

| AC - KC 135A |       |       |       | AC - B52G |       |       |       | AC - A-37 |      | AC - T-37 |      | AC - T-38 |      |
|--------------|-------|-------|-------|-----------|-------|-------|-------|-----------|------|-----------|------|-----------|------|
| Approach     |       | T/O   |       | Approach  |       | T/O   |       | Approach  | T/O  | Approach  | T/O  | Approach  | T/O  |
| SI           | Patt  | Pat   | SO    | SI        | Pat   | Pat   | SO    |           |      |           |      |           |      |
| 99.6         | 77.9  | 83.9  | 115.0 | 96.3      | 100.7 | 97.1  | 109.4 | —         | 76.1 | 81.1      | 91.1 | —         | 89.6 |
| 94.5         | 77.9  | 106.6 | 113.3 | 97.8      | 96.1  | 80.5  | 113.2 | —         | 79.1 | 73.6      | —    | —         | —    |
| 94.0         | 99.3  | 93.8  | 108.5 | 99.4      | 76.8  | 84.3  | 113.8 | —         | 78.7 | 72.5      | 81.4 | —         | 89.5 |
| 94.9         | 92.7  | 93.1  | 112.8 | 96.7      | 89.7  | 105.9 | 104.1 | —         | 91.3 | 77.7      | 92.7 | 81.3      | 91.9 |
| 95.2         | —     | 83.1  | 99.1  | 96.5      | 74.8  | 103.5 | 112.6 | —         | 92.5 | —         | 84.9 | 73.2      | 83.1 |
| 97.0         | 86.6  | 85.8  | 98.7  | 95.1      | 77.8  | 80.8  | 110.9 | —         | —    | 74.5      | 82.6 | 81.7      | 92.2 |
| 97.3         | 82.9  | 78.3  | 113.7 | 94.0      | 87.2  | 76.2  | 114.8 | —         | 80.0 | 71.5      | —    | 81.5      | 81.0 |
| 96.5         | 95.0  | 76.3  | 108.0 | 95.1      | 95.0  | —     | 113.3 | —         | 70.0 | 81.0      | 88.7 | 76.4      | —    |
| 100.3        | 82.9  | 80.4  | 107.2 | 95.2      | 100.0 | 98.7  | 114.0 | —         | 92.6 | —         | 88.8 | 84.0      | 88.6 |
| 94.4         | —     | 86.3  | 111.7 | 98.0      | 100.7 | 101.1 | 114.8 | —         | 89.8 | 76.5      | —    | —         | —    |
| 88.9         | 85.0  | 82.0  | 108.0 | 97.6      | 96.7  | 106.1 | 118.5 | 86.9      | 91.1 | 79.8      | —    | 78.8      | —    |
| 82.5         | 94.7  | 88.1  | 116.4 | 98.0      | 100.0 | 81.6  | 111.0 | 90.7      | 84.4 | 81.9      | —    | 79.8      | 87.9 |
| 96.7         | 76.8  | 88.0  | 105.9 | —         | 95.0  | 82.3  | 108.4 | 90.4      | 89.0 | 80.1      | 92.0 | 81.3      | —    |
| 72.6         | 88.5  | 86.7  | 108.8 | 98.8      | 72.3  | 76.6  | 113.3 | 76.3      | 79.7 | 80.1      | 96.7 | 69.5      | —    |
| 74.8         | 92.7  | 81.0  | 114.7 | 94.4      | 88.7  | 105.9 | 109.3 | —         | 84.6 | 78.6      | 90.0 | 78.3      | —    |
| 95.3         | 94.2  | 88.8  | 96.6  | 84.4      | 100.2 | 91.9  | 113.7 | 74.0      | 90.2 | —         | —    | —         | —    |
| 94.4         | 93.5  | 92.0  | 108.9 | 96.5      | 96.5  | 73.3  | 114.9 | —         | 85.0 | 75.9      | —    | 71.7      | —    |
| 89.0         | —     | 101.3 | 112.0 | 94.0      | 96.2  | 88.2  | 100.8 | —         | 85.2 | 78.4      | —    | 79.3      | —    |
| 94.4         | 71.4  | 93.4  | 91.9  | 95.1      | 99.2  | 87.4  | 107.6 | —         | 94.0 | —         | —    | 83.6      | —    |
| 96.9         | 75.5  | 113.2 | 100.4 | 95.2      | 99.0  | 85.7  | 115.0 | 80.6      | 91.4 | 76.4      | —    | 86.5      | —    |
| 95.1         | 95.9  | 85.8  | 117.9 | 98.6      | —     | 71.4  | 113.9 | —         | 90.2 | 86.1      | —    | 82.1      | —    |
| 73.2         | 94.6  | 75.5  | 104.5 | —         | 98.8  | 85.8  | 111.8 | 78.3      | —    | 77.9      | —    | 81.0      | —    |
| 82.5         | 88.5  | 91.1  | 108.2 | —         | 94.4  | 76.0  | 114.6 | 73.3      | 81.8 | —         | —    | 81.1      | —    |
| 94.4         | 84.1  | —     | 105.9 | —         | 84.8  | 83.8  | 110.4 | 68.6      | 93.1 | 74.7      | —    | 80.0      | —    |
| 88.9         | 95.3  | 86.1  | 114.4 | —         | 96.5  | 81.5  | 114.8 | 77.5      | 91.0 | 70.4      | —    | 74.7      | —    |
| 89.5         | 87.1  | 88.9  | 109.7 | —         | 97.8  | 65.5  | 114.8 | 82.9      | —    | 78.0      | —    | —         | —    |
| 72.6         | 88.8  | 73.9  | 116.3 | —         | 97.1  | 69.9  | 110.4 | 80.0      | 80.8 | 73.9      | —    | 78.2      | —    |
| 74.8         | 93.1  | —     | 105.8 | —         | 94.0  | —     | —     | 79.1      | 87.6 | —         | —    | 79.8      | —    |
| 94.4         | 88.2  | 88.1  | 106.6 | —         | 96.8  | 66.0  | —     | 77.9      | 97.1 | 73.1      | —    | 97.6      | —    |
| 96.9         | 82.4  | —     | 114.0 | —         | 96.6  | 104.5 | —     | 84.0      | 97.4 | 81.2      | —    | 77.3      | —    |
| 95.4         | 108.1 | 78.0  | 109.0 | —         | 95.2  | 111.5 | —     | 78.0      | 94.0 | 72.8      | —    | 85.4      | —    |
| 89.2         | 98.4  | —     | 108.8 | —         | 94.8  | 105.5 | —     | 87.9      | 94.5 | 73.4      | —    | 84.8      | —    |
| 94.8         | 98.8  | —     | 109.9 | —         | 91.2  | 106.9 | —     | 78.9      | 87.1 | 76.2      | —    | 95.0      | —    |
| 88.4         | 100.7 | 94.2  | 108.8 | —         | 95.5  | 100.3 | —     | 78.8      | 87.4 | 73.9      | —    | 85.4      | —    |
| 95.0         | 97.0  | 81.7  | 104.9 | —         | 95.8  | 101.0 | —     | 80.8      | 98.0 | 71.2      | —    | 99.4      | —    |
| 93.9         | 95.7  | 96.3  | —     | —         | 86.9  | 96.8  | —     | 83.6      | 86.0 | 76.5      | —    | 82.6      | —    |
| 94.9         | 76.0  | 77.9  | —     | —         | 96.0  | 106.2 | —     | 85.9      | 94.9 | —         | —    | 92.1      | —    |
| 96.9         | 98.0  | 72.6  | —     | —         | 97.4  | 93.5  | —     | 81.4      | 87.8 | —         | —    | —         | —    |
| 95.1         | 84.4  | 96.8  | —     | —         | 98.4  | 87.2  | —     | 78.4      | 95.5 | —         | —    | 86.0      | —    |
| 73.2         | 94.6  | 85.3  | —     | —         | 95.1  | 77.9  | —     | —         | 90.8 | —         | —    | 74.8      | —    |
| 82.5         | 95.8  | 85.3  | —     | —         | 97.2  | 95.0  | —     | 83.8      | 75.6 | —         | —    | 86.8      | —    |
| —            | 95.4  | 101.3 | —     | —         | 95.0  | 83.4  | —     | 82.0      | 86.1 | —         | —    | —         | —    |
| —            | 79.0  | 97.9  | —     | —         | 100.0 | 83.0  | —     | 66.6      | 91.5 | —         | —    | —         | —    |
| —            | 96.9  | 87.0  | —     | —         | 100.7 | 85.9  | —     | 78.6      | 72.8 | —         | —    | —         | —    |
| —            | 95.6  | 86.8  | —     | —         | 96.7  | 88.4  | —     | 75.6      | 71.3 | —         | —    | —         | —    |
| —            | 88.2  | 94.6  | —     | —         | 100.0 | 104.2 | —     | 85.2      | 90.0 | —         | —    | —         | —    |
| —            | 94.8  | 92.6  | —     | —         | 95.0  | 87.1  | —     | 70.2      | 86.8 | —         | —    | —         | —    |
| —            | 95.0  | 92.9  | —     | —         | 92.2  | 70.7  | —     | 88.8      | 75.0 | —         | —    | —         | —    |
| —            | 79.8  | —     | —     | —         | 98.7  | 72.3  | —     | 80.2      | —    | —         | —    | —         | —    |
| —            | 99.0  | —     | —     | —         | 100.2 | 103.8 | —     | 81.0      | 80.8 | —         | —    | —         | —    |

N - Number of Measurements; E - Energy Avg., dB; S - Energy Standard Deviation,  $\times 10^{10}$

TABLE A-12 MEASURED SEL TABULATION FORM, SITE 2(continued)

| AC - KC 135A |       |      |      | AC - B52G |      |         |       | AC - A-37 |       | AC - T-37 |      | AC - T-38 |      |      |
|--------------|-------|------|------|-----------|------|---------|-------|-----------|-------|-----------|------|-----------|------|------|
| Approach     |       | T/O  |      | Approach  |      | T/O     |       | Approach  | T/O   | Approach  | T/O  | Approach  | T/O  |      |
| SI           | Patt  | Pat  | SO   | SI        | Pat  | Pat     | SO    |           |       |           |      |           |      |      |
|              | 99.6  |      |      |           | 96.5 | 103.8   |       | 86.9      | 71.5  |           |      |           |      |      |
|              | 87.0  |      |      |           | 96.2 | 87.4    |       | 82.5      | —     |           |      |           |      |      |
|              | —     |      |      |           | 99.2 | 97.0    |       | 75.0      | 101.5 |           |      |           |      |      |
|              | 94.1  |      |      |           | .0   | —       |       | 87.5      | —     |           |      |           |      |      |
|              | 86.4  |      |      |           | 97.8 | 82.1    |       | 72.8      | 92.7  |           |      |           |      |      |
|              | 94.7  |      |      |           | 97.1 | 82.2    |       | 87.8      | 95.9  |           |      |           |      |      |
|              | 95.2  |      |      |           | 94.0 | 89.6    |       | 81.5      | 92.5  |           |      |           |      |      |
|              | 92.1  |      |      |           | 96.8 | 87.6    |       | —         | 92.0  |           |      |           |      |      |
|              | 87.4  |      |      |           | 96.6 | 74.0    |       | —         | 82.8  |           |      |           |      |      |
|              | 93.6  |      |      |           | 95.2 | 86.3    |       | —         | 89.0  |           |      |           |      |      |
|              | 95.7  |      |      |           | 94.8 | 106.7   |       | —         |       |           |      |           |      |      |
|              | 96.6  |      |      |           | 91.2 | 88.8    |       | 90.2      |       |           |      |           |      |      |
|              | 94.9  |      |      |           | 95.8 | 85.4    |       | 98.6      |       |           |      |           |      |      |
|              | 95.5  |      |      |           | 95.5 | 104.9   |       | 78.9      |       |           |      |           |      |      |
|              | 95.8  |      |      |           | 86.9 | 82.7    |       | 77.5      |       |           |      |           |      |      |
|              | 94.6  |      |      |           | 96.0 | 84.2    |       |           |       |           |      |           |      |      |
|              | 89.5  |      |      |           | 97.4 | 83.1    |       |           |       |           |      |           |      |      |
|              | 84.1  |      |      |           | 98.4 | 86.5    |       |           |       |           |      |           |      |      |
|              | 97.0  |      |      |           | 99.0 | 89.3    |       |           |       |           |      |           |      |      |
|              | 96.7  |      |      |           |      | 108.8   |       |           |       |           |      |           |      |      |
|              | 93.3  |      |      |           |      | 88.9    |       |           |       |           |      |           |      |      |
|              | 87.1  |      |      |           |      | 85.7    |       |           |       |           |      |           |      |      |
|              | 88.8  |      |      |           |      | 76.0    |       |           |       |           |      |           |      |      |
|              | 93.1  |      |      |           |      | 81.6    |       |           |       |           |      |           |      |      |
|              | 89.2  |      |      |           |      | 85.4    |       |           |       |           |      |           |      |      |
|              | 82.4  |      |      |           |      | 95.9    |       |           |       |           |      |           |      |      |
|              | 108.1 |      |      |           |      | 84.8    |       |           |       |           |      |           |      |      |
|              | 98.4  |      |      |           |      | 70.5    |       |           |       |           |      |           |      |      |
|              | 99.8  |      |      |           |      | 81.9    |       |           |       |           |      |           |      |      |
|              | 100.7 |      |      |           |      | 95.5(2) |       |           |       |           |      |           |      |      |
|              | 96.0  |      |      |           |      |         |       |           |       |           |      |           |      |      |
|              | 95.7  |      |      |           |      |         |       |           |       |           |      |           |      |      |
|              | 76.0  |      |      |           |      |         |       |           |       |           |      |           |      |      |
|              | 88.0  |      |      |           |      |         |       |           |       |           |      |           |      |      |
|              | 94.4  |      |      |           |      |         |       |           |       |           |      |           |      |      |
|              | 94.6  |      |      |           |      |         |       |           |       |           |      |           |      |      |
|              | 95.8  |      |      |           |      |         |       |           |       |           |      |           |      |      |
|              | 95.4  |      |      |           |      |         |       |           |       |           |      |           |      |      |
|              | 79.0  |      |      |           |      |         |       |           |       |           |      |           |      |      |
|              | 79.9  |      |      |           |      |         |       |           |       |           |      |           |      |      |
|              | 99.0  |      |      |           |      |         |       |           |       |           |      |           |      |      |
|              | 99.6  |      |      |           |      |         |       |           |       |           |      |           |      |      |
|              | 87.0  |      |      |           |      |         |       |           |       |           |      |           |      |      |
|              | —     |      |      |           |      |         |       |           |       |           |      |           |      |      |
|              | 94.1  |      |      |           |      |         |       |           |       |           |      |           |      |      |
|              | 96.4  |      |      |           |      |         |       |           |       |           |      |           |      |      |
|              | 94.7  |      |      |           |      |         |       |           |       |           |      |           |      |      |
|              | 95.2  |      |      |           |      |         |       |           |       |           |      |           |      |      |
|              | 92.1  |      |      |           |      |         |       |           |       |           |      |           |      |      |
|              | 97.4  |      |      |           |      |         |       |           |       |           |      |           |      |      |
| N            | 40    | 100  | 48   | 85        | 21   | 69      | 81    | 28        | 66    | 60        | 36   | 15        | 41   | 12   |
| E            | 94.1  | 95.9 | 92.3 | 111.2     | 96.1 | 96.1    | 100.1 | 112.4     | 89.0  | 91.3      | 77.5 | 89.2      | 87.7 | 87.5 |
| S            | 23    | .91  | 3.1  | 14.5      | .23  | .30     | 2.77  | 17.0      | .09   | .22       | .007 | .12       | .16  | .06  |

N - Number of Measurements; E - Energy Avg., dB; S - Energy Standard Deviation,  $\times 10^{-10}$

(2)

52

0-10

TABLE A-12 MEASURED SEL TABULATION FORM, SITE 202

| AC - KC 135A |       |     |    | AC - B52G |       |      |       | AC - A-37 |      | AC - T-37 |      | AC - T-38 |      |
|--------------|-------|-----|----|-----------|-------|------|-------|-----------|------|-----------|------|-----------|------|
| Approach     |       | T/O |    | Approach  |       | T/O  |       | Approach  | T/O  | Approach  | T/O  | Approach  | T/O  |
| SI           | Patt  | Pat | SO | SI        | Pat   | Pat  | SO    |           |      |           |      |           |      |
| .            | .     | .   | .  | .         | .     | .    | .     | .         | .    | .         | .    | .         | .    |
| .            | .     | .   | .  | .         | .     | .    | .     | .         | .    | .         | .    | .         | .    |
| .            | .     | .   | .  | .         | .     | .    | .     | .         | .    | .         | .    | .         | .    |
| .            | .     | .   | .  | .         | .     | .    | .     | .         | .    | .         | .    | .         | .    |
| .            | .     | .   | .  | .         | .     | .    | .     | .         | .    | .         | .    | .         | .    |
| .            | .     | .   | .  | .         | .     | .    | .     | .         | .    | .         | .    | .         | .    |
| 93.9         | .     | .   | .  | 97.3      | .     | .    | .     | .         | .    | 74.2      | .    | 80.6      | .    |
| 93.5         | .     | .   | .  | 87.1      | 96.0  | .    | .     | .         | .    | .         | 84.0 | 73.4      | .    |
| 94.0         | .     | .   | .  | 96.2      | 99.2  | .    | .     | .         | .    | .         | 74.0 | 78.9      | .    |
| 96.3         | .     | .   | .  | 97.6      | .     | .    | .     | .         | .    | 75.0      | 86.5 | 79.4      | .    |
| 98.1         | .     | .   | .  | 96.6      | .     | .    | .     | .         | .    | .         | 87.5 | 83.9      | 88.3 |
| —            | 93.8  | .   | .  | 100.6     | .     | .    | .     | .         | .    | 70.8      | 84.8 | 77.1      | —    |
| —            | 94.3  | .   | .  | 78.7      | .     | .    | .     | .         | .    | 81.3      | 87.2 | .         | 72.0 |
| 91.0         | —     | .   | .  | 94.7      | 95.1  | .    | .     | .         | .    | 83.3      | 93.7 | .         | 84.3 |
| —            | —     | .   | .  | 104.1     | 95.1  | .    | 107.8 | .         | .    | 78.2      | 89.8 | .         | .    |
| —            | 82.2  | .   | .  | 94.5      | 92.7  | .    | 116.1 | .         | .    | 80.7      | 85.8 | .         | .    |
| 101.5        | 91.4  | .   | .  | 71.4      | 94.3  | .    | 108.6 | .         | .    | .         | 71.5 | .         | .    |
| 95.8         | 72.0  | .   | .  | 101.5     | 94.5  | .    | 113.1 | .         | .    | .         | .    | .         | .    |
| —            | 78.1  | .   | .  | 87.1      | 100.1 | .    | 116.5 | .         | .    | .         | .    | .         | .    |
| —            | —     | .   | .  | 96.2      | 102.9 | .    | 86.6  | .         | .    | .         | .    | .         | .    |
| —            | 71.7  | .   | .  | 95.4      | .     | .    | 102.9 | .         | .    | .         | .    | .         | .    |
| —            | —     | .   | .  | 94.7      | .     | .    | 100.3 | .         | .    | .         | .    | .         | .    |
| —            | —     | .   | .  | 104.1     | .     | .    | 111.3 | .         | .    | .         | .    | .         | .    |
| —            | —     | .   | .  | 91.5      | .     | .    | 109.3 | .         | .    | .         | .    | .         | .    |
| 98.1         | —     | .   | .  | 97.1      | 71.4  | .    | 114.3 | —         | .    | .         | .    | .         | .    |
| —            | 100.2 | .   | .  | 107.4     | 101.5 | .    | 108.3 | —         | .    | .         | .    | .         | .    |
| —            | 96.4  | .   | .  | 108.1     | 95.7  | .    | 109.3 | 80.6      | .    | .         | .    | .         | .    |
| —            | 87.7  | .   | .  | 109.7     | 101.7 | .    | 114.3 | 81.2      | .    | .         | .    | .         | .    |
| —            | 93.3  | .   | .  | 98.9      | —     | .    | 108.1 | —         | .    | .         | .    | .         | .    |
| 95.8         | 88.6  | .   | .  | 91.2      | 98.1  | .    | —     | 69.6      | .    | .         | .    | .         | .    |
| .            | 84.0  | .   | .  | 109.1     | 95.9  | .    | —     | —         | .    | .         | .    | .         | .    |
| .            | 101.0 | .   | .  | 109.0     | —     | .    | —     | 73.5      | .    | .         | .    | .         | .    |
| .            | 96.2  | .   | .  | 108.9     | 97.9  | .    | —     | 81.3      | 89.1 | .         | .    | .         | .    |
| .            | 102.2 | .   | .  | 101.2     | 72.8  | .    | —     | 74.2      | 71.2 | .         | .    | .         | .    |
| .            | 94.7  | .   | .  | 108.9     | —     | .    | —     | 78.4      | —    | .         | .    | .         | .    |
| .            | 93.0  | .   | .  | 101.2     | —     | .    | —     | 83.4      | 87.6 | .         | .    | .         | .    |
| .            | 85.1  | .   | .  | —         | 84.8  | .    | —     | 70.8      | 81.5 | .         | .    | .         | .    |
| .            | 75.4  | .   | .  | —         | 95.3  | .    | —     | 86.5      | 93.0 | .         | .    | .         | .    |
| .            | 90.3  | .   | .  | —         | —     | .    | —     | —         | 87.7 | .         | .    | .         | .    |
| .            | 96.3  | .   | .  | —         | 97.1  | .    | —     | 78.2      | 90.7 | .         | .    | .         | .    |
| .            | 96.0  | .   | .  | —         | 97.3  | .    | —     | 80.3      | 80.0 | .         | .    | .         | .    |
| .            | 93.2  | —   | .  | —         | 96.0  | .    | —     | 74.4      | 74.1 | .         | .    | .         | .    |
| —            | 89.2  | .   | .  | —         | 94.2  | .    | —     | .         | 84.7 | .         | .    | .         | .    |
| 79.1         | 72.8  | .   | .  | —         | 97.6  | .    | —     | .         | —    | .         | .    | .         | .    |
| —            | —     | .   | .  | —         | 96.6  | 75.8 | —     | .         | —    | .         | .    | .         | .    |
| —            | —     | .   | .  | —         | 100.6 | —    | —     | .         | —    | .         | .    | .         | .    |
| —            | —     | .   | .  | —         | 78.7  | 86.1 | —     | .         | 87.0 | .         | .    | .         | .    |
| —            | —     | .   | .  | —         | 95.1  | —    | —     | .         | 84.9 | .         | .    | .         | .    |
| —            | —     | .   | .  | —         | 95.1  | —    | —     | .         | —    | .         | .    | .         | .    |
| —            | —     | .   | .  | —         | 92.7  | —    | —     | .         | 77.9 | .         | .    | .         | .    |
| —            | —     | .   | .  | —         | 94.3  | 84.8 | —     | .         | —    | .         | .    | .         | .    |

N - Number of Measurements; E - Energy Avg., dB; S - Energy Standard Deviation,  $\times 10^{-10}$

TABLE A-12 MEASURED SEL TABULATION FORM, SITE 202 (continued)

NE

N - Number of Measurements; E - Energy Avg., dB; S - Energy Standard Deviation,  $\times 10^{10}$

TABLE A-12 MEASURED SEL TABULATION FORM, SITE 203

| AC - KC 135A |       |     |       | AC - B52G |       |       |       | AC - A-37 |      | AC - T-37 |      | AC - T-38 |      |
|--------------|-------|-----|-------|-----------|-------|-------|-------|-----------|------|-----------|------|-----------|------|
| Approach     |       | T/O |       | Approach  |       | T/O   |       | Approach  | T/O  | Approach  | T/O  | Approach  | T/O  |
| SI           | Patt  | Pat | SO    | SI        | Pat   | Pat   | SO    |           |      |           |      |           |      |
| .            | .     | .   | .     | .         | .     | .     | .     | .         | .    | .         | .    | .         | .    |
| .            | .     | .   | .     | .         | .     | .     | .     | .         | .    | .         | .    | .         | .    |
| .            | .     | .   | .     | .         | .     | .     | .     | .         | .    | .         | .    | .         | .    |
| .            | .     | .   | .     | .         | .     | .     | .     | .         | .    | .         | .    | 82.5      | .    |
| .            | .     | .   | .     | 105.2     | .     | .     | .     | .         | .    | .         | .    | 81.3      | .    |
| .            | .     | .   | .     | 86.2      | 99.5  | .     | .     | .         | .    | 83.9      | 83.9 | 87.3      | .    |
| .            | .     | .   | .     | 99.3      | 107.1 | .     | .     | .         | .    | 84.7      | 81.9 | 85.6      | .    |
| .            | .     | .   | .     | 105.0     | 102.5 | .     | .     | .         | .    | 70.7      | —    | 77.8      | .    |
| 101.1        | .     | .   | .     | 104.7     | 107.7 | .     | .     | .         | .    | —         | —    | 82.4      | 80.5 |
| —            | .     | .   | .     | 103.4     | 70.8  | .     | .     | .         | .    | 83.4      | —    | 89.9      | 74.3 |
| —            | .     | .   | .     | 104.9     | 105.7 | .     | —     | .         | .    | 80.9      | —    | —         | —    |
| 100.5        | .     | .   | .     | 106.7     | 104.6 | .     | 107.2 | .         | .    | —         | —    | 97.1      | 78.1 |
| 83.9         | .     | .   | .     | 102.7     | 106.6 | .     | 97.8  | .         | .    | 82.8      | 71.3 | 71.3      | .    |
| 90.1         | 99.6  | .   | .     | 101.8     | 106.0 | .     | 110.1 | .         | .    | —         | —    | 74.5      | .    |
| 100.9        | 93.4  | .   | .     | 86.9      | 96.7  | .     | 105.3 | .         | .    | —         | 73.2 | 84.8      | .    |
| 98.2         | 98.6  | .   | .     | 84.5      | 101.5 | .     | 102.9 | .         | .    | 88.1      | —    | 81.6      | .    |
| 93.4         | —     | .   | .     | 86.2      | 101.6 | .     | —     | .         | .    | 72.5      | —    | 81.1      | .    |
| 99.0         | —     | .   | .     | 99.3      | 101.9 | .     | 101.4 | .         | .    | 101.3     | —    | —         | .    |
| 99.4         | —     | .   | .     | 105.0     | 103.2 | .     | 81.0  | .         | .    | —         | —    | 86.2      | .    |
| 85.5         | —     | .   | .     | 102.4     | 106.7 | .     | 98.3  | .         | .    | —         | —    | —         | .    |
| —            | —     | .   | .     | 102.7     | .     | 108.1 | .     | .         | .    | —         | —    | 81.0      | .    |
| —            | 95.5  | .   | 85.2  | 101.8     | .     | 98.5  | .     | .         | .    | 72.2      | —    | 74.6      | .    |
| 101.1        | —     | .   | 106.0 | 86.9      | .     | 107.0 | .     | .         | .    | —         | —    | 82.1      | .    |
| —            | 99.6  | .   | 88.9  | 84.5      | .     | 108.1 | .     | .         | .    | —         | —    | —         | .    |
| —            | 88.4  | .   | 94.2  | 100.2     | .     | 98.5  | .     | .         | .    | —         | —    | —         | .    |
| 83.9         | 97.7  | .   | 92.6  | 99.5      | .     | 109.0 | .     | .         | .    | —         | —    | 85.2      | .    |
| 90.1         | 96.4  | .   | 101.7 | —         | .     | —     | —     | .         | .    | 90.5      | —    | —         | .    |
| 98.2         | 91.4  | .   | 105.7 | 100.2     | .     | —     | 65.8  | .         | .    | —         | —    | 85.8      | .    |
| —            | 84.0  | .   | 102.0 | 100.7     | .     | —     | —     | .         | .    | —         | —    | —         | .    |
| 109.9        | 103.5 | .   | 96.0  | 99.5      | .     | —     | 82.8  | .         | .    | —         | —    | —         | .    |
| 94.6         | 98.6  | .   | 96.7  | 107.3     | .     | —     | 90.8  | 73.2      | —    | —         | —    | —         | .    |
| 92.2         | 101.4 | .   | 95.9  | 105.0     | .     | —     | 78.0  | —         | 81.5 | —         | —    | —         | .    |
| 93.4         | 99.5  | .   | 96.7  | 100.6     | .     | —     | 79.9  | —         | 78.9 | —         | —    | 72.70     | .    |
| 99.3         | 102.2 | .   | —     | 100.7     | .     | —     | 81.7  | 70.7      | —    | —         | —    | 108.4     | .    |
| 95.2         | 105.7 | .   | —     | —         | .     | —     | 84.4  | —         | 75.5 | —         | —    | 82.5      | .    |
| 97.0         | 82.4  | .   | —     | 100.9     | .     | —     | 80.8  | 76.4      | —    | —         | —    | —         | .    |
| 99.4         | —     | .   | —     | 96.0      | .     | —     | 78.5  | 72.4      | —    | —         | —    | 82.3      | .    |
| 85.5         | 95.6  | .   | —     | 98.5      | .     | —     | 87.0  | 68.6      | —    | —         | —    | 80.9      | .    |
| —            | 102.1 | .   | —     | 105.2     | .     | —     | 81.2  | —         | —    | —         | —    | —         | .    |
| —            | 94.2  | —   | —     | 98.5      | .     | —     | 79.9  | —         | —    | —         | —    | —         | .    |
| —            | —     | —   | —     | 107.1     | .     | —     | 95.2  | —         | —    | —         | —    | —         | .    |
| —            | 81.1  | —   | —     | 102.5     | .     | —     | 87.0  | —         | —    | —         | —    | —         | .    |
| —            | —     | —   | —     | 107.7     | —     | —     | 88.6  | —         | —    | —         | —    | —         | .    |
| 109.9        | —     | —   | —     | 70.8      | —     | —     | —     | —         | —    | —         | —    | —         | .    |
| 94.6         | —     | —   | —     | 105.7     | —     | —     | —     | 85.5      | —    | —         | —    | —         | .    |
| 92.2         | —     | —   | —     | 104.6     | —     | —     | —     | —         | —    | —         | —    | —         | .    |
| 99.3         | —     | —   | —     | 106.6     | —     | —     | —     | —         | —    | —         | —    | —         | .    |
| —            | —     | —   | —     | 106.0     | —     | —     | —     | —         | —    | —         | —    | —         | .    |
| 96.1         | —     | —   | —     | 92.6      | —     | —     | —     | —         | —    | —         | —    | —         | .    |

N - Number of Measurements; E - Energy Avg., dB; S - Energy Standard Deviation,  $\times 10^{-10}$

TABLE A-12 MEASURED SEL TABULATION FORM, SITE 203(continued)

| AC - KC 135A |      |     |       | AC - B52G |        |       |      | AC - A-37 |      | AC - T-37 |      | AC - T-38 |      |
|--------------|------|-----|-------|-----------|--------|-------|------|-----------|------|-----------|------|-----------|------|
| Approach     |      | T/O |       | Approach  |        | T/O   |      | Approach  |      | T/O       |      | Approach  |      |
| SI           | Patt | Pat | SO    | SI        | Pat    | Pat   | SO   | Approach  | T/O  | Approach  | T/O  | Approach  | T/O  |
| 93.8         |      |     |       | 101.5     | —      |       |      | —         | 68.7 |           |      |           |      |
| 73.0         |      |     |       | 101.6     | —      |       |      | 86.3      | 75.3 |           |      |           |      |
| —            |      |     |       | 101.9     | —      |       |      | —         | 67.1 |           |      |           |      |
| 98.2         |      |     |       | 103.2     | 101.2  |       |      | —         | —    |           |      |           |      |
| 97.6         |      |     |       | 100.2     | —      |       |      | 79.8      | 76.5 |           |      |           |      |
| 98.0         |      |     |       | 99.5      | —      |       |      | —         | —    |           |      |           |      |
| 98.0         |      |     |       | —         | —      |       |      | 88.4      | 75.2 |           |      |           |      |
| 95.3         |      |     |       | 99.2      | 87.0   |       |      | 90.2      | 84.4 |           |      |           |      |
| 90.4         |      |     |       | 100.7     | —      |       |      | 71.4      | —    |           |      |           |      |
| 92.7         |      |     |       | 99.5      | —      |       |      | 72.9      | 68.7 |           |      |           |      |
| 98.3         |      |     |       | 107.3     | 106.2  |       |      | 84.0      | —    |           |      |           |      |
| 99.4         |      |     |       | 105.0     | —      |       |      | 81.4      | —    |           |      |           |      |
| 95.6         |      |     |       | 100.6     | —      |       |      | 93.9      | —    |           |      |           |      |
| —            |      |     |       | 100.7     | 87.3   |       |      | 109.6     | —    |           |      |           |      |
| —            |      |     |       | —         | —      |       |      | —         | —    |           |      |           |      |
| —            |      |     |       | 100.9     | —      |       |      | 78.1      | —    |           |      |           |      |
| 85.5         |      |     |       | 95.9      | —      |       |      | —         | —    |           |      |           |      |
| —            |      |     |       | 98.5      | —      |       |      | —         | —    |           |      |           |      |
| 89.4         |      |     |       | 104.9     | —      |       |      | —         | —    |           |      |           |      |
| 100.5        |      |     |       | —         | 101.82 |       |      | —         | —    |           |      |           |      |
| 99.6         |      |     |       | —         | —      |       |      | —         | —    |           |      |           |      |
| 88.4         |      |     |       | —         | —      |       |      | —         | —    |           |      |           |      |
| 97.7         |      |     |       | —         | —      |       |      | —         | —    |           |      |           |      |
| 96.4         |      |     |       | —         | —      |       |      | —         | —    |           |      |           |      |
| 91.4         |      |     |       | —         | —      |       |      | —         | —    |           |      |           |      |
| 84.0         |      |     |       | —         | 70.6   |       |      | —         | —    |           |      |           |      |
| 103.5        |      |     |       | —         | —      |       |      | —         | —    |           |      |           |      |
| 98.6         |      |     |       | —         | —      |       |      | —         | —    |           |      |           |      |
| 101.4        |      |     |       | —         | —      |       |      | —         | —    |           |      |           |      |
| 89.5         |      |     |       | —         | —      |       |      | —         | —    |           |      |           |      |
| 102.2        |      |     |       | —         | —      |       |      | —         | —    |           |      |           |      |
| 105.7        |      |     |       | —         | —      |       |      | —         | —    |           |      |           |      |
| 82.4         |      |     |       | —         | —      |       |      | —         | —    |           |      |           |      |
| —            |      |     |       | —         | —      |       |      | —         | —    |           |      |           |      |
| 85.6         |      |     |       | —         | —      |       |      | —         | —    |           |      |           |      |
| 102.1        |      |     |       | —         | —      |       |      | —         | —    |           |      |           |      |
| 94.2         |      |     |       | —         | —      |       |      | —         | —    |           |      |           |      |
| —            |      |     |       | —         | —      |       |      | —         | —    |           |      |           |      |
| 81.1         |      |     |       | —         | —      |       |      | —         | —    |           |      |           |      |
| —            |      |     |       | —         | —      |       |      | —         | —    |           |      |           |      |
| 96.1         |      |     |       | —         | —      |       |      | —         | —    |           |      |           |      |
| 93.8         |      |     |       | —         | —      |       |      | —         | —    |           |      |           |      |
| 72.0         |      |     |       | —         | —      |       |      | —         | —    |           |      |           |      |
| —            |      |     |       | —         | —      |       |      | —         | —    |           |      |           |      |
| 98.2         |      |     |       | —         | —      |       |      | —         | —    |           |      |           |      |
| 97.6         |      |     |       | —         | —      |       |      | —         | —    |           |      |           |      |
| 98.0         |      |     |       | —         | —      |       |      | —         | —    |           |      |           |      |
| 88.0         |      |     |       | —         | —      |       |      | —         | —    |           |      |           |      |
| 95.3         |      |     |       | —         | —      |       |      | —         | —    |           |      |           |      |
| 90.4         |      |     |       | —         | —      |       |      | —         | —    |           |      |           |      |
| 32           | 86   | —   | 12    | 16        | 63     | 38    | 16   | 39        | 29   | 30        | 11   | 37        | 4    |
| 98.3         | 97.7 | —   | 100.4 | 102.7     | 93.5   | 104.7 |      | 94.2      | 74.7 | 87.4      | 76.0 | 93.0      | 77.1 |
| 1.72         | 1.24 | —   | 1.38  | 1.50      | 1.70   | .75   | 3.26 | 1.46      | .01  | .25       | .01  | 1.14      | —    |

N - Number of Measurements; E - Energy Avg., dB; S - Energy Standard Deviation,  $\times 10^{-10}$

exceed the SEL threshold at the particular site. Dots represent events which occurred when the portable noise level monitor was not operational at that site at the time.

Sample energy averages and standard deviations were computed from the tabulated data using Eqs. (8) and (9).

$$\overline{L_{AE}} = 10 \log \frac{1}{n} \sum_q 10^{\frac{L_{AE}}{10}} \quad (8)$$

$$s^2 = \frac{1}{n-1} \left[ \sum_q \left( 10^{\frac{L_{AE}}{10}} \right)^2 - n \left( 10^{\frac{\overline{L_{AE}}}{10}} \right)^2 \right] \quad (9)$$

where

$L_{AE}$  = individual A-weighted sound exposure level (SEL), dB

$\overline{L_{AE}}$  = energy average A-weighted sound exposure level (SEL), dB

$s$  = sample standard deviation for SEL values as an antilog with 1.0 equal to the sound level reference of  $20 \mu \text{ N/m}^2$

$n$  = number of SEL values in the sample

$q$  = summation index for SEL values for a specific aircraft/operation

Zero was used as the SEL level for events which did not register at a site (dashes in Table A-12).

#### SYNTHESIS OF AVERAGE DAY DNL VALUES

The individual aircraft average SEL values were used to synthesize average day DNL estimates as shown in Table A-13. In this table the measured SEL values are expressed in decibels. The equivalent day acoustic energy was derived by multiplying the individual energy average SEL antilog values by the

Table A-13 Summation of Mean and Variance of Measured SEL Contribution  
to Synthesized DNL Values

Site 1

| Type<br>A/C                                  | Operations |      |      |    | Aver. Day Frequency    |                         |  | Average<br>Measured<br>SEL | Equivalent Day<br>DNL Value |
|--|------------|------|------|----|------------------------|-------------------------|--|----------------------------|-----------------------------|
|  | App        |      | T/O  |    | Day,<br>F <sub>D</sub> | Night<br>F <sub>N</sub> | Equiv.<br>Day<br>F=F <sub>D</sub><br>+10F <sub>N</sub> |                            |                             |
|  | SI         | Patt | Patt | SO |                        |                         |  |                            |                             |
| KC -<br>135A                                 | ✓          |      |      |    | 3.180                  | 0.510                   | 8.28   | 102.2                      | 62.0                        |
|  |            | ✓    |      |    | 12.412                 | 2.670                   | 39.112   | 101.2                      | 67.7                        |
|  |            |      | ✓    |    | 8.240                  | 1.780                   | 26.04  | 103.8                      | 68.6                        |
|  |            |      |      | ✓  | 2.871                  | 0.426                   | 7.131  | 113.4                      | 72.5                        |
| B52G   | ✓          |      |      |    | 2.910                  | 0.960                   | 12.51  | 106.5                      | 68.1                        |
|  |            | ✓    |      |    | 9.750                  | 3.600                   | 45.75  | 100.7                      | 67.9                        |
|  |            |      | ✓    |    | 6.480                  | 2.400                   | 30.48  | 106.6                      | 72.0                        |
|  |            |      |      | ✓  | 2.436                  | 0.225                   | 4.686  | 115.3                      | 72.6                        |
| A-37   | ✓          |      |      |    | 14.430                 | 0.092                   | 15.35  | 88.8                       | 51.3                        |
|  |            | ✓    |      |    | 7.168                  | 0.144                   | 8.608  | 88.8                       | 48.7                        |
|  |            |      | ✓    |    | 4.770                  | 0.099                   | 5.76   | 94.8                       | 53.0                        |
|  |            |      |      | ✓  | 5.420                  | 0.140                   | 6.820  | 94.8                       | 53.7                        |
| T-37   | ✓          |      |      |    | 5.400                  | 0                       | 5.40   | 88.2                       | 46.1                        |
|  |            | ✓    |      |    | 19.260                 | 0                       | 19.26  | 88.2                       | 51.6                        |
|  |            |      | ✓    |    | 10.50                  | 0.02                    | 10.70  | 97.8                       | 58.7                        |
|  |            |      |      | ✓  | 3.580                  | 0.02                    | 3.78   | 97.8                       | 54.2                        |
| T-38   | ✓          |      |      |    | 1.780                  | 0.102                   | 2.80   | 81.4                       | 36.5                        |
|  |            | ✓    |      |    | 4.160                  | 0.298                   | 7.14   | 81.4                       | 40.5                        |
|  |            |      | ✓    |    | 2.548                  | 0.172                   | 4.268  | 92.4                       | 49.3                        |
|  |            |      |      | ✓  | 1.190                  | 0.07                    | 1.890  | 92.4                       | 45.8                        |
| T-39   | ✓          |      |      |    | 2.540                  | 1.220                   | 14.74  | 92.3                       | 54.6                        |
|  |            | ✓    |      |    | 5.230                  | 0.190                   | 7.13   | 92.3                       | 51.4                        |
|  |            |      | ✓    |    | 3.490                  | 0.820                   | 11.69  | 92.3                       | 53.6                        |
|  |            |      |      | ✓  | 2.370                  | 0.130                   | 3.67   | 92.3                       | 48.5                        |
| Other  | ✓          |      |      |    | 2.80                   | 0.10                    | 3.80   | -                          | -                           |
|  |            | ✓    |      |    | 5.875                  | 0.57                    | 11.575   | -                          | -                           |
|  |            |      | ✓    |    | 4.08                   | 0.41                    | 8.18   | -                          | -                           |
|  |            |      |      | ✓  | 1.75                   | 0.07                    | 2.45   | -                          | -                           |
| Totals                                       |            |      |      |    | 156.62                 | 17.238                  | 329  |                            |                             |
| Energy Average DNL, $\overline{L}_{dn}$ , dB |            |      |      |    |                        |                         |  |                            | 79.1                        |
| NOISEMAP DNL Prediction, dB (REF)            |            |      |      |    |                        |                         |  |                            | 80.5                        |

Table A-13 Summation of Mean and Variance of Measured SEL Contribution to Synthesized DNL Values

Site 2

| Type<br>A/C                                  | Operations |      |      |    | Aver. Day Frequency    |                         |  | Average<br>Measured<br>SEL | Equivalent Day<br>DNL Value |
|--|------------|------|------|----|------------------------|-------------------------|--|----------------------------|-----------------------------|
|  | App        |      | T/O  |    | Day,<br>F <sub>D</sub> | Night<br>F <sub>N</sub> | Equiv.<br>Day<br>F=F <sub>D</sub><br>+10F <sub>N</sub> |                            |                             |
|  | SI         | Patt | Patt | SO |                        |                         |  |                            |                             |
| KC -<br>135A                                 | ✓          |      |      |    | 3.180                  | 0.510                   | 8.28   | 94.1                       | 53.9                        |
|  |            | ✓    |      |    | 12.412                 | 2.670                   | 39.112   | 95.9                       | 62.4                        |
|  |            |      | ✓    |    | 8.240                  | 1.780                   | 26.04  | 98.3                       | 63.1                        |
|  |            |      |      | ✓  | 2.871                  | 0.426                   | 7.131  | 111.2                      | 70.3                        |
| B52G   | ✓          |      |      |    | 2.910                  | 0.960                   | 12.51  | 96.1                       | 57.7                        |
|  |            | ✓    |      |    | 9.750                  | 3.600                   | 45.75  | 96.1                       | 63.3                        |
|  |            |      | ✓    |    | 6.480                  | 2.400                   | 30.48  | 100.1                      | 65.5                        |
|  |            |      |      | ✓  | 2.436                  | 0.225                   | 4.686  | 113.4                      | 70.7                        |
| A-37   | ✓          |      |      |    | 14.430                 | 0.092                   | 15.35  | 84.0                       | 46.5                        |
|  |            | ✓    |      |    | 7.168                  | 0.144                   | 8.608  | 84.0                       | 43.9                        |
|  |            |      | ✓    |    | 4.770                  | 0.099                   | 5.76   | 91.3                       | 49.5                        |
|  |            |      |      | ✓  | 5.420                  | 0.140                   | 6.820  | 91.3                       | 50.2                        |
| T-37   | ✓          |      |      |    | 5.400                  | 0                       | 5.40   | 77.5                       | 35.4                        |
|  |            | ✓    |      |    | 19.260                 | 0                       | 19.26  | 77.5                       | 40.9                        |
|  |            |      | ✓    |    | 10.50                  | 0.02                    | 10.70  | 89.2                       | 50.1                        |
|  |            |      |      | ✓  | 3.580                  | 0.02                    | 3.78   | 89.2                       | 45.6                        |
| T-38   | ✓          |      |      |    | 1.780                  | 0.102                   | 2.80   | 87.7                       | 42.8                        |
|  |            | ✓    |      |    | 4.160                  | 0.298                   | 7.14   | 87.7                       | 46.8                        |
|  |            |      | ✓    |    | 2.548                  | 0.172                   | 4.268  | 87.5                       | 44.4                        |
|  |            |      |      | ✓  | 1.190                  | 0.07                    | 1.890  | 87.5                       | 40.9                        |
| T-39   | ✓          |      |      |    | 2.540                  | 1.220                   | 14.74  | 88.1                       | 50.4                        |
|  |            | ✓    |      |    | 5.230                  | 0.190                   | 7.13   | 88.1                       | 47.2                        |
|  |            |      | ✓    |    | 3.490                  | 0.820                   | 11.69  | 93.9                       | 55.2                        |
|  |            |      |      | ✓  | 2.370                  | 0.130                   | 3.67   | 93.9                       | 50.1                        |
| Other  | ✓          |      |      |    | 2.80                   | 0.10                    | 3.80   | -                          | -                           |
|  |            | ✓    |      |    | 5.875                  | 0.57                    | 11.575   | -                          | -                           |
|  |            |      | ✓    |    | 4.08                   | 0.41                    | 8.18   | -                          | -                           |
|  |            |      |      | ✓  | 1.75                   | 0.07                    | 2.45   | -                          | -                           |
| Totals                                       |            |      |      |    | 156.62                 | 17.238                  | 329  |                            |                             |
| Energy Average DNL, $\overline{L}_{dn}$ , dB |            |      |      |    |                        |                         |  |                            | 75.3                        |
| NOISEMAP DNL Prediction, dB (REF)            |            |      |      |    |                        |                         |  |                            | 76.4                        |

Table A-13 Summation of Mean and Variance of Measured SEL Contribution to Synthesized DNL Values

Site 3

| Type<br>A/C                                  | Operations |      |      |    | Aver. Day Frequency    |                         |  | Average<br>Measured<br>SEL | Equivalent Day<br>DNL Value |
|--|------------|------|------|----|------------------------|-------------------------|--|----------------------------|-----------------------------|
|  | App        |      | T/O  |    | Day,<br>F <sub>D</sub> | Night<br>F <sub>N</sub> | Equiv.<br>Day<br>F=F <sub>D</sub><br>+10F <sub>N</sub> |                            |                             |
|  | SI         | Patt | Patt | SO |                        |                         |  |                            |                             |
| KC -<br>135A                                 | ✓          |      |      |    | 3.180                  | 0.510                   | 8.28   | 88.6                       | 48.4                        |
|  |            | ✓    |      |    | 12.412                 | 2.670                   | 39.112   | 82.9                       | 49.4                        |
|  |            |      | ✓    |    | 8.240                  | 1.780                   | 26.04  | 87.6                       | 52.4                        |
|  |            |      |      | ✓  | 2.871                  | 0.426                   | 7.131  | 104.6                      | 63.7                        |
| B52G   | ✓          |      |      |    | 2.910                  | 0.960                   | 12.51  | 86.6                       | 48.2                        |
|  |            | ✓    |      |    | 9.750                  | 3.600                   | 45.75  | 0                          | 0                           |
|  |            |      | ✓    |    | 6.480                  | 2.400                   | 30.48  | 90.4                       | 55.8                        |
|  |            |      |      | ✓  | 2.436                  | 0.225                   | 4.686  | 107.1                      | 64.8                        |
| A-37   | ✓          |      |      |    | 14.430                 | 0.092                   | 15.35  | 71.3                       | 33.8                        |
|  |            | ✓    |      |    | 7.168                  | 0.144                   | 8.608  | 71.3                       | 30.2                        |
|  |            |      | ✓    |    | 4.770                  | 0.099                   | 5.76   | 86.0                       | 44.2                        |
|  |            |      |      | ✓  | 5.420                  | 0.140                   | 6.820  | 86.0                       | 44.9                        |
| T-37   | ✓          |      |      |    | 5.400                  | 0                       | 5.40   | 0                          | 0                           |
|  |            | ✓    |      |    | 19.260                 | 0                       | 19.26  | 0                          | 0                           |
|  |            |      | ✓    |    | 10.50                  | 0.02                    | 10.70  | 82.0                       | 42.9                        |
|  |            |      |      | ✓  | 3.580                  | 0.02                    | 3.78   | 82.0                       | 38.4                        |
| T-38   | ✓          |      |      |    | 1.780                  | 0.102                   | 2.80   | 0                          | 0                           |
|  |            | ✓    |      |    | 4.160                  | 0.298                   | 7.14   | 0                          | 0                           |
|  |            |      | ✓    |    | 2.548                  | 0.172                   | 4.268  | 82.2                       | 39.1                        |
|  |            |      |      | ✓  | 1.190                  | 0.07                    | 1.890  | 82.2                       | 35.6                        |
| T-39   | ✓          |      |      |    | 2.540                  | 1.220                   | 14.74  | 0                          | 0                           |
|  |            | ✓    |      |    | 5.230                  | 0.190                   | 7.13   | 0                          | 0                           |
|  |            |      | ✓    |    | 3.490                  | 0.820                   | 11.69  | 87.3                       | 48.3                        |
|  |            |      |      | ✓  | 2.370                  | 0.130                   | 3.67   | 87.3                       | 43.5                        |
| Other  | ✓          |      |      |    | 2.80                   | 0.10                    | 3.80   | -                          | -                           |
|  |            | ✓    |      |    | 5.875                  | 0.57                    | 11.575   | -                          | -                           |
|  |            |      | ✓    |    | 4.08                   | 0.41                    | 8.18   | -                          | -                           |
|  |            |      |      | ✓  | 1.75                   | 0.07                    | 2.45   | -                          | -                           |
| Totals                                       |            |      |      |    | 156.62                 | 17.238                  | 329  |                            |                             |
| Energy Average DNL, $\overline{L}_{dn}$ , dB |            |      |      |    |                        |                         |  | 68.0                       |                             |
| NOISEMAP DNL Prediction, dB (REF)            |            |      |      |    |                        |                         |  | 69.4                       |                             |

Table A-13 Summation of Mean and Variance of Measured SEL Contribution to Synthesized DNL Values

Site 202

| Type<br>A/C                                  | Operations |      |      |    | Aver. Day Frequency    |                         |  | Average<br>Measured<br>SEL | Equivalent Day<br>DNL Value |
|--|------------|------|------|----|------------------------|-------------------------|--|----------------------------|-----------------------------|
|  | App        |      | T/O  |    | Day,<br>F <sub>D</sub> | Night<br>F <sub>N</sub> | Equiv.<br>Day<br>F=F <sub>D</sub><br>+10F <sub>N</sub> |                            |                             |
|  | SI         | Patt | Patt | SO |                        |                         |  |                            |                             |
| KC -<br>135A                                 | ✓          |      |      |    | 3.180                  | 0.510                   | 8.28   | 93.0                       | 52.8                        |
|  |            | ✓    |      |    | 12.412                 | 2.670                   | 39.112   | 92.7                       | 59.2                        |
|  |            |      | ✓    |    | 8.240                  | 1.780                   | 26.04  | 79.8                       | 44.6                        |
|  |            |      |      | ✓  | 2.871                  | 0.426                   | 7.131  | 106.8                      | 65.9                        |
| B52G   | ✓          |      |      |    | 2.910                  | 0.960                   | 12.51  | 96.2                       | 57.8                        |
|  |            | ✓    |      |    | 9.750                  | 3.600                   | 45.75  | 97.2                       | 64.4                        |
|  |            |      | ✓    |    | 6.480                  | 2.400                   | 30.48  | 92.8                       | 58.1                        |
|  |            |      |      | ✓  | 2.436                  | 0.225                   | 4.686  | 111.5                      | 68.8                        |
| A-37   | ✓          |      |      |    | 14.430                 | 0.092                   | 15.35  | 78.9                       | 41.4                        |
|  |            | ✓    |      |    | 7.168                  | 0.144                   | 8.608  | 78.9                       | 38.8                        |
|  |            |      | ✓    |    | 4.770                  | 0.099                   | 5.76   | 85.5                       | 43.7                        |
|  |            |      |      | ✓  | 5.420                  | 0.140                   | 6.820  | 85.5                       | 44.4                        |
| T-37   | ✓          |      |      |    | 5.400                  | 0                       | 5.40   | 77.4                       | 35.3                        |
|  |            | ✓    |      |    | 19.260                 | 0                       | 19.26  | 77.4                       | 40.8                        |
|  |            |      | ✓    |    | 10.50                  | 0.02                    | 10.70  | 85.3                       | 46.2                        |
|  |            |      |      | ✓  | 3.580                  | 0.02                    | 3.78   | 85.3                       | 41.7                        |
| T-38   | ✓          |      |      |    | 1.780                  | 0.102                   | 2.80   | 79.6                       | 34.7                        |
|  |            | ✓    |      |    | 4.160                  | 0.298                   | 7.14   | 79.6                       | 38.7                        |
|  |            |      | ✓    |    | 2.548                  | 0.172                   | 4.268  | 83.8                       | 40.7                        |
|  |            |      |      | ✓  | 1.190                  | 0.07                    | 1.890  | 83.8                       | 37.2                        |
| T-39   | ✓          |      |      |    | 2.540                  | 1.220                   | 14.74  | 87.0                       | 49.3                        |
|  |            | ✓    |      |    | 5.230                  | 0.190                   | 7.13   | 87.0                       | 46.1                        |
|  |            |      | ✓    |    | 3.490                  | 0.820                   | 11.69  | 87.8                       | 49.1                        |
|  |            |      |      | ✓  | 2.370                  | 0.130                   | 3.67   | 87.8                       | 44.0                        |
| Other  | ✓          |      |      |    | 2.80                   | 0.10                    | 3.80   | -                          | -                           |
|  |            | ✓    |      |    | 5.875                  | 0.57                    | 11.575   | -                          | -                           |
|  |            |      | ✓    |    | 4.08                   | 0.41                    | 8.18   | -                          | -                           |
|  |            |      |      | ✓  | 1.75                   | 0.07                    | 2.45   | -                          | -                           |
| Totals                                       |            |      |      |    | 156.62                 | 17.238                  | 329  |                            |                             |
| Energy Average DNL, $\overline{L}_{dn}$ , dB |            |      |      |    |                        |                         |  |                            | 72.3                        |
| NOISEMAP DNL Prediction, dB (REF)            |            |      |      |    |                        |                         |  |                            | 75.8                        |

Table A-13 Summation of Mean and Variance of Measured SEL Contribution to Synthesized DNL Values

Site 203

| Type<br>A/C                                  | Operations |      |      |    | Aver. Day Frequency    |                         |  | Average<br>Measured<br>SEL | Equivalent Day<br>DNL Value |
|--|------------|------|------|----|------------------------|-------------------------|--|----------------------------|-----------------------------|
|  | App        |      | T/O  |    | Day,<br>F <sub>D</sub> | Night<br>F <sub>N</sub> | Equiv.<br>Day<br>F=F <sub>D</sub><br>+10F <sub>N</sub> |                            |                             |
|  | SI         | Patt | Patt | SO |                        |                         |  |                            |                             |
| KC -<br>135A                                 | ✓          |      |      |    | 3.180                  | 0.510                   | 8.28   | 98.5                       | 58.3                        |
|  |            | ✓    |      |    | 12.412                 | 2.670                   | 39.112   | 97.7                       | 64.2                        |
|  |            |      | ✓    |    | 8.240                  | 1.780                   | 26.04  | 0                          | 0                           |
|  |            |      |      | ✓  | 2.871                  | 0.426                   | 7.131  | 100.4                      | 59.5                        |
| B52G   | ✓          |      |      |    | 2.910                  | 0.960                   | 12.51  | 102.7                      | 64.3                        |
|  |            | ✓    |      |    | 9.750                  | 3.600                   | 45.75  | 102.9                      | 70.1                        |
|  |            |      | ✓    |    | 6.480                  | 2.400                   | 30.48  | 93.5                       | 58.9                        |
|  |            |      |      | ✓  | 2.436                  | 0.225                   | 4.686  | 104.7                      | 62.0                        |
| A-37   | ✓          |      |      |    | 14.430                 | 0.092                   | 15.35  | 94.2                       | 56.7                        |
|  |            | ✓    |      |    | 7.168                  | 0.144                   | 8.608  | 94.2                       | 54.1                        |
|  |            |      | ✓    |    | 4.770                  | 0.099                   | 5.76   | 74.7                       | 32.9                        |
|  |            |      |      | ✓  | 5.420                  | 0.140                   | 6.820  | 74.7                       | 33.6                        |
| T-37   | ✓          |      |      |    | 5.400                  | 0                       | 5.40   | 87.4                       | 45.3                        |
|  |            | ✓    |      |    | 19.260                 | 0                       | 19.26  | 87.4                       | 50.8                        |
|  |            |      | ✓    |    | 10.50                  | 0.02                    | 10.70  | 76.0                       | 36.9                        |
|  |            |      |      | ✓  | 3.580                  | 0.02                    | 3.78   | 76.0                       | 32.4                        |
| T-38   | ✓          |      |      |    | 1.780                  | 0.102                   | 2.80   | 93.0                       | 48.1                        |
|  |            | ✓    |      |    | 4.160                  | 0.298                   | 7.14   | 93.0                       | 52.1                        |
|  |            |      | ✓    |    | 2.548                  | 0.172                   | 4.268  | 77.1                       | 34.0                        |
|  |            |      |      | ✓  | 1.190                  | 0.07                    | 1.890  | 77.1                       | 30.5                        |
| T-39   | ✓          |      |      |    | 2.540                  | 1.220                   | 14.74  | 89.7                       | 52.0                        |
|  |            | ✓    |      |    | 5.230                  | 0.190                   | 7.13   | 89.7                       | 48.8                        |
|  |            |      | ✓    |    | 3.490                  | 0.820                   | 11.69  | 79.7                       | 41.0                        |
|  |            |      |      | ✓  | 2.370                  | 0.130                   | 3.67   | 79.7                       | 35.9                        |
| Other  | ✓          |      |      |    | 2.80                   | 0.10                    | 3.80   | -                          | -                           |
|  |            | ✓    |      |    | 5.875                  | 0.57                    | 11.575   | -                          | -                           |
|  |            |      | ✓    |    | 4.08                   | 0.41                    | 8.18   | -                          | -                           |
|  |            |      |      | ✓  | 1.75                   | 0.07                    | 2.45   | -                          | -                           |
| Totals                                       |            |      |      |    | 156.62                 | 17.238                  | 329  |                            |                             |
| Energy Average DNL, $\overline{L}_{dn}$ , dB |            |      |      |    |                        |                         |  |                            | 73.2                        |
| NOISEMAP DNL Prediction, dB (REF)            |            |      |      |    |                        |                         |  |                            | 73.7                        |

NOISEMAP equivalent day frequency of occurrence  $F$ , summing, taking 10 times the logarithm of the sum and subtracting 49.4 dB for the number of seconds in a day. In equation form:

$$\overline{L}_{dn} = 10 \log(\sum_k \overline{E} \cdot F) - 49.4 \quad (10)$$

where

$F$  = equivalent day average day aircraft frequency

$\overline{E}$  = energy average of SEL measurements for a specific aircraft/operation combination expressed as an antilog

$k$  = summation index for different aircraft/operations.

Expressing the equivalent day DNL value for each type of aircraft operation in Table A-13 emphasizes the differences between the noise levels due to different aircraft. Summing the equivalent day energy values for the four smaller aircraft shows that they account for only 2.5 to 5 percent of the total energy. Excluding the four smaller aircraft decreases the DNL estimates by an average of only 0.2 dB, Table A-14.

Comparison of the SEL-based estimates from Table A-14 with the DNL-based estimates of Table A-10 shows that the SEL-based estimates are slightly higher. However, comparison with NOISEMAP values shows that SEL-based estimates are still consistently lower than predictions.

The use of SEL measurements to estimate average day DNL values has reduced the potential field test bias because the mix of operations during the field test is not a factor. In addition, the statistical uncertainty should be reduced because the number of data samples has been increased from the numbers of days to numbers of aircraft. Therefore, the most likely cause of the differences between measurements-based estimates and NOISEMAP predictions is incorrect NOISEMAP input data.

#### ANALYSIS BY EXTRAPOLATION FROM KEY SITE DNL ESTIMATE USING MEASURED HNL VALUES

#### COMPUTATION OF ENERGY AVERAGE HNL VALUES

To extrapolate from the key site (Site 2) to satellite sites (Sites 1, 3, 202, 203, and 4), energy average HNL values

TABLE A-14 AVERAGE DAY ESTIMATED DNL VALUES  
BASED ON SEL MEASUREMENTS, dB

| Site | All*<br>Aircraft | Heavy**<br>Aircraft | Difference<br>All A/C(-)<br>Heavy A/C | NOISEMAP<br>(Ref) |
|------|------------------|---------------------|---------------------------------------|-------------------|
| 1    | 79.1             | 79.0                | .1                                    | 80.5              |
| 2    | 75.1             | 75.0                | .1                                    | 76.4              |
| 3    | 68.2             | 68.1                | 0.1                                   | 69.4              |
| 202  | 72.4             | 72.4                | 0.1                                   | 75.8              |
| 203  | 73.3             | 73.0                | 0.3                                   | 73.7              |

\* The six aircraft listed in Table A-13. These aircraft comprise 93% of Barksdale flight operations.

\*\* B52G and KC135A

were computed for all sites from the HNL values listed in Table A-6. The averages were taken only for data measured simultaneously at the key site and the particular satellite site. Therefore, five different energy average HNL values were computed for Site 2 because no satellite site was operational for exactly the same time period as any other satellite site. The computation of energy average HNL was facilitated by using LEQ values for complete days, Eq. (12).

$$\overline{L}_h = 10 \log \frac{1}{24d + h} \left( 24 \sum_{\ell} 10^{\frac{L_{24}}{10}} + \sum_i 10^{\frac{L_h}{10}} \right) \quad (12)$$

where

$\overline{L}_h$  = energy average HNL value, dB

$L_{24}$  = twenty-four hour average noise level (LEQ), dB

$L_h$  = hourly noise level (HNL), dB

$\ell$  = summation index for complete measurement days at both key site and satellite site

$i$  = summation index for hours from incomplete measurement days at both key site and satellite site

$d$  = number of complete measurement days at both key site and satellite site

$h$  = number of hourly noise level values from incomplete measurement days at both key site and satellite site.

In Table A-15 the energy average HNL values are presented, the site-to-site differences calculated, and the extrapolations from Site 2 to the satellite sites performed.

Extrapolations from two different Site 2 average day DNL estimates are presented, one based on DNL measurements and the other based on SEL measurements.

TABLE A-15 EXTRAPOLATION FROM KEY SITE TO SATELLITE SITE DNL VALUES  
USING ENERGY AVERAGE HNL VALUES

| Satellite<br>Site<br>Number | Energy Average<br>HNL, dB |                    |                                     | DNL          |               |                            |                    |                        | Standard Deviation<br>of HNL Differences |       |     |
|-----------------------------|---------------------------|--------------------|-------------------------------------|--------------|---------------|----------------------------|--------------------|------------------------|--|-------|-----|
|                             |                           |                    |                                     | Key Site DNL |               | Key Site DNL<br>From SEL's |                    | NOISE-<br>MAP<br>(Ref) |  |       |     |
|                             | Satel<br>Site             | Key<br>Site<br>(2) | $\Delta$ HNL<br>Satel<br>(-)<br>Key | From DNL's   |               | Key*<br>Site<br>(2)        | Key<br>Site<br>(2) |                        | Satel<br>Site                            |       |     |
|                             |                           |                    |                                     | Key*         | Satel<br>Site |                            |                    |                        |  |       |     |
|                             |                           |                    |                                     |              |               |                            |                    |                        |  | s, dB | n   |
| 1                           | 74.6                      | 71.6               | 3.0                                 | 72.7         | 75.7          | 75.3                       | 78.3               | 80.5                   | 5.1                                      | 11.5  | 0.5 |
| 3                           | 65.3                      | 71.7               | -6.4                                | 72.7         | 66.3          | 75.3                       | 68.9               | 69.4                   | 7.6                                      | 12.2  | 0.7 |
| 202                         | 69.4                      | 71.3               | -1.9                                | 72.7         | 70.8          | 75.3                       | 73.4               | 75.8                   | 6.0                                      | 9.1   | 0.6 |
| 203                         | 67.8                      | 69.4               | -1.6                                | 72.7         | 71.1          | 75.3                       | 73.7               | 73.7                   | 7.6                                      | 21.7  | 0.5 |
| 4                           | 59.4                      | 65.4               | -6.0                                | 72.7         | 66.7          | 75.3                       | 69.3               | 69.0                   | 8.9                                      | 14.6  | 0.7 |

\* Corrected for number of operations.

## POST TEST BIAS CORRECTIONS

Four types of post test overall corrections were considered. These were for atmospheric absorption bias, for temperature bias, for calibrator calibration bias, and for calibrator altitude correction.

An atmospheric absorption or humidity bias was evaluated by comparing the atmospheric absorption during the field test with average yearly atmospheric absorption. The atmospheric absorption values were determined by plotting temperature and relative humidity values on an absorption contour, Figure A-3. For the field test, temperature and relative humidity values taken every three hours were averaged separately, yielding 78.1° F and 73.5 percent relative humidity. Averaging the two parameters separately instead of plotting every point is valid because the points tend to lie on a straight line. This is evidenced by the monthly average data, also presented in Figure A-3. The atmospheric absorption difference between the field test and yearly average is 0.13 dB/1000 feet at 1000 Hz. An additional 0.1 dB/1000 feet at 1000 Hz exists between the Barksdale AFB yearly average and standard conditions (59° F, 70 percent relative humidity) which were used for the NOISEMAP computations.

The average temperature being greater than standard conditions also tends to decrease the noise levels because of decreased thrust and impedance changes. This is balanced somewhat by an increase in noise levels with decreased aircraft speed. Figure A-4 shows the combination of these temperature effects. For the Barksdale AFB field test, the estimated decrease in noise level due to increased temperature is 0.7 dB.

However, applying the corrections for these biases was considered unsound, especially for large slant distances (over 4000 feet) for two reasons:

- . The higher than average temperature during the field test also affects the measured noise levels by lowering climb performance. Bias error corrections should include factors for this phenomena.
- . For long slant distances, the peak in the frequency spectra tends to be shifted lower than 1000 Hz. Precise corrections should take the frequency spectra into consideration.




FIGURE A-3. 1000 Hz ABSORPTION VALUES (REF.16)




FIGURE A-4. CORRECTIONS FOR TEMPERATURE-THRUST VARIATIONS  
(REF. 17)

Instead of applying corrections, the atmospheric absorption bias, 0.1 to 0.2 dB, has been used as a measure of uncertainty in computing confidence intervals. The temperature-thrust bias has also been used as another contributor to the uncertainty.

Calibrator calibration bias, on the other hand, has been identified and corrections applied. Before the field test program, the calibrators were checked against a B&K model 4220 pistonphone using a variety of microphones as transfer transducers. The results showed the calibrators consistently producing 114.4 dB. After the field test, this was confirmed by factory calibration by GEN/RAD. As a result of this well documented bias, the experimental results were increased by 0.4 dB. This correction was applied to all reported levels throughout this document.

The acoustic output of calibrators decreases with atmospheric pressure at a rate of approximately 0.2 dB per 1000 feet altitude. However, the altitude at Barksdale AFB is only 164 feet above sea level. Since the resulting error is less than 0.05 dB, no corrections were applied to the measured levels.

#### CONFIDENCE LIMITS

Statistical confidence limits were derived from the measured data for all estimates of yearly average DNL. The 90 percent level confidence coefficient was employed. The selection of this confidence coefficient was essentially arbitrary, but it is consistent with current practice. In addition to the variabilities in the measured data, other uncertainties were evaluated. These include uncorrected temperature-humidity absorption bias, uncorrected temperature-thrust bias, instrumentation errors which weren't averaged during the field test, and unrepresentative flight activity during the field test. The variances from all sources of error were combined to arrive at overall confidence intervals.

#### CONFIDENCE LIMITS FOR DNL-BASED ESTIMATES

Statistical confidence limits for the estimated yearly average DNL values were derived from the measured data. For

estimates obtained from the measured DNL values, the Student t statistic with the number of degrees of freedom equal to one less than the sample size was utilized (see Table A-16).

The confidence limits were calculated from the DNL statistics of Table A-10 as follows.

$$\text{Confidence limits} = 10 \log \left[ \text{Energy Avg.} \pm \frac{t}{\sqrt{n}} \text{Energy Std Dev} \right] \quad (14)$$

For example, from Table A-10, for Site 2 with corrections for total aircraft volume,

$$\begin{aligned} \text{Confidence limits} &= 10 \log \left[ 10^{\frac{72.7}{10}} \pm \frac{1.78}{\sqrt{13}} (1.44 \times 10^7) \right] \quad (15) \\ &= \frac{74.1}{70.6} \text{ dB} \end{aligned}$$

The confidence interval is the difference between the upper and lower limit, in this case  $74.1 (-) 70.6 = 3.5 \text{ dB}$  or  $1.4, - 2.1 \text{ dB}$  in relation to the average  $72.7 \text{ dB}$ .

The average day DNL estimates and the associated confidence intervals are summarized in Table A-17.

#### CONFIDENCE LIMITS FOR SEL-BASED ESTIMATES

Statistical confidence limits for the SEL-based estimates of yearly average DNL values were derived from the measured data. With the large number of SEL samples contributing to the computation, the normal distribution statistic for the 90th percentile, 1.64, was used. (Note that this is the limiting value for the Student t distribution as the sample size becomes large, Table A-16.) Confidence limits were calculated as follows:

$$\text{Confidence limits} = 10 \log \left[ \sum_k (\bar{E} F) \pm 1.64 \sqrt{F \left( \frac{s}{\sqrt{n}} \right)^2} \right] - 49.4 \quad (16)$$

TABLE A-16 STUDENT t STATISTICAL DISTRIBUTION FACTORS  
FOR 90% CONFIDENCE IN ESTIMATION OF MEAN

| Number<br>of<br>Samples | Statistical<br>Degrees<br>of<br>Freedom | Student<br>t factor<br>for 90%<br>Confidence | $t/\sqrt{n}$ |
|-------------------------|---|--|--------------|
| 2                       | 1                                       | 6.31   | 4.46         |
| 3                       | 2                                       | 2.92   | 1.69         |
| 4                       | 3                                       | 2.35   | 1.18         |
| 5                       | 4                                       | 2.13   | 0.95         |
| 6                       | 5                                       | 2.02   | 0.82         |
| 7                       | 6                                       | 1.94   | 0.73         |
| 8                       | 7                                       | 1.90   | 0.67         |
| 9                       | 8                                       | 1.86   | 0.62         |
| 10                      | 9                                       | 1.83   | 0.58         |
| 11                      | 10                                      | 1.81   | 0.55         |
| 12                      | 11                                      | 1.80   | 0.52         |
| 13                      | 12                                      | 1.78   | 0.49         |
| 14                      | 13                                      | 1.77   | 0.47         |
| 15                      | 14                                      | 1.76   | 0.45         |
| 16                      | 15                                      | 1.75   | 0.44         |
| 17                      | 16                                      | 1.75   | 0.42         |
| 18                      | 17                                      | 1.74   | 0.41         |
| 19                      | 18                                      | 1.73   | 0.40         |
| 20                      | 19                                      | 1.73   | 0.39         |
| 21                      | 20                                      | 1.73   | 0.38         |
| 22                      | 21                                      | 1.72   | 0.37         |
| 23                      | 22                                      | 1.72   | 0.36         |
| 24                      | 23                                      | 1.71   | 0.35         |
| 25                      | 24                                      | 1.71   | 0.34         |
| 26                      | 25                                      | 1.71   | 0.34         |
| 27                      | 26                                      | 1.71   | 0.33         |
| 28                      | 27                                      | 1.70   | 0.32         |
| 29                      | 28                                      | 1.70   | 0.32         |
| 30                      | 29                                      | 1.70   | 0.31         |
| 31                      | 30                                      | 1.70   | 0.31         |
| $\infty$                | $\infty$                                | 1.64   | 0            |

Table A-17 Barksdale AFB Yearly DNL Estimates With Confidence Intervals  
Based Only on Sample Statistics

| Data Source                   | SITE |          |      |              |      |          |      |          |      |          |      |        |
|-------------------------------|------|----------|------|--------------|------|----------|------|----------|------|----------|------|--------|
|                               | 1    |          |      | 2            |      |          | 3    |          |      | 4        |      |        |
|                               | Avg  | 90% CI   | Avg  | 90% CI       | Avg  | 90% CI   | Avg  | 90% CI   | Avg  | 90% CI   | Avg  | 90% CI |
| All Days Measurements         |      |          |      |              |      |          |      |          |      |          |      |        |
| No Corrections                | -    | -        | 72.0 | +2.5<br>-2.6 | -    | -        | -    | -        | -    | -        | -    | -      |
| Corrected for total A/C       | -    | -        | 72.7 | +1.4<br>-2.1 | -    | -        | -    | -        | -    | -        | -    | -      |
| Corrected for heavy A/C       | -    | -        | 72.6 | +1.4<br>-2.1 | -    | -        | -    | -        | -    | -        | -    | -      |
| Week Days Measurements        |      |          |      |              |      |          |      |          |      |          |      |        |
| No Corrections                | -    | -        | 73.5 | +1.3<br>-1.8 | -    | -        | -    | -        | -    | -        | -    | -      |
| Corrected for total A/C       | -    | -        | 73.2 | +1.3<br>-1.9 | -    | -        | -    | -        | -    | -        | -    | -      |
| Corrected for heavy A/C       | -    | -        | 72.4 | +1.6<br>-2.5 | -    | -        | -    | -        | -    | -        | -    | -      |
| SEL Synthesis Measured Data   | 79.1 | +2<br>-2 | 75.3 | +3<br>-2     | 68.0 | +4<br>-4 | 72.3 | +4<br>-1 | 73.2 | +1<br>-1 | -    | -      |
| Extrapolation from Site 2 DNL | 75.7 | +1.9     | -    | -            | 66.3 | +2.1     | 70.8 | +2.0     | 71.1 | +1.9     | 66.7 | +2.1   |
| NOISEMAP (REF)                | 80.5 |          | 76.4 |              | 69.4 | 75.8     | 73.7 |          |      | 69.0     |      |        |

where

F = equivalent day, average day aircraft frequency

$\bar{E}$  = energy average of SEL measurements for a specific aircraft/operation combination expresses as an antilog

s = standard deviation of energy of SEL measurements

k = summation index for different aircraft/operations

For example, from Table A-18 for Site 2

$$\begin{aligned} \text{Confidence limits} &= 10 \log \left[ 296.49 \times 10^{10} \pm 1.64 \sqrt{99.85 \times 10^{20}} \right] - 49.4 \\ &= 75.6/75.1 \end{aligned} \quad (17)$$

The confidence interval is +0.3, -0.2 in relation to the average value of 75.3 dB. The average day DNL estimates with associated confidence intervals are summarized in Table A-17.

#### CONFIDENCE LIMITS FOR EXTRAPOLATIONS FROM KEY SITE

Statistical confidence limits for the yearly average DNL estimates based on extrapolations from the key site were determined by combining the key site variability and the variability of HNL differences

$$\text{Confidence limits} = \bar{L}_{dn} + \Delta \pm 1.64 \sqrt{\left(\frac{CI}{2(1.64)}\right)^2 + s_{\Delta}^2} \quad (18)$$

where

$\bar{L}_{dn}$  = key site yearly average DNL estimate, dB

$\Delta$  = average energy HNL difference, satellite site (-) key site, dB

CI = confidence interval for the key site DNL estimate, dB

$s_{\Delta}$  = standard deviation of the arithmetic differences in HNL values, satellite site (-) key site.

TABLE A-18 SUMMATION OF MEAN AND VARIANCE OF MEASURED SEL CONTRIBUTION  
TO SYNTHESIZED DNL VALUES.

Site 2

| Type<br>A/C  | Operations |      |      |    | Frequency              |                         |                      | Measured SEL         |  |   |                          |                               | Equiv. Day                          |  |
|--------------|------------|------|------|----|------------------------|-------------------------|----------------------|----------------------|--|---|--------------------------|-------------------------------|-------------------------------------|--|
|              | App        |      | T/O  |    | Day,<br>F <sub>d</sub> | Night<br>F <sub>n</sub> | Equiv.<br>Day,<br>F* | Energy<br>Avg,<br>dB | Energy<br>Mean<br>E,<br>x10 <sup>-10</sup> | Energy<br>Std<br>Dev, S<br>x10 <sup>-10</sup> | No.<br>SEL<br>Samp.<br>N | S<br>√N<br>x10 <sup>-10</sup> | Energy<br>E·F<br>x10 <sup>-10</sup> | Vari-<br>ance,<br>F[s/√N] <sup>2</sup><br>x10 <sup>-20</sup> |
|              | SI         | Patt | Patt | SO |                        |                         |                      |                      |  |   |                          |                               |                                     |  |
| KC -<br>135A | ✓          |      |      |    | 3.180                  | 0.510                   | 8.28                 | 94.1                 | .26  | .23   | 40                       | .04                           | 2.15                                | .01  |
|              |            | ✓    |      |    | 12.412                 | 2.670                   | 39.112               | 95.9                 | .39  | .91   | 100                      | .09                           | 15.25                               | .32  |
|              |            |      | ✓    |    | 8.240                  | 1.780                   | 26.04                | 98.3                 | .68  | 3.10  | 48                       | .45                           | 17.71                               | 5.27   |
|              |            |      |      | ✓  | 2.871                  | 0.426                   | 7.131                | 111.2                | 13.18                                      | 14.5  | 35                       | 2.45                          | 93.99                               | 42.80  |
| B52G         | ✓          |      |      |    | 2.910                  | 0.960                   | 12.51                | 96.1                 | .41  | .23   | 21                       | .05                           | 5.13                                | .03  |
|              |            | ✓    |      |    | 9.750                  | 3.600                   | 45.75                | 96.1                 | .41  | .30   | 69                       | .04                           | 18.76                               | .07  |
|              |            |      | ✓    |    | 6.480                  | 2.400                   | 30.48                | 100.1                | 1.02                                       | 2.77  | 81                       | .31                           | 31.09                               | 2.93   |
|              |            |      |      | ✓  | 2.436                  | 0.225                   | 4.686                | 113.4                | 21.88                                      | 17.0  | 28                       | 3.21                          | 102.53                              | 48.29  |
| A-37         | ✓          |      |      |    | 14.430                 | 0.092                   | 15.35                | 84.0                 | .03  | .09   | 66                       | .01                           | .46                                 | .00  |
|              |            | ✓    |      |    | 7.168                  | 0.144                   | 8.608                | 84.0                 | .03  | .09   | 66                       | .01                           | .26                                 | .00  |
|              |            |      | ✓    |    | 4.770                  | 0.099                   | 5.76                 | 91.3                 | .13  | .22   | 60                       | .03                           | .75                                 | .01  |
|              |            |      |      | ✓  | 5.420                  | 0.140                   | 6.820                | 91.3                 | .13  | .22   | 60                       | .07                           | .89                                 | .03  |
| T-37         | ✓          |      |      |    | 5.400                  | 0                       | 5.40                 | 77.5                 | .01  | .007  | 36                       | -                             | .05                                 | .00  |
|              |            | ✓    |      |    | 19.260                 | 0                       | 19.26                | 77.5                 | .01  | .007  | 36                       | -                             | .19                                 | .00  |
|              |            |      | ✓    |    | 10.50                  | 0.02                    | 10.70                | 89.2                 | .08  | .12   | 15                       | .03                           | .86                                 | .01  |
|              |            |      |      | ✓  | 3.580                  | 0.02                    | 3.78                 | 89.2                 | .08  | .12   | 15                       | .03                           | .30                                 | .00  |
| T-38         | ✓          |      |      |    | 1.780                  | 0.102                   | 2.80                 | 87.7                 | .06  | .16   | 41                       | .02                           | .17                                 | .00  |
|              |            | ✓    |      |    | 4.160                  | 0.298                   | 7.14                 | 87.7                 | .06  | .16   | 41                       | .02                           | .43                                 | .00  |
|              |            |      | ✓    |    | 2.548                  | 0.172                   | 4.268                | 87.5                 | .06  | .06   | 12                       | .02                           | .26                                 | .00  |
|              |            |      |      | ✓  | 1.190                  | 0.07                    | 1.890                | 87.5                 | .06  | .06   | 12                       | .02                           | .11                                 | .00  |
| T-39         | ✓          |      |      |    | 2.540                  | 1.220                   | 14.74                | 88.1                 | .06  | .14   | 20                       | .03                           | .88                                 | .01  |
|              |            | ✓    |      |    | 5.230                  | 0.190                   | 7.13                 | 88.1                 | .06  | .14   | 20                       | .03                           | .43                                 | .01  |
|              |            |      | ✓    |    | 3.490                  | 0.820                   | 11.69                | 93.9                 | .25  | .43   | 16                       | .11                           | 2.92                                | .01  |
|              |            |      |      | ✓  | 2.370                  | 0.130                   | 3.67                 | 93.9                 | .25  | .43   | 16                       | .11                           | .92                                 | .04  |
| Other        | ✓          |      |      |    | 2.80                   | 0.10                    | 3.80                 | -                    |  |   |                          |                               |                                     |  |
|              |            | ✓    |      |    | 5.875                  | 0.57                    | 11.575               | -                    |  |   |                          |                               |                                     |  |
|              |            |      | ✓    |    | 4.08                   | 0.41                    | 8.18                 | -                    |  |   |                          |                               |                                     |  |
|              |            |      |      | ✓  | 1.75                   | 0.07                    | 2.45                 | -                    |  |   |                          |                               |                                     |  |
| Totals       |            |      |      |    | 156.62                 | 17.238                  | 329                  |                      |  |   |                          |                               | 296.49                              | 99.85  |

$$*F = F_d + 10F_n$$

For example, from the example given as Eq. (14) (or from Table A-17), the confidence interval for the Site 2 DNL estimate based on all days DNL's corrected for total aircraft volume is +1.4, -2.1 dB. In addition, from Table A-15, the standard deviation for the average difference between Site 1 and Site 2 is 0.5 dB. Table A-15 also derives the nominal extrapolated DNL value for Site 1 which is  $72.7 + 3 = 75.7$  dB. Therefore, the confidence limits for the Site 1 DNL estimate is

$$\begin{aligned} \text{Confidence limits} &= 75.7 \pm 1.64 \sqrt{\left(\frac{1.4 + 2.1}{2(1.64)}\right)^2 + (0.5)^2} \quad (19) \\ &= 77.6/73.8 \text{ dB} \end{aligned}$$

The confidence interval is  $\pm 1.9$  dB. The extrapolated average day DNL estimates with associated confidence intervals for all satellite sites are summarized in Table A-17.

Unfortunately, this calculation procedure is not rigorously sound for two reasons. First, the confidence intervals for the key site DNL-based estimate was determined using the Student t distribution. Use of Eq. 19 assumes that the confidence interval has an equivalent normal distribution variance. However, the result tends to be conservative, producing a larger variance than the original sample mean variance. Second, using the arithmetic difference is inconsistent. However, computing the variance of the ratio of two random variables (in this case the average acoustic energy at two sites) is extremely difficult. An alternate approach, summing the variances of the estimates of sample averages, would be correct only if the standard deviations are relatively small. Suffice to say that the procedure used produces credible values.

#### OTHER ERROR SOURCES AND OVERALL CONFIDENCE INTERVALS

In addition to the variability within sets of measured data, other factors contribute to the uncertainty in the final result. The factors and the estimated values are as follows:

| <u>Factors</u>        | <u>Type Error</u>  | <u>Value, dB</u> |
|-----------------------|--------------------|------------------|
| Temperature-thrust    | Uncorrected bias   | 0.7              |
| Temperature-humidity  |                    |                  |
| absorption            | Uncorrected bias   | 0.4              |
| Instrumentation       | Uncertainty        | 0.2              |
| <u>Field Test</u>     | <u>Uncertainty</u> | <u>0.5</u>       |
| Root sum square total |                    | 0.97             |

The temperature and humidity bias errors were identified, evaluated, but not corrected for in the section on Post Test Bias Corrections. These uncorrected bias errors are simply squared and added to the variance of the random errors.

The variability of instrumentation errors which vary day to day are already accounted for in the variability in the measured data. Instrumentation errors which do not average out (for example a nighttime sensitivity increase or decrease) add additional uncertainty. This error source is considered small, 0.2 dB.

Finally, aircraft operational factors which are under the pilot's control are usually assumed to be represented faithfully, on the average, during the field test. These factors are power settings, speeds/altitude profiles, and flight tracks. If these factors were indeed representative during the field test, no bias error results from extrapolation of measured noise levels to yearly average day DNL estimates. However, experience has shown that this is not exactly the case. Repeating field measurement programs under apparently identical conditions produces differences in results which are not accountable for by the measurement variability. Based on this somewhat qualitative experience, a value of 0.5 dB was chosen for this factor.

The overall standard deviation of the other error sources (0.97 dB) was combined with confidence intervals obtained from measurement variability (Table A-17), to arrive at "realistic" confidence intervals as follows:

$$\text{Realistic Confidence Interval} = \pm 1.64 \sqrt{\left(\frac{\text{CI}}{2(1.64)}\right)^2 + (0.97)^2} \quad (20)$$

where

CI = confidence interval from measurements.

The "realistic" confidence intervals are listed with the calibrator bias corrected DNL estimates in Table A-19. Inspection of the confidence intervals in Table A-19 shows that statistical accuracy of SEL-derived estimates is better than

Table A-19 Barksdale AFB Yearly DNL Estimates With Realistic Confidence Intervals Based on All Sources of Variability

| Data Source                   | SITE |        |  |      |        |  |      |        |  |      |        |  |      |        |  |      |        |  |
|-------------------------------|------|--------|--|------|--------|--|------|--------|--|------|--------|--|------|--------|--|------|--------|--|
|                               | 1    |        |  | 2    |        |  | 3    |        |  | 202  |        |  | 203  |        |  | 4    |        |  |
|                               | Avg  | 90% CI |  | Avg  | 90% CI |  | Avg  | 90% CI |  | Avg  | 90% CI |  | Avg  | 90% CI |  | Avg  | 90% CI |  |
| All Days Measurements         |      |        |  |      |        |  |      |        |  |      |        |  |      |        |  |      |        |  |
| No Corrections                | -    | -      |  | 72.0 | +3.0   |  | -    | -      |  | -    | -      |  | -    | -      |  | -    | -      |  |
| Corrected for total A/C       | -    | -      |  | 72.7 | +2.4   |  | -    | -      |  | -    | -      |  | -    | -      |  | -    | -      |  |
| Corrected for heavy A/C       | -    | -      |  | 72.6 | +2.4   |  | -    | -      |  | -    | -      |  | -    | -      |  | -    | -      |  |
| Week Days Measurements        |      |        |  |      |        |  |      |        |  |      |        |  |      |        |  |      |        |  |
| No Corrections                | -    | -      |  | 73.5 | +2.2   |  | -    | -      |  | -    | -      |  | -    | -      |  | -    | -      |  |
| Corrected for total A/C       | -    | -      |  | 73.2 | +2.3   |  | -    | -      |  | -    | -      |  | -    | -      |  | -    | -      |  |
| Corrected for heavy A/C       | -    | -      |  | 72.4 | +2.6   |  | -    | -      |  | -    | -      |  | -    | -      |  | -    | -      |  |
| SEL Synthesis Measured Data   | 79.1 | +1.6   |  | 75.3 | +1.6   |  | 68.0 | +1.6   |  | 72.3 | +1.6   |  | 73.2 | +1.6   |  | -    | -      |  |
| Extrapolation from Site 2 DNL | 75.7 | +2.5   |  | -    | -      |  | 66.3 | +2.6   |  | 70.8 | +2.6   |  | 71.1 | +2.5   |  | 66.7 | +2.6   |  |
| NOISEMAP (REF)                | 80.5 | -      |  | 76.4 | -      |  | 69.4 | -      |  | 75.8 | -      |  | 73.7 | -      |  | 69.0 | -      |  |

for DNL-derived estimates but not by as great a margin as indicated in the previous table (which was based only on measurement variability). Another important observation is that the "realistic" confidence intervals do not account for the differences between measured and predicted DNL values.

#### CRITIQUE OF FIELD MEASUREMENT RESULTS

In the previous section, the average day DNL estimates for all sites at Barksdale AFB were found to be consistently lower than NOISEMAP predictions. In this section, the differences are traced through individual aircraft/operation SEL differences to incorrect NOISEMAP input data. This procedure requires accurate reconstruction of aircraft flight profiles from NOISEMAP chronicles to arrive at a close approximation of NOISEMAP SEL values.

#### NOISEFILE 1.0 SEL VALUES

Nominal SEL values for most military aircraft have been determined as a function of slant distance. The compilation of these data is called NOISEFILE 1.0. The data are available both in computer tape files and in report form, References 18-23. Listings are presented for takeoff power, cruise power, and approach power for each aircraft. Additional listings are presented for special power settings such as afterburner and water injection. Reference 18 also presents a method for adjusting the SEL values for power settings and speeds which are not identical to the nominal values.

The first step in computing NOISEMAP SEL's was to assemble the SEL listings from References 18-23 for the aircraft at Barksdale AFB as shown in Table A-20. This summary identifies the type of aircraft, the unique aircraft/operation code, the power setting expressed in RPM and/or EPR, and the aircraft speed. Both air-to-ground and ground-to-ground listings are presented.

#### NOISEMAP AIRCRAFT OPERATIONAL PARAMETERS

The information which is input to NOISEMAP to describe each individual aircraft mission is listed in the NOISEMAP chronicles. The mission frequencies are summarized, but other parameters appear in the order in which the input data package was assembled. The parameters used to reconstruct NOISEMAP SEL values are:

TABLE A-20 NOISEFILE 1.0 SEL SUMMARY (59°F, 70% R.H.)

Air-To-Ground Propagation, Operation/Power Setting: Takeoff

| SIntDist.(ft) | A/C Type | KC-135A | KC-135A | B-52-G  | A-37    | T-37    | T-38    | T-38    | T-39    | C-130A    |  |
|---------------|----------|---------|---------|---------|---------|---------|---------|---------|---------|-----------|--|
|               | ACC/OPC  | 026/102 | 026/103 | 043/103 | 504/103 | 024/103 | 033/101 | 033/103 | 032/103 | 006/103   |  |
|               | RPM/EPR  | 96/2.85 | 96/2.45 | 94/2.37 | 100     | 99      | 100     | 100     | 100     | 16800/970 |  |
|               | Knots    | 200     | 200     | 170     | 300     | 170     | 300     | 300     | 180     | 170       |  |
| 200           |          | 128.6   | 126.9   | 129.9   | 115.2   | 107.2   | 123.8   | 115.1   | 112.4   | 98.3      |  |
| 250           |          | 127.1   | 125.6   | 128.6   | 113.9   | 106.0   | 122.0   | 113.9   | 111.1   | 97.2      |  |
| 315           |          | 125.6   | 124.2   | 127.4   | 112.7   | 104.8   | 120.1   | 112.6   | 109.9   | 96.1      |  |
| 400           |          | 124.2   | 122.8   | 126.1   | 111.3   | 103.6   | 118.3   | 111.3   | 108.6   | 94.9      |  |
| 500           |          | 122.7   | 121.4   | 124.7   | 110.0   | 102.2   | 116.4   | 109.9   | 107.3   | 93.7      |  |
| 630           |          | 121.2   | 120.0   | 123.3   | 108.5   | 100.9   | 114.6   | 108.5   | 105.9   | 92.4      |  |
| 800           |          | 119.8   | 118.5   | 121.9   | 107.0   | 99.4    | 112.9   | 107.0   | 104.4   | 91.1      |  |
| 1000          |          | 118.2   | 117.0   | 120.4   | 105.4   | 97.9    | 111.2   | 105.4   | 102.9   | 89.8      |  |
| 1250          |          | 116.6   | 115.5   | 118.8   | 103.7   | 96.3    | 109.5   | 103.6   | 101.3   | 88.4      |  |
| 1600          |          | 115.0   | 113.8   | 117.1   | 101.9   | 94.6    | 107.8   | 101.8   | 99.6    | 86.9      |  |
| 2000          |          | 113.2   | 112.1   | 115.3   | 99.9    | 92.8    | 106.0   | 99.9    | 97.8    | 85.4      |  |
| 2500          |          | 111.4   | 110.3   | 113.4   | 97.8    | 90.9    | 104.0   | 97.8    | 95.8    | 83.8      |  |
| 3150          |          | 109.4   | 108.4   | 111.4   | 95.6    | 88.9    | 102.0   | 95.6    | 93.8    | 82.1      |  |
| 4000          |          | 107.3   | 106.4   | 109.3   | 93.2    | 86.7    | 99.9    | 93.2    | 91.6    | 80.4      |  |
| 5000          |          | 105.0   | 104.2   | 107.0   | 90.6    | 84.4    | 97.6    | 90.6    | 89.3    | 78.5      |  |
| 6300          |          | 102.6   | 101.9   | 104.5   | 87.9    | 81.9    | 95.2    | 87.9    | 86.9    | 76.5      |  |
| 8000          |          | 100.0   | 99.4    | 101.9   | 84.9    | 79.2    | 92.5    | 85.0    | 84.2    | 74.3      |  |
| 10000         |          | 97.2    | 96.7    | 99.1    | 81.8    | 76.2    | 89.6    | 81.8    | 81.4    | 72.1      |  |
| 12500         |          | 94.1    | 93.8    | 96.0    | 78.4    | 73.0    | 86.5    | 78.4    | 78.3    | 69.8      |  |
| 16000         |          | 90.9    | 90.7    | 92.8    | 74.7    | 69.6    | 83.2    | 74.8    | 75.1    | 67.4      |  |
| 20000         |          | 87.4    | 87.3    | 89.2    | 70.9    | 65.7    | 79.6    | 71.0    | 71.6    | 65.1      |  |
| 25000         |          | 83.6    | 83.7    | 85.4    | 66.8    | 61.6    | 75.8    | 66.9    | 67.6    | 62.7      |  |

Ground-To-Ground Propagation, Operation/Power Setting:

| SIntDist.(ft) | A/C Type | KC-135  | KC-135  | B-52G   | A-37    | T-37    | T-38    | T-38    | T-39    | C-130A    |  |
|---------------|----------|---------|---------|---------|---------|---------|---------|---------|---------|-----------|--|
|               | ACC/OPC  | 026/102 | 026/103 | 043/103 | 504/103 | 024/103 | 033/101 | 033/103 | 032/103 | 006/103   |  |
|               | RPM/EPR  | 96/2.85 | 96/2.45 | 94/2.37 | 100     | 99      | 100     | 100     | 100     | 16800/970 |  |
|               | Knots    | 200     | 200     | 170     | 300     | 170     | 300     | 300     | 180     | 170       |  |
| 200           |          | 123.6   | 121.9   | 124.9   | 110.2   | 102.2   | 118.8   | 110.1   | 107.4   | 93.3      |  |
| 250           |          | 122.1   | 120.6   | 123.6   | 108.9   | 101.0   | 117.0   | 108.9   | 106.1   | 92.2      |  |
| 315           |          | 120.6   | 119.2   | 122.4   | 107.7   | 99.8    | 115.1   | 107.6   | 104.9   | 91.1      |  |
| 400           |          | 119.1   | 117.8   | 121.1   | 106.3   | 98.6    | 113.3   | 106.3   | 103.6   | 89.9      |  |
| 500           |          | 117.7   | 116.4   | 119.7   | 105.0   | 97.2    | 111.4   | 104.9   | 102.2   | 88.7      |  |
| 630           |          | 116.2   | 114.9   | 118.3   | 103.5   | 95.9    | 109.6   | 103.5   | 100.8   | 87.4      |  |
| 800           |          | 114.6   | 113.5   | 116.8   | 102.0   | 94.4    | 107.9   | 102.0   | 99.4    | 86.1      |  |
| 1000          |          | 113.1   | 111.9   | 115.3   | 100.4   | 92.9    | 106.2   | 100.3   | 97.8    | 84.7      |  |
| 1250          |          | 111.3   | 110.3   | 113.7   | 98.7    | 91.2    | 104.4   | 98.6    | 96.2    | 83.2      |  |
| 1600          |          | 109.5   | 108.5   | 112.0   | 96.8    | 89.5    | 102.6   | 96.8    | 94.4    | 81.6      |  |
| 2000          |          | 107.6   | 106.7   | 110.1   | 94.8    | 87.6    | 100.7   | 94.8    | 92.6    | 79.9      |  |
| 2500          |          | 105.3   | 104.5   | 108.1   | 92.7    | 85.5    | 98.6    | 92.6    | 90.4    | 77.9      |  |
| 3150          |          | 102.6   | 102.1   | 105.8   | 90.3    | 83.2    | 96.2    | 90.2    | 88.0    | 75.6      |  |
| 4000          |          | 99.4    | 99.2    | 103.1   | 87.6    | 80.4    | 93.5    | 87.6    | 85.3    | 73.0      |  |
| 5000          |          | 95.7    | 95.8    | 100.0   | 84.5    | 77.2    | 90.2    | 84.4    | 82.1    | 70.0      |  |
| 6300          |          | 91.5    | 92.0    | 96.5    | 81.0    | 73.6    | 86.6    | 81.0    | 78.5    | 66.7      |  |
| 8000          |          | 87.8    | 88.7    | 93.3    | 77.6    | 70.3    | 83.3    | 77.5    | 75.2    | 63.7      |  |
| 10000         |          | 83.7    | 85.0    | 89.7    | 73.7    | 66.6    | 79.6    | 73.7    | 71.4    | 60.4      |  |
| 12500         |          | 79.1    | 80.8    | 85.7    | 69.5    | 62.5    | 75.4    | 69.5    | 67.3    | 56.8      |  |
| 16000         |          | 73.9    | 76.2    | 81.3    | 64.7    | 57.9    | 70.7    | 64.7    | 62.7    | 52.7      |  |
| 20000         |          | 68.3    | 71.1    | 76.4    | 59.4    | 52.7    | 65.4    | 59.4    | 57.5    | 48.5      |  |
| 25000         |          | 62.3    | 65.4    | 70.8    | 53.4    | 46.9    | 59.5    | 53.5    | 51.8    | 44.2      |  |

TABLE A-20 NOISEFILE 1.0 SEL SUMMARY (59°F, 70% R.H.)

Air-To-Ground Propagation, Operation/Power Setting: *CRUISE*

| SlntDist.(ft) | A/C Type | KC/35A  | B-52-G    | A-37    | T-37    | T-38    | T-39    |  |  |  |  |
|---------------|----------|---------|-----------|---------|---------|---------|---------|--|--|--|--|
| ACC/OPC       |          | 026/104 | 043/104   | 504/104 | 024/104 | 033/104 | 032/104 |  |  |  |  |
| RPM/EPR       |          | 86/1.50 | 83.5/1.48 | 90      | 90      | 90      | 89/1.66 |  |  |  |  |
| Knots         |          | 300     | 250       | 300     | 225     | 300     | 250     |  |  |  |  |
| 200           |          | 108.8   | 113.4     | 95.9    | 97.9    | 95.8    | 101.8   |  |  |  |  |
| 250           |          | 107.5   | 112.2     | 94.8    | 96.7    | 94.6    | 100.7   |  |  |  |  |
| 315           |          | 106.2   | 110.9     | 93.6    | 95.5    | 93.4    | 99.4    |  |  |  |  |
| 400           |          | 104.8   | 109.6     | 92.3    | 94.2    | 92.2    | 98.2    |  |  |  |  |
| 500           |          | 103.3   | 108.2     | 91.0    | 92.9    | 90.9    | 96.9    |  |  |  |  |
| 630           |          | 101.8   | 106.8     | 89.7    | 91.5    | 89.6    | 95.5    |  |  |  |  |
| 800           |          | 100.2   | 105.3     | 88.3    | 90.0    | 88.2    | 94.0    |  |  |  |  |
| 1000          |          | 98.5    | 103.7     | 86.8    | 88.4    | 86.7    | 92.4    |  |  |  |  |
| 1250          |          | 96.8    | 102.1     | 85.2    | 86.8    | 85.1    | 90.8    |  |  |  |  |
| 1600          |          | 94.9    | 100.3     | 83.6    | 85.0    | 83.5    | 89.0    |  |  |  |  |
| 2000          |          | 93.0    | 98.5      | 81.8    | 83.2    | 81.7    | 87.2    |  |  |  |  |
| 2500          |          | 91.0    | 96.5      | 79.9    | 81.3    | 79.8    | 85.1    |  |  |  |  |
| 3150          |          | 88.8    | 94.4      | 77.9    | 79.2    | 77.8    | 82.9    |  |  |  |  |
| 4000          |          | 86.6    | 92.2      | 75.7    | 76.9    | 75.6    | 80.6    |  |  |  |  |
| 5000          |          | 84.2    | 89.8      | 73.3    | 74.6    | 73.3    | 78.0    |  |  |  |  |
| 6300          |          | 81.6    | 87.3      | 70.8    | 72.0    | 70.7    | 75.3    |  |  |  |  |
| 8000          |          | 78.8    | 84.7      | 68.0    | 69.2    | 68.0    | 72.4    |  |  |  |  |
| 10000         |          | 75.8    | 81.8      | 65.0    | 66.2    | 65.0    | 69.3    |  |  |  |  |
| 12500         |          | 72.6    | 78.8      | 61.8    | 63.0    | 61.8    | 66.1    |  |  |  |  |
| 16000         |          | 69.0    | 75.6      | 58.4    | 59.5    | 58.4    | 62.6    |  |  |  |  |
| 20000         |          | 65.2    | 72.1      | 54.8    | 55.7    | 54.8    | 59.0    |  |  |  |  |
| 25000         |          | 61.1    | 68.4      | 51.0    | 51.7    | 51.0    | 55.1    |  |  |  |  |

Ground-To-Ground Propagation, Operation/Power Setting:

| SlntDist.(ft) | A/C Type | KC/35A  | B-52-G    | A-37    | T-37    | T-38    | T-39    |  |  |  |  |
|---------------|----------|---------|-----------|---------|---------|---------|---------|--|--|--|--|
| ACC/OPC       |          | 026/104 | 043/104   | 504/104 | 024/104 | 033/104 | 032/104 |  |  |  |  |
| RPM/EPR       |          | 86/1.50 | 83.5/1.48 | 90      | 90      | 90      | 89/1.66 |  |  |  |  |
| Knots         |          | 300     | 250       | 300     | 225     | 300     | 250     |  |  |  |  |
| 200           |          | 103.8   | 108.4     | 90.9    | 92.9    | 90.8    | 96.8    |  |  |  |  |
| 250           |          | 102.5   | 107.2     | 89.8    | 91.7    | 89.6    | 95.7    |  |  |  |  |
| 315           |          | 101.2   | 105.9     | 88.6    | 90.5    | 88.4    | 94.4    |  |  |  |  |
| 400           |          | 99.8    | 104.6     | 87.3    | 89.2    | 87.2    | 93.2    |  |  |  |  |
| 500           |          | 98.3    | 103.2     | 86.0    | 87.9    | 85.9    | 91.8    |  |  |  |  |
| 630           |          | 96.8    | 101.8     | 84.7    | 86.5    | 84.6    | 90.5    |  |  |  |  |
| 800           |          | 95.2    | 100.3     | 83.3    | 85.0    | 83.1    | 89.0    |  |  |  |  |
| 1000          |          | 93.5    | 98.7      | 81.8    | 83.4    | 81.7    | 87.4    |  |  |  |  |
| 1250          |          | 91.7    | 97.0      | 80.2    | 81.7    | 80.1    | 85.8    |  |  |  |  |
| 1600          |          | 89.8    | 95.2      | 78.5    | 80.0    | 78.4    | 84.0    |  |  |  |  |
| 2000          |          | 87.8    | 93.3      | 76.7    | 78.1    | 76.5    | 82.1    |  |  |  |  |
| 2500          |          | 85.6    | 91.2      | 74.6    | 76.0    | 74.5    | 79.9    |  |  |  |  |
| 3150          |          | 83.1    | 88.8      | 72.4    | 73.7    | 72.3    | 77.6    |  |  |  |  |
| 4000          |          | 80.3    | 86.1      | 69.8    | 71.1    | 69.7    | 74.9    |  |  |  |  |
| 5000          |          | 77.0    | 83.0      | 66.8    | 68.0    | 66.7    | 71.7    |  |  |  |  |
| 6300          |          | 73.3    | 79.5      | 63.5    | 64.6    | 63.3    | 68.2    |  |  |  |  |
| 8000          |          | 69.8    | 76.2      | 60.1    | 61.3    | 60.0    | 64.7    |  |  |  |  |
| 10000         |          | 66.0    | 72.5      | 56.4    | 57.6    | 56.4    | 60.9    |  |  |  |  |
| 12500         |          | 61.7    | 68.5      | 52.3    | 53.5    | 52.3    | 56.7    |  |  |  |  |
| 16000         |          | 56.9    | 64.0      | 47.6    | 48.9    | 47.7    | 52.0    |  |  |  |  |
| 20000         |          | 51.5    | 59.0      | 42.4    | 43.7    | 42.6    | 46.9    |  |  |  |  |
| 25000         |          | 45.4    | 53.5      | 36.7    | 37.9    | 36.9    | 41.2    |  |  |  |  |

TABLE A-20 NOISEFILE 1.0 SEL SUMMARY (59°F, 70% R.H.)

Air-To-Ground Propagation, Operation/Power Setting: *APPROACH*

| SlntDist.(ft) | A/C Type | KC/35A                | B-52-G                | A-37                  | T-37                  | T-38                  | T-39                    | C-130A                 |  |  |  |
|---------------|----------|-----------------------|-----------------------|-----------------------|-----------------------|-----------------------|-------------------------|------------------------|--|--|--|
|               | ACC/OPC  | <del>026</del><br>105 | <del>043</del><br>105 | <del>504</del><br>105 | <del>024</del><br>105 | <del>033</del><br>105 | <del>032</del><br>105   | <del>006</del><br>105  |  |  |  |
|               | RPM/EPR  | <del>90</del><br>1.75 | <del>86</del><br>1.57 | <del>91</del>         | <del>80</del>         | <del>91</del>         | <del>79.5</del><br>1.37 | <del>4000</del><br>580 |  |  |  |
|               | Knots    | 160                   | 140                   | 170                   | 105                   | 170                   | 115                     | 140                    |  |  |  |
| 200           |          | 115.2                 | 118.0                 | 100.4                 | 103.0                 | 100.3                 | 100.7                   | 96.8                   |  |  |  |
| 250           |          | 114.0                 | 116.7                 | 99.2                  | 101.8                 | 99.2                  | 99.5                    | 95.6                   |  |  |  |
| 315           |          | 112.8                 | 115.5                 | 98.0                  | 100.6                 | 98.0                  | 98.3                    | 94.4                   |  |  |  |
| 400           |          | 111.5                 | 114.2                 | 96.8                  | 99.3                  | 96.8                  | 97.1                    | 93.2                   |  |  |  |
| 500           |          | 110.2                 | 112.9                 | 95.6                  | 98.0                  | 95.5                  | 95.8                    | 91.9                   |  |  |  |
| 630           |          | 108.8                 | 111.5                 | 94.3                  | 96.7                  | 94.2                  | 94.5                    | 90.6                   |  |  |  |
| 800           |          | 107.4                 | 110.1                 | 92.9                  | 95.2                  | 92.9                  | 93.1                    | 89.2                   |  |  |  |
| 1000          |          | 105.9                 | 108.6                 | 91.5                  | 93.7                  | 91.4                  | 91.6                    | 87.7                   |  |  |  |
| 1250          |          | 104.4                 | 107.0                 | 90.0                  | 92.2                  | 89.9                  | 90.0                    | 86.2                   |  |  |  |
| 1600          |          | 102.8                 | 105.4                 | 88.4                  | 90.5                  | 88.3                  | 88.4                    | 84.6                   |  |  |  |
| 2000          |          | 101.1                 | 103.7                 | 86.7                  | 88.8                  | 86.6                  | 86.6                    | 82.8                   |  |  |  |
| 2500          |          | 99.3                  | 101.9                 | 84.9                  | 87.0                  | 84.8                  | 84.7                    | 81.0                   |  |  |  |
| 3150          |          | 97.4                  | 100.0                 | 82.9                  | 85.0                  | 82.9                  | 82.6                    | 79.1                   |  |  |  |
| 4000          |          | 95.4                  | 97.9                  | 80.9                  | 82.9                  | 80.8                  | 80.5                    | 77.1                   |  |  |  |
| 5000          |          | 93.2                  | 95.7                  | 78.6                  | 80.7                  | 78.5                  | 78.2                    | 75.0                   |  |  |  |
| 6300          |          | 90.9                  | 93.4                  | 76.2                  | 78.3                  | 76.1                  | 75.7                    | 72.7                   |  |  |  |
| 8000          |          | 88.5                  | 90.9                  | 73.6                  | 75.7                  | 73.5                  | 73.1                    | 70.3                   |  |  |  |
| 10000         |          | 85.8                  | 88.3                  | 70.8                  | 72.9                  | 70.7                  | 70.3                    | 67.8                   |  |  |  |
| 12500         |          | 83.0                  | 85.4                  | 67.8                  | 69.8                  | 67.8                  | 67.3                    | 65.2                   |  |  |  |
| 16000         |          | 79.9                  | 82.4                  | 64.7                  | 66.5                  | 64.6                  | 64.1                    | 62.5                   |  |  |  |
| 20000         |          | 76.6                  | 79.1                  | 61.3                  | 62.8                  | 61.2                  | 60.7                    | 59.8                   |  |  |  |
| 25000         |          | 73.0                  | 75.7                  | 57.7                  | 58.8                  | 57.6                  | 57.2                    | 57.0                   |  |  |  |

Ground-To-Ground Propagation, Operation/Power Setting: *APPROACH*

| SlntDist.(ft) | A/C Type | KC/35A                | B-52-G                | A-37                  | T-37                  | T-38                  | T-39                    | C-130A                 |  |  |  |
|---------------|----------|-----------------------|-----------------------|-----------------------|-----------------------|-----------------------|-------------------------|------------------------|--|--|--|
|               | ACC/OPC  | <del>026</del><br>105 | <del>043</del><br>105 | <del>504</del><br>105 | <del>024</del><br>105 | <del>033</del><br>105 | <del>032</del><br>105   | <del>006</del><br>105  |  |  |  |
|               | RPM/EPR  | <del>90</del><br>1.75 | <del>86</del><br>1.57 | <del>91</del>         | <del>80</del>         | <del>91</del>         | <del>79.5</del><br>1.37 | <del>4000</del><br>580 |  |  |  |
|               | Knots    | 160                   | 140                   | 170                   | 105                   | 170                   | 115                     | 140                    |  |  |  |
| 200           |          | 110.2                 | 113.0                 | 95.4                  | 98.0                  | 95.3                  | 95.7                    | 91.8                   |  |  |  |
| 250           |          | 109.0                 | 111.7                 | 94.2                  | 96.8                  | 94.2                  | 94.5                    | 90.6                   |  |  |  |
| 315           |          | 107.8                 | 110.5                 | 93.0                  | 95.6                  | 93.0                  | 93.3                    | 89.4                   |  |  |  |
| 400           |          | 106.5                 | 109.2                 | 91.8                  | 94.3                  | 91.8                  | 92.1                    | 88.2                   |  |  |  |
| 500           |          | 105.2                 | 107.9                 | 90.6                  | 93.0                  | 90.5                  | 90.8                    | 86.9                   |  |  |  |
| 630           |          | 103.8                 | 106.5                 | 89.3                  | 91.6                  | 89.2                  | 89.5                    | 85.5                   |  |  |  |
| 800           |          | 102.3                 | 105.0                 | 87.9                  | 90.2                  | 87.8                  | 88.0                    | 84.1                   |  |  |  |
| 1000          |          | 100.8                 | 103.5                 | 86.4                  | 88.7                  | 86.4                  | 86.5                    | 82.6                   |  |  |  |
| 1250          |          | 99.3                  | 101.9                 | 84.9                  | 87.1                  | 84.8                  | 84.9                    | 81.0                   |  |  |  |
| 1600          |          | 97.6                  | 100.2                 | 83.2                  | 85.4                  | 83.2                  | 83.2                    | 79.3                   |  |  |  |
| 2000          |          | 95.8                  | 98.4                  | 81.5                  | 83.5                  | 81.4                  | 81.4                    | 77.5                   |  |  |  |
| 2500          |          | 93.8                  | 96.4                  | 79.5                  | 81.4                  | 79.4                  | 79.3                    | 75.5                   |  |  |  |
| 3150          |          | 91.5                  | 94.1                  | 77.3                  | 79.0                  | 77.2                  | 77.0                    | 73.2                   |  |  |  |
| 4000          |          | 88.9                  | 91.5                  | 74.7                  | 76.3                  | 74.6                  | 74.3                    | 70.6                   |  |  |  |
| 5000          |          | 85.8                  | 88.4                  | 71.7                  | 73.0                  | 71.6                  | 71.2                    | 67.5                   |  |  |  |
| 6300          |          | 82.4                  | 85.0                  | 68.4                  | 69.4                  | 68.2                  | 67.7                    | 64.1                   |  |  |  |
| 8000          |          | 79.3                  | 81.8                  | 65.2                  | 66.1                  | 65.0                  | 64.4                    | 61.0                   |  |  |  |
| 10000         |          | 75.9                  | 78.3                  | 61.6                  | 62.4                  | 61.4                  | 60.7                    | 57.4                   |  |  |  |
| 12500         |          | 72.1                  | 74.3                  | 57.6                  | 58.4                  | 57.5                  | 56.6                    | 53.6                   |  |  |  |
| 16000         |          | 67.8                  | 70.0                  | 53.1                  | 53.8                  | 53.0                  | 52.1                    | 49.2                   |  |  |  |
| 20000         |          | 63.1                  | 65.2                  | 48.1                  | 48.7                  | 48.1                  | 47.2                    | 44.5                   |  |  |  |
| 25000         |          | 57.8                  | 59.8                  | 42.6                  | 42.9                  | 42.6                  | 41.7                    | 39.4                   |  |  |  |

Flight tracks  
Altitude profiles  
Delta SEL

Typically, this data will be taken directly from the NOISEMAP chronicles. However, the speed and power setting data used to develop the NOISEMAP inputs were found to be incorrect for the two major aircraft, KC-135A and B52-G. A telephone conversation with Barksdale AFB, Hq. SAC/DEV and AFETO/DEE resulted in the following revised power and airspeeds:

|         |  |
|---------|--|
| KC-135A | 1.50 EPR @ 140 knots for approach and approach pattern |
|         | 1.80 EPR @ 180 knots for takeoff pattern               |
|         | 2.20 EPR @ 215 knots for takeoff for Sites 1, 2, 3     |
|         | @ 250 knots for Site 202                               |
|         | @ 285 knots for Site 203                               |
| B-52G   | 1.50 EPR @ 140 knots for approach and approach pattern |
|         | 1.80 EPR @ 180 knots for takeoff pattern               |
|         | 2.20 EPR @ 200 knots for takeoff for Sites 1, 2, 3     |
|         | @ 250 knots for Site 202                               |
|         | @ 285 knots for Site 203                               |

Table A-20 gives the nominal SEL values for the various aircraft. Tables A21-A26 give the equivalent NOISEMAP SEL's for the KC-135A and B-52G.

#### COMPARISON OF MEASURED AND PREDICTED SEL VALUES

In Tables A28-A32 the average measured SEL values, from Table A-12, are with the NOISEMAP SEL values from Tables A21-A27. All five measurement sites to the north of the runway were so evaluated. In Tables A28-A32 the significance of SEL difference is dependent on how much the particular mission contributes to the DNL.

The total DNL values calculated using measured data is within one dB of the calculated values using the NOISEMAP inputs. However, the difference in calculated values for individual procedures was often several dB. These differences are seen for both types of aircraft. The calculated values are consistently lower than the original NOISEMAP values. Up to .3 dB of this difference can be attributed to the fact that only the heavy aircraft were used in the calculations (see Table A-14). The remaining difference probably results from incorrect delta SEL values being used in the original NOISEMAP run.

TABLE A-21 AIRCRAFT OPERATIONAL INFORMATION  
STRAIGHT IN APPROACH

| KC-135-A |                  |                   |                        |         |                  |                 |
|----------|------------------|-------------------|------------------------|---------|------------------|-----------------|
| Site     | Noise<br>Profile | Slant<br>Distance | NOISEFILE<br>(1.0) SEL | Speed   | Power<br>Setting | NOISEMAP<br>SEL |
| 1        | 026/105          | 790               | 107.5                  | 140 kts | 1.5 EPR          | 103.6           |
| 2        | 026/105          | 1800              | 101.9                  | 140 kts | 1.5 EPR          | 98.0            |
| 3        | 026/105          | 4600              | 94.0                   | 140 kts | 1.5 EPR          | 90.1            |
| 202      | 026/105          | 1740              | 102.7                  | 140 kts | 1.5 EPR          | 98.8            |
| 203      | 026/105          | 1650              | 102.5                  | 140 kts | 1.5 EPR          | 98.6            |
| B-52-G   |                  |                   |                        |         |                  |                 |
| 1        | 043/105          | 790               | 110.2                  | 140 kts | 1.5 EPR          | 108.3           |
| 2        | 043/105          | 1800              | 104.5                  | 140 kts | 1.5 EPR          | 102.6           |
| 3        | 043/105          | 4600              | 96.5                   | 140 kts | 1.5 EPR          | 94.6            |
| 202      | 043/105          | 1740              | 104.8                  | 140 kts | 1.5 EPR          | 102.9           |
| 203      | 043/105          | 1650              | 105.1                  | 140 kts | 1.5 EPR          | 103.2           |

TABLE A-22 AIRCRAFT OPERATIONAL INFORMATION  
PATTERN APPROACH

| <u>KC-135A Mission 23</u> |                          |                           |                                |              |                          |             |
|---------------------------|--------------------------|---------------------------|--------------------------------|--------------|--------------------------|-------------|
| <u>Site</u>               | <u>Noise<br/>Profile</u> | <u>Slant<br/>Distance</u> | <u>NOISEFILE<br/>(1.0) SEL</u> | <u>Speed</u> | <u>Power<br/>Setting</u> | <u>DSEL</u> |
| 1                         | 026/105                  | 790                       | 107.5                          | 140 kts      | 1.5 EPR                  | -3.9        |
| 2                         | 026/105                  | 1800                      | 101.9                          | 140 kts      | 1.5 EPR                  | -3.9        |
| 3                         | 026/105                  | 4600                      | 94.0                           | 140 kts      | 1.5 EPR                  | -3.9        |
| 202                       | 026/105                  | 6600                      | 90.5                           | 140 kts      | 1.5 EPR                  | -3.9        |
| 203                       | 026/105                  | 15550(4 <sup>0</sup> )    | 67.9                           | 140 kts      | 1.5 EPR                  | -3.9        |
|                           |                          |                           |                                |              |                          | 103.6       |
|                           |                          |                           |                                |              |                          | 98.0        |
|                           |                          |                           |                                |              |                          | 90.1        |
|                           |                          |                           |                                |              |                          | 86.2        |
|                           |                          |                           |                                |              |                          | 64.0        |
| <u>B-52G Mission 22</u>   |                          |                           |                                |              |                          |             |
| 1                         | 043/105                  | 790                       | 110.2                          | 140 kts      | 1.5 EPR                  | -1.9        |
| 2                         | 043/105                  | 1800                      | 104.5                          | 140 kts      | 1.5 EPR                  | -1.9        |
| 3                         | 043/105                  | 4600                      | 96.5                           | 140 kts      | 1.5 EPR                  | -1.9        |
| 202                       | 043/105                  | 6600                      | 93.0                           | 140 kts      | 1.5 EPR                  | -1.9        |
| 203                       | 043/105                  | 15550(4 <sup>0</sup> )    | 69.9                           | 140 kts      | 1.5 EPR                  | -1.9        |
|                           |                          |                           |                                |              |                          | 108.2       |
|                           |                          |                           |                                |              |                          | 102.6       |
|                           |                          |                           |                                |              |                          | 94.6        |
|                           |                          |                           |                                |              |                          | 91.1        |
|                           |                          |                           |                                |              |                          | 68.0        |

TABLE A-23 AIRCRAFT OPERATIONAL INFORMATION  
PATTERN APPROACH

| Site                 | Noise<br>Profile | Slant<br>Distance | KC-135A Missions 31-35 |         |                  |                 |
|----------------------|------------------|-------------------|------------------------|---------|------------------|-----------------|
|                      |                  |                   | NOISEFILE<br>(1.0) SEL | Speed   | Power<br>Setting | NOISEMAP<br>SEL |
| 1                    | 026/105          | 710               | 108.1                  | 140 kts | 1.5 EPR          | 104.2           |
| 2                    | 026/105          | 1600              | 102.8                  | 140 kts | 1.5 EPR          | 98.9            |
| 3                    | 026/105          | 4500              | 94.2                   | 140 kts | 1.5 EPR          | 90.3            |
| 202                  | 026/105          | 1720              | 102.2                  | 140 kts | 1.5 EPR          | 98.3            |
| 203                  | 026/105          | 1600              | 102.8                  | 140 kts | 1.5 EPR          | 98.9            |
| B-52G Missions 31-35 |                  |                   |                        |         |                  |                 |
| 1                    | 043/105          | 700               | 110.9                  | 140 kts | 1.5 EPR          | 109.2           |
| 2                    | 043/105          | 1750              | 104.7                  | 140 kts | 1.5 EPR          | 102.8           |
| 3                    | 043/105          | 4500              | 96.7                   | 140 kts | 1.5 EPR          | 94.8            |
| 202                  | 043/105          | 1700              | 104.9                  | 140 kts | 1.5 EPR          | 103.0           |
| 203                  | 043/105          | 1700              | 104.9                  | 140 kts | 1.5 EPR          | 103.0           |

TABLE A-24 AIRCRAFT OPERATIONAL INFORMATIONAL  
PATTERN TAKEOFF

| KC-135A Mission 23 |                  |                   |                        |         |                  |                 |
|--------------------|------------------|-------------------|------------------------|---------|------------------|-----------------|
| Site               | Noise<br>Profile | Slant<br>Distance | NOISEFILE<br>(1.0) SEL | Speed   | Power<br>Setting | NOISEMAP<br>SEL |
| 1                  | 026/103          | 6900              | 101.0                  | 180 kts | 1.8 EPR          | 90.4            |
| 2                  | 026/103          | 9100              | 97.9                   | 180 kts | 1.8 EPR          | 87.3            |
| 3                  | 026/103          | 12150(6°)         | 88.5                   | 180 kts | 1.8 EPR          | 77.9            |
| 202                | 026/103          | 18000(4°)         | 73.6                   | 180 kts | 1.8 EPR          | 63.0            |
| 203                | 026/103          | -                 | -                      | -       | -                | -               |
| B-52G Mission 22   |                  |                   |                        |         |                  |                 |
| 1                  |                  | 8600              | 101.0                  | 180 kts | 1.8 EPR          | 91.7            |
| 2                  |                  | 10900(6%)         | 92.1                   | 180 kts | 1.8 EPR          | 82.8            |
| 3                  |                  | 13500(5%)         | 87.0                   | 180 kts | 1.8 EPR          | 77.7            |
| 202                |                  | -                 | -                      | -       | -                | -               |
| 203                |                  | -                 | -                      | -       | -                | -               |

TABLE A-25 AIRCRAFT OPERATIONAL INFORMATIONAL  
PATTERN TAKEOFF

| <u>KC-135A Missions 31-35</u> |                          |                           |                                |              |                          |             |                         |
|-------------------------------|--------------------------|---------------------------|--------------------------------|--------------|--------------------------|-------------|-------------------------|
| <u>Site</u>                   | <u>Noise<br/>Profile</u> | <u>Slant<br/>Distance</u> | <u>NOISEFILE<br/>(1.0) SEL</u> | <u>Speed</u> | <u>Power<br/>Setting</u> | <u>DSEL</u> | <u>NOISEMAP<br/>SEL</u> |
| 1                             | 026/103                  | 1750                      | 113.2                          | 180 kts      | 1.8 EPR                  | -10.6       | 102.6                   |
| 2                             | 026/103                  | 2300                      | 111.0                          | 180 kts      | 1.8 EPR                  | -10.6       | 100.4                   |
| 3                             | 026/103                  | 4300                      | 105.7                          | 180 kts      | 1.8 EPR                  | -10.6       | 95.1                    |
| 202                           | 026/103                  | 5300                      | 103.7                          | 180 kts      | 1.8 EPR                  | -10.6       | 93.1                    |
| 203                           | 026/103                  | 14000                     | 92.5                           | 180 kts      | 1.8 EPR                  | -10.6       | 81.9                    |
| <u>B-52G Missions 31-35</u>   |                          |                           |                                |              |                          |             |                         |
| 1                             | 43/103                   | 2000                      | 115.3                          | 180 kts      | 1.8 EPR                  | -9.3        | 106.0                   |
| 2                             | 43/103                   | 3400                      | 110.8                          | 180 kts      | 1.8 EPR                  | -9.3        | 101.5                   |
| 3                             | 43/103                   | 6000                      | 104.6                          | 180 kts      | 1.8 EPR                  | -9.3        | 95.3                    |
| 202                           | 43/103                   | 11100                     | 97.7                           | 180 kts      | 1.8 EPR                  | -9.3        | 88.4                    |
| 203                           | 43/103                   | 21500(4 <sup>0</sup> )    | 74.3                           | 180 kts      | 1.8 EPR                  | -9.3        | 65.0                    |

TABLE A-26 AIRCRAFT OPERATIONAL INFORMATION  
STRAIGHT-OUT TAKEOFF

| <u>KC-135A Mission 2</u> |                          |                           |                                |              |                          |                         |
|--------------------------|--------------------------|---------------------------|--------------------------------|--------------|--------------------------|-------------------------|
| <u>Site</u>              | <u>Noise<br/>Profile</u> | <u>Slant<br/>Distance</u> | <u>NOISEFILE<br/>(1.0) SEL</u> | <u>Speed</u> | <u>Power<br/>Setting</u> | <u>NOISEMAP<br/>SEL</u> |
| 1                        | 26/103                   | 1150                      | 116.1                          | 215          | 2.2 EPR                  | 111.5                   |
| 2                        | 26/103                   | 2070                      | 111.8                          | 215          | 2.2 EPR                  | 107.2                   |
| 3                        | 26/103                   | 4680                      | 104.9                          | 215          | 2.2 EPR                  | 100.3                   |
| 202                      | 26/103                   | 2510                      | 110.3                          | 250          | 2.2 EPR                  | 105.0                   |
| 203                      | 26/103                   | 3200                      | 108.3                          | 285          | 2.2 EPR                  | 102.5                   |
| <u>B-52G Mission 1</u>   |                          |                           |                                |              |                          |                         |
| 1                        | 213/103                  | 1860                      | 115.9                          | 200          | 2.2 EPR                  | 112.5                   |
| 2                        | 213/103                  | 2550                      | 113.3                          | 200          | 2.2 EPR                  | 109.9                   |
| 3                        | 213/103                  | 4900                      | 107.2                          | 200          | 2.2 EPR                  | 103.8                   |
| 202                      | 213/103                  | 2700                      | 112.7                          | 250          | 2.2 EPR                  | 108.3                   |
| 203                      | 213/103                  | 3000                      | 111.8                          | 280          | 2.2 EPR                  | 106.9                   |

TABLE A-27 AIRCRAFT OPERATIONAL INFORMATION  
STRAIGHT-OUT TAKEOFF

| KC-135A Mission 3 |                  |                   |                        |       |                  |                 |
|-------------------|------------------|-------------------|------------------------|-------|------------------|-----------------|
| Site              | Noise<br>Profile | Slant<br>Distance | NOISEFILE<br>(1.0) SEL | Speed | Power<br>Setting | DSEL            |
| 1                 | 026.103          | 1075              | 116.5                  | 215   | 2.2 EPR          | -4.6            |
| 2                 | 026.103          | 1950              | 112.2                  | 215   | 2.2 EPR          | -4.6            |
| 3                 | 026/103          | 5600              | 105.1                  | 215   | 2.2 EPR          | -4.6            |
| 202               | 026/103          | 1850              | 112.7                  | 250   | 2.2 EPR          | -5.3            |
| 203               | 026/103          | 1850              | 112.7                  | 285   | 2.2 EPR          | -5.8            |
|                   |                  |                   |                        |       |                  | NOISEMAP<br>SEL |
|                   |                  |                   |                        |       |                  | 111.9           |
|                   |                  |                   |                        |       |                  | 107.6           |
|                   |                  |                   |                        |       |                  | 100.5           |
|                   |                  |                   |                        |       |                  | 107.4           |
|                   |                  |                   |                        |       |                  | 106.9           |

TABLE A-28 SYNTHESIS OF SITE DNL VALUES FROM  
MEASURED AND NOISEMAP SEL VALUES

SITE 1

| Type<br>A/C    | Mission No. |       | Frequency |       |                      | SEL, dB                          |                                |                                      | DNL, dB                                |                       |      |      |      |
|----------------|-------------|-------|-----------|-------|----------------------|----------------------------------|--------------------------------|--------------------------------------|--|-----------------------|------|------|------|
|                | App         | T/O   | Day       | Night | Equiv.<br>Day,<br>N* | Measured<br>Values<br>(Table 20) | NOISEMAP<br>Values<br>(Fig. 8) | Derived<br>from<br>Measured<br>SEL's | Derived<br>from<br>NOISEMAP<br>SEL's** | Meas.<br>Pred.<br>(-) |      |      |      |
|                |             |       |           |       |                      |                                  |                                |                                      |  |                       | SI   | Patm | SO   |
| KC-135A        | 10          |       | 3.180     | 0.510 | 8.28                 | 102.2                            | 103.6                          | 62.0                                 | 63.4                                   | -1.4                  |      |      |      |
|                | 23          |       | 3.81      | 1.32  | 17.01                | 101.2                            | 103.6                          | 67.7                                 | 70.5                                   | -2.8                  |      |      |      |
|                | 31-35       |       | 8.602     | 1.35  | 22.1                 | 101.2                            | 104.2                          |                                      |  |                       |      |      |      |
|                |             | 23    | 2.54      | 0.44  | 6.94                 | 103.8                            | 90.4                           | 67.8                                 | 65.0                                   | 2.8                   |      |      |      |
|                |             | 31-35 | 5.7       | 0.9   | 14.7                 | 103.8                            | 102.6                          |                                      |  |                       |      |      |      |
|                |             |       | 2         | 2.461 | 0.36                 | 6.06                             | 113.4                          | 111.5                                | 72.5                                   | 70.2                  | 2.3  |      |      |
| B52G           |             |       | 3         | 0.41  | 1.08                 | 113.4                            | 106.9                          |                                      |  |                       |      |      |      |
|                | 10          |       | 2.910     | 0.960 | 12.51                | 106.5                            | 108.3                          | 68.1                                 | 69.9                                   | -1.8                  |      |      |      |
|                | 22          |       | 2.07      | 1.23  | 14.4                 | 100.7                            | 108.3                          | 67.9                                 | 76.0                                   | -8.1                  |      |      |      |
|                | 31-35       |       | 7.68      | 2.37  | 31.4                 | 100.7                            | 109.0                          |                                      |  |                       |      |      |      |
|                |             | 22    | 1.38      | 0.820 | 9.6                  | 106.6                            | 91.7                           | 72.0                                 | 69.9                                   | 2.1                   |      |      |      |
|                |             | 31-35 | 5.1       | 1.58  | 20.9                 | 106.6                            | 106.0                          | 72.6                                 | 69.8                                   | 2.8                   |      |      |      |
|                |             |       | 1         | 2.436 | 4.686                | 115.3                            | 112.5                          |                                      |  |                       |      |      |      |
| DNL Total      |             |       |           |       |                      |                                  |                                |                                      |  |                       | 78.9 | 79.8 | -9.9 |
| NOISEMAP (REF) |             |       |           |       |                      |                                  |                                |                                      |  |                       | 80.5 | 80.5 |      |

\*N = Freq.(day)+10xFreq.(night)      \*\*DNL = SEL+10LogN-49.4

TABLE A-29 SYNTHESIS OF SITE DNL VALUES FROM  
MEASURED AND NOISEMAP SEL VALUES

SITE 2

| Type<br>A/C    | Mission No. |       |     | Frequency |       | SEL, dB              |                                  |                                | DNL, dB                              |  |                       |
|----------------|-------------|-------|-----|-----------|-------|----------------------|----------------------------------|--------------------------------|--------------------------------------|--|-----------------------|
|                | App         |       | T/O | Day       | Night | Equiv.<br>Day,<br>N* | Measured<br>Values<br>(Table 20) | NOISEMAP<br>Values<br>(Fig. 8) | Derived<br>from<br>Measured<br>SEL's | Derived<br>from<br>NOISEMAP<br>SEL's** | Meas.<br>(-)<br>Pred. |
|                | SI          | Pat's | SO  |           |       |                      |                                  |                                |                                      |  |                       |
| KC-135A        | 10          |       |     | 3.180     | 0.510 | 8.28                 | 94.1                             | 98.0                           | 53.9                                 | 57.8                                   | -3.9                  |
|                | 23          |       |     | 3.81      | 1.32  | 17.01                | 95.9                             | 98.0                           | 62.4                                 | 65.0                                   | -2.6                  |
|                | 31-35       |       |     | 8.602     | 1.35  | 22.1                 | 95.9                             | 98.9                           |                                      |  |                       |
|                |             | 23    |     | 2.54      | 0.44  | 6.94                 | 98.3                             | 87.3                           | 62.3                                 | 62.8                                   | -5.5                  |
|                |             | 31-35 |     | 5.7       | 0.9   | 14.7                 | 98.3                             | 100.4                          |                                      |  |                       |
|                |             |       | 2   | 2.461     | 0.36  | 6.06                 | 111.2                            | 107.2                          | 70.3                                 | 66.4                                   | 3.9                   |
| B52G           |             |       | 3   | 0.41      | 0.067 | 1.08                 | 111.2                            | 107.6                          |                                      |  |                       |
|                | 10          |       |     | 2.910     | 0.960 | 12.51                | 96.1                             | 102.6                          | 57.7                                 | 64.2                                   | -6.5                  |
|                | 22          |       |     | 2.07      | 1.23  | 14.4                 | 96.1                             | 102.6                          | 63.3                                 | 70.0                                   | -6.7                  |
|                | 31-35       |       |     | 7.68      | 2.37  | 31.4                 | 96.1                             | 102.8                          |                                      |  |                       |
|                |             | 22    |     | 1.38      | 0.820 | 9.6                  | 100.1                            | 82.8                           | 65.5                                 | 65.3                                   | .2                    |
|                |             | 31-35 |     | 5.1       | 1.58  | 20.9                 | 100.1                            | 101.5                          | 70.7                                 | 67.2                                   | 3.5                   |
|                |             |       |     | 1         | 2.436 | 4.686                | 113.4                            | 109.9                          |                                      |  |                       |
| DNL Total      |             |       |     |           |       |                      |                                  |                                |                                      |  | .1                    |
| NOISEMAP (REF) |             |       |     |           |       |                      |                                  |                                |                                      |  | 76.4                  |

\*N = Freq.(day)+10xFreq.(night)      \*\*DNL = SEL+10logN-49.4

TABLE A-30 SYNTHESIS OF SITE DNL VALUES FROM  
MEASURED AND NOISEMAP SEL VALUES

SITE 3

| Type<br>A/C    | Mission No. |       |       | Frequency |       |                      | SEL, dB                          |                                |                                      | DNL, dB                                |                       |     |
|----------------|-------------|-------|-------|-----------|-------|----------------------|----------------------------------|--------------------------------|--------------------------------------|--|-----------------------|-----|
|                | App         | T/O   |       | Day       | Night | Equiv.<br>Day,<br>N* | Measured<br>Values<br>(Table 20) | NOISEMAP<br>Values<br>(Fig. 8) | Derived<br>from<br>Measured<br>SEL's | Derived<br>from<br>NOISEMAP<br>SEL's** | Meas.<br>(-)<br>Pred. |     |
|                |             | SI    | Pat 3 |           |       |                      |                                  |                                |                                      |  |                       | OS  |
|                |             |       |       |           |       |                      |                                  |                                |                                      |  |                       |     |
| KC-135A        | 10          |       |       | 3.180     | 0.510 | 8.28                 | 88.6                             | 90.1                           | 48.4                                 | 49.9                                   | -1.5                  |     |
|                |             | 23    |       | 3.81      | 1.32  | 17.01                | 82.9                             | 90.1                           | 49.4                                 | 56.7                                   | -7.3                  |     |
|                |             | 31-35 |       | 8.602     | 1.35  | 22.1                 | 82.9                             | 90.3                           |                                      |  |                       |     |
|                |             |       | 23    | 2.54      | 0.44  | 6.94                 | 87.6                             | 77.9                           | 51.6                                 | 57.4                                   | -5.8                  |     |
|                |             |       | 31-35 | 5.7       | 0.9   | 14.7                 | 87.6                             | 95.1                           |                                      |  |                       |     |
|                |             |       |       | 2         | 2.461 | 0.36                 | 6.06                             | 104.6                          | 100.3                                | 63.7                                   | 59.5                  | 4.3 |
| B52G           |             |       |       | 3         | 0.41  | 0.067                | 1.08                             | 104.6                          | 100.5                                |  |                       |     |
|                | 10          |       |       | 2.910     | 0.960 | 12.51                | 86.6                             | 94.6                           | 48.2                                 | 56.2                                   | -8.0                  |     |
|                |             | 22    |       | 2.07      | 1.23  | 14.4                 | -                                | 94.6                           | 0                                    | 62.0                                   |                       |     |
|                |             | 31-35 |       | 7.68      | 2.37  | 31.4                 | -                                | 94.8                           |                                      |  |                       |     |
|                |             |       | 22    | 1.38      | 0.820 | 9.6                  | 90.4                             | 77.7                           | 55.8                                 | 59.1                                   | -3.3                  |     |
|                |             |       | 31-35 | 5.1       | 1.58  | 20.9                 | 90.4                             | 95.3                           |                                      |  |                       |     |
| DNL Total      |             |       |       |           |       |                      | 107.1                            | 103.8                          | 64.4                                 | 61.1                                   | 3.3                   |     |
|                |             |       |       |           |       |                      |                                  |                                | 67.7                                 | 67.8                                   | -1                    |     |
| NOISEMAP (REF) |             |       |       |           |       |                      |                                  |                                | 69.4                                 | 69.4                                   |                       |     |

\*N = Freq.(day)+10xFreq.(night)

\*\*DNL = SEL+10logN-49.4

TABLE A-31 SYNTHESIS OF SITE DNL VALUES FROM  
MEASURED AND NOISEMAP SEL VALUES

SITE 202

| Type<br>A/C    | Mission No. |       |       | Frequency |       |                      | SEL, dB                          |                                |                                      | DNL, dB                                |                       |      |
|----------------|-------------|-------|-------|-----------|-------|----------------------|----------------------------------|--------------------------------|--------------------------------------|--|-----------------------|------|
|                | App         | T/O   |       | Day       | Night | Equiv.<br>Day,<br>N* | Measured<br>Values<br>(Table 20) | NOISEMAP<br>Values<br>(Fig. 8) | Derived<br>from<br>Measured<br>SEL's | Derived<br>from<br>NOISEMAP<br>SEL's** | Meas.<br>Pred.<br>(-) |      |
|                |             | SI    | Pat's |           |       |                      |                                  |                                |                                      |  |                       | OS   |
|                |             |       |       |           |       |                      |                                  |                                |                                      |  |                       |      |
| KC-135A        | 10          |       |       | 3.180     | 0.510 | 8.28                 | 92.8                             | 98.8                           | 52.6                                 | 58.6                                   | -6.0                  |      |
|                |             | 23    |       | 3.81      | 1.32  | 17.01                | 92.7                             | 86.2                           | 59.2                                 | 62.5                                   | -3.3                  |      |
|                |             | 31-35 |       | 8.602     | 1.35  | 22.1                 | 92.7                             | 98.3                           |                                      |  |                       |      |
|                |             |       | 23    | 2.54      | 0.44  | 6.94                 | 79.8                             | 63.0                           | 43.8                                 | 55.4                                   | -11.5                 |      |
|                |             |       | 31-35 | 5.7       | 0.9   | 14.7                 | 79.8                             | 93.1                           |                                      |  |                       |      |
|                |             |       |       | 2         | 2.461 | 0.36                 | 6.06                             | 106.8                          | 105.0                                | 65.9                                   | 64.6                  | -1.3 |
| B52G           |             |       |       | 3         | 0.41  | 1.08                 | 106.8                            | 107.4                          |                                      |  |                       |      |
|                | 10          |       |       | 2.910     | 0.960 | 12.51                | 96.2                             | 102.9                          | 57.8                                 | 64.5                                   | -6.7                  |      |
|                |             | 22    |       | 2.07      | 1.23  | 14.4                 | 97.2                             | 91.1                           | 64.4                                 | 68.7                                   | -4.3                  |      |
|                |             | 31-35 |       | 7.68      | 2.37  | 31.4                 | 97.2                             | 103.0                          |                                      |  |                       |      |
|                |             |       | 22    | 1.38      | 0.820 | 9.6                  | 92.8                             | -                              | 58.2                                 | 52.2                                   | +6                    |      |
|                |             |       | 31-35 | 5.1       | 1.58  | 20.9                 | 92.8                             | 88.4                           | 68.8                                 | 65.6                                   | +3.2                  |      |
| DNL Total      |             |       |       |           |       |                      |                                  |                                |                                      |  |                       |      |
| 72.2           |             |       |       |           |       |                      |                                  |                                |                                      |  |                       |      |
| 73.0           |             |       |       |           |       |                      |                                  |                                |                                      |  |                       |      |
| 75.8           |             |       |       |           |       |                      |                                  |                                |                                      |  |                       |      |
| NOISEMAP (REF) |             |       |       |           |       |                      |                                  |                                |                                      |  |                       |      |
| 75.8           |             |       |       |           |       |                      |                                  |                                |                                      |  |                       |      |

\*N = Freq.(day)+10xFreq.(night)      \*\*DNL = SEL+10logN-49.4

TABLE A-32 SYNTHESIS OF SITE DNL VALUES FROM  
MEASURED AND NOISEMAP SEL VALUES

SITE 203

| Type<br>A/C    | Mission No. |       |       | Frequency |       |                      | SEL, dB                          |                                |                                      | DNL, dB                                |                       |      |
|----------------|-------------|-------|-------|-----------|-------|----------------------|----------------------------------|--------------------------------|--------------------------------------|--|-----------------------|------|
|                | App         | T/O   |       | Day       | Night | Equiv.<br>Day,<br>N* | Measured<br>Values<br>(Table 20) | NOISEMAP<br>Values<br>(Fig. 8) | Derived<br>from<br>Measured<br>SEL's | Derived<br>from<br>NOISEMAP<br>SEL's** | Meas.<br>Pred.<br>(-) |      |
|                |             | SI    | Patn  |           |       |                      |                                  |                                |                                      |  |                       | SO   |
|                |             |       |       |           |       |                      |                                  |                                |                                      |  |                       |      |
| KC-135A        | 10          |       |       | 3.180     | 0.510 | 8.28                 | 98.3                             | 98.6                           | 58.1                                 | 58.4                                   | -3.3                  |      |
|                |             | 23    |       | 3.81      | 1.32  | 17.01                | 97.7                             | 64.0                           | 64.2                                 | 62.9                                   | 1.3                   |      |
|                |             | 31-35 |       | 8.602     | 1.35  | 22.1                 | 97.7                             | 98.9                           |                                      |  |                       |      |
|                |             |       | 23    | 2.54      | 0.44  | 6.94                 | -                                | -                              |                                      | 44.2                                   | -                     |      |
|                |             |       | 31-35 | 5.7       | 0.9   | 14.7                 | -                                | 81.9                           |                                      |  |                       |      |
|                |             |       |       | 2         | 2.461 | 0.36                 | 6.06                             | 100.4                          | 102.5                                | 59.5                                   | 62.6                  | -3.1 |
| B52G           |             |       |       | 3         | 0.41  | 0.067                | 1.08                             | 100.4                          | 106.9                                |  |                       |      |
|                | 10          |       |       | 2.910     | 0.960 | 12.51                | 102.7                            | 103.2                          | 64.3                                 | 64.8                                   | -5.5                  |      |
|                |             | 22    |       | 2.07      | 1.23  | 14.4                 | 102.9                            | 68.0                           | 70.1                                 | 68.6                                   | 1.5                   |      |
|                |             | 31-35 |       | 7.68      | 2.37  | 31.4                 | 102.9                            | 103.0                          |                                      |  |                       |      |
|                |             |       | 22    | 1.38      | 0.820 | 9.6                  | 93.5                             | -                              | 58.9                                 | 28.8                                   | -                     |      |
|                |             |       | 31-35 | 5.1       | 1.58  | 20.9                 | 93.5                             | 65.0                           |                                      |  |                       |      |
|                |             |       |       | 1         | 2.436 | 0.225                | 4.686                            | 104.7                          | 106.9                                | 62.0                                   | 64.2                  | -2.2 |
| DNL Total      |             |       |       |           |       |                      |                                  |                                | 72.9                                 | 72.4                                   | .5                    |      |
| NOISEMAP (REF) |             |       |       |           |       |                      |                                  |                                | 73.7                                 | 73.7                                   |                       |      |

\*N = Freq.(day)+10xFreq.(night)      \*\*DNL = SEL+10logN-49.4

#### REFERENCES

1. Horonjeff, R. D., Kandukuri, R. R., Reddingius, N. H., "Community Noise Exposure Resulting from Aircraft Operations: Computer Program Description", Air Force Report AMRL TR-73-109, 1974. [AD A004821]
2. Rentz, Peter E., "NOISECHECK Procedures; Planning, Conducting and Analyzing Data from Noise Level Field Measurement Programs, BBN Report \_\_\_\_\_, November 1978.
3. Comprehensive Planning Organization of the San Diego Region (CPO) "Aircraft Noise Contours: NAS Miramar", January 1977.
4. Seidman, H., Horonjeff, R. D., Bishop, D. E., "Validation of Aircraft Noise Exposure Prediction Procedure", AMRL TR-76-111, 1976. [AD A041674]
5. Bolt Beranek and Newman Inc. Report 2225, "Noise from Aircraft Operations, U. S. Naval Air Station, Lemoore, California", August 1972.
6. Bolt Beranek and Newman Inc. Report 2425, "Noise from Aircraft Operations, U. S. Naval Air Station, Fallon, Nevada", submitted to United States Navy Western Division Naval Facilities Engineering Command, San Bruno, California 94066, March 1973.
7. Bolt Beranek and Newman Inc. Report 1952, "Noise from Aircraft Operations, Marine Corps Air Stations, El Toro, Santa Ana and Half Mile Square, California", submitted to: United States Navy, Commander Naval Facilities Engineering Command S. W., 1220 Pacific Highway, San Diego, California 92132, July 1970.
8. Bolt Beranek and Newman Inc. unpublished delta-SEL data, El Toro Marine Corps Air Station, 1977.
9. Bolt Beranek and Newman Inc., Report 1965 "Noise from Aircraft Operations, March Air Force Base, Riverside, California", submitted to: United States Navy, Commander, Naval Facilities Engineering Command S. W., 1220 Pacific Highway, San Diego, California 92132, November 1970.

10. Bolt Beranek and Newman Inc., Report 2223, "Noise Exposure Forecast for Aircraft Departures from Runways 6L and 6R at Anchorage International Airport", submitted to: State of Alaska, Division of Aviation, Department of Public Works, 4510 International Airport Road, Anchorage, Alaska, 99502, July 1972.
11. Bolt Beranek and Newman Inc. Report 3569, "Noise From Aircraft Operations at Stockton Metropolitan Airport", submitted to R. Dixon Speas Associates, Inc., October 1977.
12. Bolt Beranek and Newman Inc. unpublished data, San Diego International Airport, 1977.
13. Mills, J. F., and Bishop, D. E., "Quarterly Noise Monitoring at Hollywood-Burbank Airport, July-September 1977" prepared for: Lockheed Air Terminal, Inc., Burbank, California 91505. BBN Report 3691, 30 November 1977.
14. Mills, J. F., "Noise from Aircraft Operations at Woodrum Field Roanoke, Virginia", submitted to: Ralph Burke Associates, 1550 Northwest Highway, Suite 400, Park Ridge, Illinois 60068, BBN Report 3704, April 1978.
15. MIL-STD-882, System Safety Program for Systems and Associated Subsystems and Equipment: Requirements for, 15 July 1969.
16. Bishop, D. E., Dunderdale, T. C., Horonjeff, R. D., Mills, J. F., "Further Sensitivity Studies of Community-Aircraft Noise Exposure (NOISEMAP) Prediction Procedure", AMRL-TR-76-116, 1977. [AD AO41781]
17. Bishop, D. E., Dunderdale, T. C., Horonjeff, R. D., Mills, J. F., "Sensitivity Studies of Community Aircraft Noise Exposure (NOISEMAP) Prediction Procedure", AMRL-TR-75-115, March 1976. [AD AO26535]
18. Speakman, J. D., Powell, R. G., Cole, J. N., "Community Noise Exposure Resulting From Aircraft Operations: Volume 1 Acoustic Data on Military Aircraft; AMRL-TR-73-110, November 1977. [AD AO53699]

19. Speakman, J. D., Powell, R. G., Lee, R. A., "Community Noise Exposure Resulting From Aircraft Operations: Volume 2 Acoustic Data on Air Force Bomber/Cargo Aircraft", AMRL-TR-73-110, November 1977. [AD A053700]
20. Speakman, J. D., Powell, R. G., Lee, R. A., "Community Noise Exposure Resulting From Aircraft Operations: Volume 3 Acoustic Data on Air Force Attack/Fighter Aircraft", AMRL-TR-73-110, February 1978. [AD A053701]
21. Speakman, J. D., Powell, R. G., Lee, R. A., "Community Noise Exposure Resulting From Aircraft Operations: Volume 4 Acoustic Data on Air Force Trainer/Fighter Aircraft", AMRL-TR-73-110, February 1978. [AD A053702]
22. Speakman, J. D., Powell, R. G., Lee, R. A., "Community Noise Exposure Resulting From Aircraft Operations: Volume 5 Acoustic Data on Air Force Propeller Aircraft", AMRL-TR-73-110, February 1978. [AD A053709]
23. Speakman, J. D., Powell, R. G., Lee, R. A., "Community Noise Exposure Resulting From Aircraft Operations: Volume 6 Acoustic Data on Navy Aircraft", AMRL-TR-73-110, February 1978. [AD A056217]